

ACKNOWLEDGMENTS

Sponsoring Agency:



Kansas Department of Transportation Dwight D. Eisenhower State Office Building 700 S.W. Harrison Street Topeka, KS 66603

Partner Agencies:



City of Mulvane 211 N. Second Ave. Mulvane, KS 67110



Sumner County 501 N. Washington Wellington, KS 67152



Kansas Turnpike Authority 9401 E. Kellogg Wichita, KS 67207



City of Haysville 200 W. Grand Haysville, KS 67060



Sedgwick County 525 N. Main Wichita KS, 67203



Wichita Area Metropolitan Planning Organization 455 N. Main Wichita, KS 67202

Consultant Team:



Professional Engineering Consultants, P.A. 303 South Topeka Wichita, KS 67202



TranSystems 245 N. Waco, Suite 222 Wichita, KS 67202

V-ZHA, LLC

W-ZHA, LLC 1031 Skidmore Drive Annapolis, MD 21409



TABLE OF CONTENTS

	INTRODUCTION
CHAPTER 2:	PUBLIC INVOLVEMENT
CHAPTER 3:	EXISTING DEVELOPMENT & ENVIRONMENTAL CONDITIONS
CHAPTER 4:	FUTURE AREA DEVELOPMENT
CHAPTER 5:	EXISTING TRANSPORTATION CONDITIONS
	FUTURE TRANSPORTATION CONDITIONS
	TRANSPORTATION RECOMMENDATIONS
	PLAN IMPLEMENTATION
	: LOCAL & REGIONAL PLANS45
	: DEMOGRAPHIC, ECONOMIC & MARKET ANALYSIS47
	: TRAVEL DEMAND MODEL DOCUMENTATION6
APPENDIX 4	: MULVANE ALTERNATIVE ROUTE
ADDENIDIY 5	· ACCESS MANIAGEMENT INFORMATION



LIST OF MAPS, TABLES & EXHIBITS

MAPS		
MAP A: STUDY A	AREA LOCATION MAP	2
MAP B: IMAGES	OF STUDY AREA	9
MAP C: EXISTING	G LAND USE & INFRASTRUCTURE	10
MAP D: WATER F	EATURES, FLOOD ZONES, DEPTH TO WATER TABLE & TOPOGRAPHY	11
MAP E: SOILS		12
MAP F: FUTURE L	AND USE SCENARIO	15
MAP G: WAMPC	REGIONAL PATHWAY SYSTEM PLAN CORRIDORS	24
EXHIBITS		
EXHIBIT 1: US-81	INTERSECTION DIAGRAMS	20
EXHIBIT 2: K-53 I	NTERSECTION DIAGRAMS	21
EXHIBIT 3: CASIN	NO VICINITY INTERSECTION DIAGRAMS	22
EXHIBIT 4: CATP	MODEL NETWORK	23
EXHIBIT 5: MUTC	D BICYCLE SIGNAGE EXAMPLES	26
EXHIBIT 6: CONC	CEPT IMPROVEMENT PLAN (US-81/87TH ST. SOUTH & 95TH ST. SOUTH INTERSECTIONS,)31
EXHIBIT 7: CONC	CEPT IMPROVEMENT PLAN (US-81 MID-MILE BETWEEN 111TH ST. SOUTH & K-53)	32
EXHIBIT 8: CONC	CEPT IMPROVEMENT PLAN (CASINO VICINITY RECOMMENDATIONS)	33
EXHIBIT 9: CONC	CEPT IMPROVEMENT PLAN (US-81/K-55 INTERSECTION)	34
EXHIBIT 10: CON	ICEPT IMPROVEMENT PLAN (K-53/WASHINGTON ST. & WINERY INTERSECTION)	35
EXHIBIT 11: CON	ICEPT IMPROVEMENT PLAN (K-53/KTA CONNECTOR & HYDRAULIC INTERSECTIONS)	36
EXHIBIT A3.1: ST	UDY AREA	65
EXHIBIT A3.2: CA	ATP MODEL NETWORK	66
EXHIBIT A3.3: EX	ISTING DAILY TRAFFIC VOLUMES	67
EXHIBIT A3.4: AM	M PEAK PERIOD VOLUMES	68
EXHIBIT A3.5: PM	1 PEAK PERIOD VOLUMES	69
EXHIBIT A3.6: RC	DADWAY FACILITY TYPE	70
EXHIBIT A3.7: LC	CATION OF CAPACITY ENHANCEMENTS	71
EXHIBIT A3.8: CA	ATP & WAMPO TRAFFIC ANALYSIS ZONES	<i>7</i> 2
EXHIBIT A4.1: PR	OPOSED MULVANE ALTERNATIVE ROUTE	<i>7</i> 3
EXHIBIT A5.1: IN	TERSECTION CONFLICT POINTS	75
EXHIBIT A5.2: RC	DUNDABOUT CONFLICT POINTS	76

TA	B	LES
		LES

TABLE 1: EXISTING LAND USE (2012)	5
TABLE 2: PARK & RECREATION SITES	6
TABLE 3: SCHOOL-RELATED SITES	6
TABLE 4: HISTORIC RESOURCES	6
TABLE 5: WATER FEATURES	7
TABLE 6: HYDROLOGIC UNIT CODES	7
TABLE 7: FARMLAND	7
TABLE 8: SOIL TYPES	7
TABLE 9: PROJECTED RETAIL & NON-RETAIL JOB GROWTH	13
TABLE 10: FUTURE LAND USE	13
TABLE 11: BRIDGES	17
TABLE 12: INTERSECTION LEVEL OF SERVICE THRESHOLDS	18
TABLE 13: INTERSECTION OPERATIONAL ANALYSIS (2012)	18
TABLE 14: US-81 ROUTE CHARACTERISTICS	19
TABLE 15: US-81 INTERSECTION CHARACTERISTICS	19
TABLE 16: K-53 ROUTE CHARACTERISTICS	19
TABLE 17: K-53 INTERSECTION CHARACTERISTICS	19
TABLE 18: INTERSECTION OPERATIONAL ANALYSIS (FUTURE NO BUILD SCENARIO)	23
TABLE 19: INTERSECTION OPERATIONAL ANALYSIS (FUTURE BUILD SCENARIO)	29
TABLE 20: SENSITIVITY ANALYSIS RESULTS	29
TABLE A3.1: MODEL INPUT SUMMARY	64
TABLE A3.2: OBSERVED & MODELED ADT VOLUMES	64
TABLE A5.1: ACCESS MANAGEMENT TECHNIQUES & BENEFITS	75





CHAPTER 1: INTRODUCTION

The Kansas Department of Transportation (KDOT) has partnered with the city of Mulvane, the city of Haysville, Sumner County, Sedgwick County, the Kansas Turnpike Authority (KTA), and the Wichita Area Metropolitan Planning Organization (WAMPO) to develop the US-81/K-53 Casino Area Transportation Plan (CATP). The CATP was developed using an open and involved planning process to assess the transportation impacts of expected development caused the by Kansas Star Casino and surrounding development.

PURPOSE

The purpose of the US-81/K-53 Casino Area Transportation Plan is to identify needed future transportation infrastructure improvements caused by ancillary development driven by the opening of the Kansas Star Casino. The CATP identifies the development potential for the area surrounding the Casino Complex, assesses transportation impacts from the anticipated development, and recommends short-term and long-term improvements to the transportation system. The recommendations include preserving and enhancing the safe, efficient operation of US-81 and K-53 over the next 30 years.

BACKGROUND

The historic development pattern of the Study Area will influence future development potential. The Study Area has historically experienced slow growth due to a mainly rural/agricultural setting, with slow conversion from agriculture to mainly low-density residential. However, the development of the Kansas Star Casino Complex has brought the potential for commercial growth to the Study Area and will likely change how the Study Area develops.

Study Area

The Study Area for the US-81/K-53 Casino Area Transportation Plan exists within Sedgwick County and Sumner County, Kansas and includes a portion of the city of Mulvane. The Study Area includes a six square mile area surrounding the Casino Complex bounded by Seneca St. on the west, Hillside Rd. on the east, 111th St. South on the north, and 140th St. North on the south. The Study Area also includes a small area surrounding the junction of US-81 and K-55. The CATP identifies development potential within these areas and assesses transportation impacts.

The Study Area also includes corridors which have been analyzed for transportation impacts only. The corridors include:

- 3 mile segment of the US-81/Broadway Ave. corridor from 87th St. South to 111th St. South in Sedgwick County
- 1 mile segment of the US-81/Broadway Ave. corridor from 140th St. North to 130th St. North in Sumner County
- 4 mile segment of the K-53 corridor from Hillside Rd. to K-15

The entire Study Area includes a total of 9.05 square miles (5,792 acres) and is shown in **Map A**.

Historic Development of the Study Area

Historical development in the southeastern area of Sedgwick County and the northeastern area of Sumner County has shown slow and steady growth. Urban and suburban type residential growth outward from the cities of Haysville, Mulvane, Derby, and Belle Plain has been the trend in and around the Study Area. The area has seen some conversion of agricultural lands to primarily residential urban and suburban type uses.

The development of the Casino Complex represents unprecedented commercial growth in the Study Area. Due to the massive change in the landscape, the historic development pattern is not expected to continue. Future development will be influenced by market demands from the Casino Complex as well as spin-off developments.

Casino Complex

The Kansas Star Casino is located eight miles south of the southern city limits of Wichita, five miles south of the southern city limits of Haysville, and five miles west of downtown Mulvane. The Casino Complex is located within the city of Mulvane between US-81/Broadway and I-35 and a half of a mile south of K-53 in Sumner County, Kansas. The city of Mulvane annexed the land for the Kansas Star Casino on January 10, 2008. The annexation included 1.375 square miles (880 acres) of land in both Sedgwick County and Sumner County.

The Kansas Star Casino is being developed in two phases to be completed by 2015. Phase One, which opened in December of 2011, was a temporary casino in the Event Center of the Casino Complex. This included 1,350 slot machines, 32 table games, a 50 seat snack bar, and several food and beverage kiosks. The second part of Phase One was to move gaming from the temporary casino in the Event Center to the permanent casino. The permanent casino opened in December of 2012 and includes a 250 seat buffet, a 115 seat steakhouse, a 40 seat food court, and a 150 room hotel. The Event Center was converted from the temporary casino to an actual Event Center, which is a 100,000 square foot, 3,000 seat indoor arena with the ability to hold 4,200 people for certain events.

Phase Two will include an additional 500 slot machines, 10 additional table games, a 5 table poker room, an outdoor 24-acre equestrian center with arenas and stalls, an RV park with 60 spaces, another 150 hotel rooms, and a sports bar. At full build-out, the Kansas Star Casino Complex will include 1,850 slot machines, 42 table games, 300 hotel rooms, 5 restaurants, an indoor Event Center, an outdoor equestrian center, and an RV park. The Casino Complex is expected to have an annual attendance of 2.7 million, 25% of which are expected to be tourists.

PUBLIC & STAKEHOLDER INVOLVEMENT


The involvement of the public and stakeholders was vital during the development of the CATP. From the existing conditions inventory to feedback on recommended improvements, all facets of this Plan were vetted through a project advisory committee. This committee included representatives of all partner agencies, KDOT, as well as interested parties. Along with the committee, a website was created and updated to disseminate information about the Plan and opportunities for input. A facebook page was also available as another online forum for discussion and comments. Local media was also involved through press releases and regular emails.

SUMMARY

The CATP utilized an open and involved planning process with many jurisdictions, agencies, stakeholders, and citizens involved in identifying needed transportation infrastructure improvements caused by the development of the Casino Complex and spin-off development. The historic development pattern of the Study Area, which has been a slow conversion of agricultural land to large-lot residential uses, is not expected to continue on the same course into the future. The Casino Complex represents a large commercial development that will impact the future development potential and travel patterns in the Study Area.



CHAPTER 1: INTRODUCTION



CHAPTER 2: PUBLIC INVOLVEMENT

The Casino Area Transportation Plan was developed through a coordinated and collaborative process that involved many stakeholders. From staff to elected officials to the public, the process utilized many resources representing many different agencies and interests. The process utilized several forms of electronic media to disseminate information and provide a forum for discussion and to obtain feedback.

PURPOSE OF PUBLIC INVOLVEMENT

The public involvement component is critical to the success of any planning initiative. It is not only important for conveying project information to area residents, but for gathering input from the public regarding a project and building an understanding of local issues. Successful public involvement begins with a true commitment to such an interactive communication process.

Some of the main objectives of community involvement are:

- Reassuring people that their opinions are of value to the planning process.
- Learning public perceptions and local knowledge of a project.
- Educating citizens on project alternatives and options.
- Gauging local response to potential alternatives and developing acceptable solutions.
- Identifying changes in public opinion and perceptions.
- Building consensus and local buy-in.

PUBLIC INVOLVEMENT APPROACH

The project's public involvement approach was centered on meaningful public and stakeholder participation. The process needed to identify transportation issues, build consensus, learn local preferences and create solutions to a variety of concerns. Also, choices needed to be provided for how people could share their thoughts. Many individuals are not comfortable speaking freely in a public meeting setting. Relying too heavily on meetings can limit the amount of valid, constructive insight received during the planning process. These needs are best served through a qualitative approach to public involvement.

Emphasis was placed on providing numerous options for providing information and receiving feedback rather than the number of meetings held. Throughout the process, several methods were used to engage stakeholders and area residents in the planning process:

- Integrated public/project advisory committee meetings
- Project outreach
- Targeted stakeholder coordination
- Public agency presentations

PROJECT ADVISORY COMMITTEE

The main role of the project advisory committee was to serve the interests of each partner agency, the broader community and the region in project decision making. This required committee members to be in touch with the values, goals and concerns of those whom they represented and to have some degree of authority and accountability. Therefore, the group was primarily made up of partner agency officials and staff along with other interested stakeholders.



A total of four project advisory committee meetings were held during which the committee provided accurate background information for the Plan. The group also gave input on local needs and expectations while serving as a sounding board for the project team.

The public was invited to attend and participate in project advisory committee meetings rather than conducting separate forums. This integration was done mainly because the Study Area was relatively large with a diverse group of stakeholders. Meetings were advertised on the project website and through the email distribution list, which included members of the local media.

The meetings were held in central locations and advertised broadly, rather than conducting multiple meetings on the same topic in a number of locations. This allowed budgeted funds to be focused on the critical analyses while providing qualitative public involvement.

PROJECT OUTREACH

In addition to the previous points about the qualitative public involvement approach, it is impractical to think everyone can attend every project meeting. Taking these things into account, multiple formats were implemented for exchanging information with Study Area residents. A robust outreach and notification plan was conducted to keep the public well-informed of key findings, recommendations, general project status and upcoming events/meetings. Furthermore, several forums were available to receive questions, comments and other input.

A contact database of interested parties and organizations was maintained for the distribution of meeting notifications. Project information was shared with the local press. This included meeting announcements and status updates. Also, area broadcast media ran at least two stories on the plan. Presentations to advisory boards were aired on local government cable outlets where the programming is made available.

The outreach strategy for online communications provided a means for not only giving information, but receiving input. A project website (8153catp.com) was developed and updated periodically throughout the planning process with pertinent information. The website provided:

- Information and updates about the CATP
- News and press releases about the CATP
- Upcoming events
- A Google map of the Study Area with project content
- Contact information
- Links to the CATP facebook page
- Links to partner agency websites
- Project presentations
- Information about specific improvement recommendations, such as roundabouts

Additionally, the website was developed with an active blog interface. This allowed site visitors to post comments directly to content pages on the website. A facebook page was used to receive feedback, get out the word, post hyperlinks and link to the more substantive content of the project website. This outreach strategy allowed anyone convenient 24/7 access to project information and multiple tools for sharing input.

TARGETED STAKEHOLDER COORDINATION

Throughout the process, coordination took place with key stakeholders to obtain targeted information and feedback. These issue-specific discussions provided for a more comprehensive and detailed look at the Study Area as





CHAPTER 2: PUBLIC INVOLVEMENT

well as potential opportunities and challenges. Targeted coordination took place with the following stakeholders:

- Study Area businesses
- Kansas Star Casino representatives
- Economic development focus group
- Farming community
- WAMPO
- City of Mulvane
- City of Haysville
- City of Derby
- Sedgwick County
- Sumner County
- Wichita-Sedgwick County Metropolitan Area Planning Department
- Kansas Turnpike Authority

FEEDBACK ON DRAFT PLAN

The first draft was posted on the CATP website for public review on June 27, 2013 and presented to the project advisory committee that afternoon. The following is a summary of revisions incorporated into the final draft Plan based on input received during the comment period:

- The document cover page was finalized and added.
- Public Involvement chapter was drafted when engagement activities were substantially complete and added to the document.
- Additional options were provided for several recommended improvement locations where alternative solutions would perform acceptably.
- Planning-level cost estimates were added for each recommended improvement.
- Concept drawings of the recommended improvements were finalized and the Concept Improvement Plan was added to illustrate the recommendations.
- Several aspects of the analyses were revised to clarify meaning.
- Revisions were made to the "Other Recommendations" to provide better guidance regarding the Mulvane Alternative Route project.
- Recommendations for bicycle/pedestrian facilities and public transit services were added to the "Other Recommendations" section.
- Capital improvement programming was added to the Implementation Toolbox.

PUBLIC AGENCY PRESENTATIONS

Each of the partner agencies is a public entity with governing bodies and advisory boards playing decision-making roles. They will oversee much of the local implemention efforts. Keeping them informed is a critical aspect of ensuring project success. The feedback of these key decision makers also helps to refine project recommendations.

Presentations on the final draft CATP were offered to these groups through their representatives on the project advisory committee and several agencies accepted the offer. The project team presented the final draft Plan to the following groups on the indicated dates:

- WAMPO's Transportation Policy Body (July 9, 2013)
- WAMPO's Technical Advisory Committee (July 22, 2013)
- Haysville Planning Commission (July 25, 2013)
- Sumner County Commission (August 13, 2013)
- Belle Plaine City Council (September 5, 2013)

Each presentation included opportunities to ask questions and provide comments. The groups were also encouraged to review the final draft CATP and contact the project team with any additional comments, questions or concerns.



The Study Area includes various land developments, utilities, services, resources, and environmental characteristics. This chapter summarizes the existing land uses and development, utilities and services, historic resources, and environmental conditions. In addition to supplementing development approval, this information offers a preliminary review of National Environmental Protection Act (NEPA) considerations.

EXISTING LAND USE & DEVELOPMENT

The Study Area is mainly rural in nature with the majority (63%) of land being classified for agricultural purposes. However, the Study Area includes other land uses typical of transitional development areas. Historically, the development has occurred due to the proximity of the Study Area to several cities (downtown Mulvane, Haysville, Derby, Belle Plaine, and Wichita), as well as the access provided by the road network. The Casino Complex represents a change in development pattern, which has the potential to change the landscape of land uses in the Study Area.

The Study Area includes land area in and around downtown Mulvane, which contains much of the residential development. This residential area has higher density developments on smaller lots. Another part of the Study Area that has somewhat higher density residential development is the area north of 103rd St. South along US-81. There are residential uses along US-81 north of 103rd St. South as well as just northwest of the junction of US-81 and K-55. There are also residential developments closer to the Casino Complex. Most of these developments include lower density housing on larger lots. Many of the large-lot residential developments are located in Sumner County east of the Casino Complex, and one small development west of the Complex.

The Casino Complex has added a large commercial development to the Study Area, which has changed the existing development pattern from what would be expected from the historical development pattern. Most commercial land uses are outside of the Study Area approximately five miles from the Casino Complex in Haysville north of 79th St. North or Mulvane at K-15. The Study Area contains only small areas of commercial/office land uses, one of which is the Casino Complex. Other areas of commercial/office are just north of the Casino Complex, north of 103rd St. South along US-81, and near K-53 and Rock Rd. in downtown Mulvane. There are some manufacturing/industrial land uses and very small tracts of warehouse/distribution uses within the Study Area east of the Casino Complex along K-53 east of Oliver Rd. In total, 5.4% of the Study Area is dedicated to commercial, industrial, and warehousing.

Government and Institutional uses are located in downtown Mulvane at the far eastern reaches of the Study Area and include school district offices, a middle school, Cowley College, the Mulvane Emergency Services building, places of worship, a nursing facility, and Mulvane City Hall.

There are a few park/recreation land uses in the Study Area. There is the Polo Ranch (Great Plains Equestrian Sports) on US-81 north of 95th St. South. There are also four parks, a rodeo arena, and the Cobb Family Historic Park alona K-53 near downtown Mulvane.

Shown in **Table 1** is the land area for each major land use category as well as the percent of the total land area in each land use category within the Study Area. Map B shows images of development at major intersections and developments within the Study Area. **Map C** shows the existing land use within and surrounding the Study Area.

Table 1: Existing Land Use (2012)

Existing Land Use (2012)	Acres	Sq. Miles	% of Study Area
Agricultural	3,650	5.70	63.0%
Residential	840	1.31	14.5%
Commercial/Office	260	0.41	4.5%
Manufacturing/Industrial	38	0.06	0.7%
Warehouse/Distribution	12	0.02	0.2%
Government/Institution	66	0.10	1.1%
Park/Recreation	48	0.07	0.8%
Open Space/Vacant	217	0.34	3.7%
Utility Infrastructure	71	0.11	1.2%
Right-of-Way	590	0.92	10.2%
TOTAL	5 792	9.05	100%

EXISTING UTILITIES & SERVICES

Utilities and services provide many existing developments within the Study Area with water, sewer, electricity, and natural gas. The extents and capacities of these systems will impact where development can occur and the intensity of development. These services most likely can be extended and capacities can be increased, but it will come with a cost.

Potable Water

Mulvane receives potable water through a contract with Augusta, Kansas to receive up to 200 million gallons per year. The current water tower is located at 111th St. and Rock Rd., which is 120 feet tall. To enable sufficient potable water for Mulvane citizens in the future may require alternative sources and increasing the size of pipes.

There are currently two existing water lines under the Arkansas River to serve the area west of the Arkansas River. A new water tower will be constructed at the northeast corner of K-53 and Oliver Rd. as well as a new water treatment facility to treat Mulvane's well water. Other improvements to the water system are recommended to improve water quality and future capacity. The new improvements may open up the area west of the Arkansas River for more development with potable water being available.

Besides for the Study Area within Mulvane, there are no water providers, such as rural water districts, in the Study Area. The closest water providers are the city of Haysville north of 87th Street North, Sedgwick County Rural Water District 3 east of Mulvane, and Sumner County Rural Water District west of Meridian. If developments are unable to receive water from Mulvane or possibly Haysville on the northern portion of the Study Area along US-81, they must be able to access water via private well.

Sanitary Sewer

The wastewater treatment plant for Mulvane is located southwest of Mulvane near the Arkansas River. It has a maximum daily flow of 0.63 million gallons per day, which has the population equivalent of 10,000 people. This is more than sufficient to handle expected growth of the city of Mulvane based on the Comprehensive Plan. However, there are some issues that are identified in the capacity of the sanitary sewer collection system. Mulvane and the Kansas Star Casino agreed to sewer line modifications to include 10 inch and 6 inch pressure force main lines to be extended along the south side of K-53 to the Casino Complex. These improvements will likely allow connections of future developments west of the Arkansas River. Other improvements are likely necessary to the sewer system as development occurs.

Electric

Mulvane distributes electricity to customers throughout the city via overhead and underground distribution lines. All power obtained from outside sources is delivered through a single interconnection with the Southwest Power Pool connected to the Westar El Paso substation. Mulvane also receives power from Nearman Generation Station Unit 1, the Southwestern Power Administration, and Westar. Mulvane also generates electricity at two city owned and operated power plants. In 2011, Mulvane began negotiating a contract with Westar to provide electricity to the Casino Complex. Future electric service for the Study Area, especially west of the Arkansas River, will need to be updated. Other improvements or extensions of the electric power system will likely be necessary as the Study Area develops. It is assumed that electricity will be made available to areas surrounding the Casino Complex to allow for future development.

Gas

Kansas Gas Service supplies natural gas to the Casino Complex from a main located at the northwest corner of US-81 and 140th St. North. Future extensions of service and connections will likely be necessary as development continues.

Public Safety

The Mulvane Public Safety building is located at 910 East Main St., seven road miles from the Casino Site, as shown on Map C. The Emergency Services building houses two of the three branches of the Mulvane Public Safety

Department; fire rescue and emergency medical services (EMS). The third branch is the police department, which is housed at 211 North Second St.

Mulvane police officers cover incorporated Mulvane and occasionally assist in unincorporated Sedgwick and Sumner Counties. Response time for police officers to reach the Casino Site is estimated to be seven minutes from the Emergency Services building.

Mulvane fire rescue covers incorporated Mulvane and also respond to fires on the Kansas Turnpike from milepost 33 to 26. Mulvane fire also covers a rural area known as Sumner County Fire District #12 to the east and south of Mulvane.

Mulvane Emergency Medical Service (EMS) covers incorporated Mulvane and an area along K-53 from Mulvane extending west to Ridge Rd. south to 126th St., east to the Arkansas River. They also cover a corridor on the Kansas Turnpike from US-53 to 70th Ave. North. Of the calls outside Mulvane, most were to Sumner County. Based on judgment of the Captain, 25-30% of EMS calls are from west of the railroad tracks. Drive time from the Public Safety Building to the Casino Site is about 11 minutes.

Increases in police call volumes from the Casino Complex should be marginal. Fire rescue calls are likely to increase on the portion of the Kansas Turnpike based on increased vehicular travel due to the Casino Complex. EMS calls from the Casino should not dictate any additional EMS staffing. However, it appears reasonable to acquire an extra ambulance to handle standby duties at the events held at the Casino. These conclusions are based on the Casino Site itself and not additional development that may occur. These developments may pose additional demand on public safety departments.

Of major concern to all departments is the delay in response time caused by train traffic. A new west substation would not eliminate train traffic conflicts for the volunteer fire department since volunteers still need to travel over railroad tracks to get to the substation.

As part of the Casino Development, a future EMS facility will be located at the Casino Complex along US-81. Also, an automatic aid agreement has also been approved with Sedgwick County Fire District No. 1, which includes the Kansas Star Casino Site.

Recreation

The Study Area contains six locations within the Study Area designated for recreational purposes. These include public parks and other recreation areas. **Table 2** identifies the park/recreation sites and locations and **Map C** shows the locations.

Table 2: Park & Recreation Sites

Name	Location
Polo Grounds	East side of US-81 between 87th St. S. and 95th St. S.
Rodeo Arena	West of BNSF and north of K-53
Cobb Family Historical Park	North of Main St. near Santa Fe Depot
Fairchild Park	Northeast of Blair St. and Swan Drive
Styx Creek West Park	Franklin St. and 4th Ave. N.
Main Street Park 1	Main St. and 4th Ave. N.

Schools

The Study Area is within Unified School Districts (USD) 263, 357, and small portions of 260 and 261. There are four school-related sites within the Study Area, which are shown in **Table 3** and **Map C**.

Table 3: School-Related Sites

Name	Location
Mulvane Grade School	411 S.E. Louis Drive
Mulvane District Office and Special Education	628 E. Mulvane St.
Cowley College	430 E. Main St.
Cowley College	201 Industrial Drive

HISTORIC RESOURCES

There are historical resources and landmarks within the Study Area. These resources are important to identify prior to development because projects within environs of historic resources require consideration of impacts on the resources. K.S.A. 75-2724: historic preservation officer be notified and given opportunity to comment upon any project which will "encroach upon, damage or destroy any historic property." Similar provisions apply if a proposed project is within 500 feet of a historic structure within a city or within 1,000 feet if located in an unincorporated area (for listings on National Register of Historic Places).

There are seven historically significant sites within the Study Area that are identified on the Kansas Historic Resources Inventory. None of these sites, however, are listed on the state or national register of historic places. <u>Table 4</u> and **Map C** identify the historic resources and their location.

Table 4: Historic Resources

Name	Location	
Lenny C. Helbert House	322 N. 2nd St.	
H.M. Maguire House	511 S. 4th St.	
Mulvane State Bank	203 W. Main St.	
H.L. Pegram House	202 W. Blair St.	
Mulvane Santa Fe Depot	300 W. Main St.	
Phillips 66 Service Station	211 S. 1st St.	
Mulvane Old High School Gym	628 E. Mulvane St.	

EXISTING ENVIRONMENTAL CONDITIONS

The natural environment of the Study Area, such as topography and wildlife, sets the stage for human development. Prior to assessing the development potential for the Study Area, the characteristics of the natural environment must first be inventoried. The inventory allows the assessment of how the natural environment will impact development potential, specifically in regards to potential locations of development. The inventory is also used when developing and assessing future transportation investment options.

Climate

The climate of the Study Area has wide temperature variations, abundant spring rainfall, high winds, and mainly clear skies. The Study Area is subject to abrupt weather changes. Annual average minimum and maximum temperatures are 45-46 degrees Fahrenheit and 68 degrees Fahrenheit respectively (based on data from DASC sourced from USDA/NRCS). Annual average precipitation from 1981-2010 has been between 34 and 35 inches per year (based on data from DASC sourced from Oregon State University and the Oregon Climate Service at Oregon State University).

Topography

The topography of the Study Area is relatively flat, ranging from 1,210 to 1,296 feet above sea level. The highest point is located in Mulvane near K-15. The lowest point is located at the Arkansas River just south of K-53. **Map D** shows the topography of the Study Area.

Water, Wetlands & Flood Zones

Lakes, rivers, streams, wetlands, and subsurface water all exist in the Study Area. The primary water features are the Arkansas River, the Cowskin Creek, and the Ninnescah River. There are also riverine areas surrounding the rivers and creeks, a few small lakes and ponds near the Arkansas River, and small areas of wetlands near the Arkansas River and Cowskin Creek. These areas represent undevelopable areas and often act as barriers to development. **Table 5** shows the types of water features and the area covered by each water feature type. **Map D** shows the location of water features within the Study Area. The wetland features are from National Wetland Inventory data and have not been formally delineated for this project. The location of features is



being shown to identify areas likely to contain wetlands or water features and will need particular consideration. Jurisdictional determinations for wetlands and waterways will be made as needed at the time of permitting.

Table 5: Water Features

Water Feature	Acres	Sq. Miles	% of Study Area
Lake	25	0.04	0.4%
Riverine	38	0.06	0.7%
Pond	7	0.01	0.1%
Emergent Wetland	1	0.00	0.0%
Forested/Shrub Wetland	30	0.05	0.5%
Other	0	0.00	0.0%
TOTAL	101	0.16	1.7%

There is a large area within the Study Area that is designated by the Federal Emergency Management Agency (FEMA) as 100-year flood zone. The area near the Arkansas River and the Cowskin Creek make up the majority of the flood zone. The area surrounding the US-81 and K-55 junction is entirely within the 100-year flood zone. The flood zones limit the development potential within the Study Area. For cases where construction occurs in the floodway, detailed analysis demonstrating the impacts of proposed construction will be required. **Map D** shows the 100-year flood zone within the Study Area.

Ground water can impact specific site development potential, especially where it is very close to the surface. The average depth to the water table is 20 feet or less from the surface in most of the Study Area. In many areas, it is much less. During particularly wet times, the water table can be around five feet from the surface. The draft Sedgwick County Quad Cities Joint Area Plan indicated that high groundwater in the area was a concern. **Map D** shows the average depth to the water table for areas in the Study Area.

Consideration of water features and wetlands is necessary in future development, especially when under the jurisdiction of the U.S. Army Corp of Engineers (USACE). Avoiding development in these areas is the preferred approach when development occurs. However, this approach is not always feasible and practical. Section 404 permits are required when placing fill in any water features or wetlands under the jurisdiction of the USACE. Construction or modification of bridges or culverts, or changes to the cross section of streams will require Stream Obstructions or Channel Changes permits from the Kansas Department of Agriculture, Division of Water Resources.

Watersheds

Watersheds are areas that drain to a common waterway, such as a lake, river, stream, drainage way, wetland, or aquifer. Watersheds function to direct storm water to a drainage way or water feature. The Study Area includes two watersheds; one drains to the Arkansas River and the other drains to the

Ninnescah River. Storm water runoff and drainage are major concerns within the Study Area and can impact development within the area. The Hydrologic Unit Codes and names for the watersheds are included in <u>Table 6</u> and the HUC 12 boundaries are shown in <u>Map D</u>.

Table 6: Hydrologic Unit Codes

HUC 8		HUC 10		HUC 12	
Name	#	# Name #		Name	#
Middle	11030013	Mill Race Canal	1103001303	Spring Creek	110300130301
Arkansas-				Cowskin Creek Cutoff	110300130302
				Dog Creek	110300130303
Slate				Outlet Cowskin Creek	110300130304
	n 11030016 Spring Creek	Spring	1103001602	Wattles Lake	110300160201
Ninnescah				Elm Creek	110300160202
		Creek		Dry Creek	110300160203

Farmlands

The Study Area includes soils that are designated as prime farmland and farmlands of statewide importance. Prime farmlands have the best characteristics for efficient agricultural productivity. Farmlands of statewide importance, which are designated by the states, are slightly less suited for agricultural production than prime farmlands. However, they may still produce high yields using acceptable farming practices.

The Study Area includes 5,436 acres of prime farmland located throughout the Study Area. The area surrounding the US-81 and K-55 junction includes a small area of prime farmland on the northern and northeastern border. The Study Area also includes about 30 acres of farmlands of statewide importance. Two small pockets of these farmlands are located on the far north of the Study Area near 87th St. South just west of US-81 and north of 119th St. South. **Table 7** shows the types of farmland, the acres per farmland type, and the percent of the Study Area each farmland type covers. **Map E** shows the designated prime farmland and the farmland of statewide importance within the Study Area.

Developing or constructing in prime farmland or farmland of statewide importance can impact the potential agricultural productivity. However, the Study Area is likely to incorporate much more non-agricultural uses that can increase economic productivity.

Table 7: Farmland

Farmland	Acres	Sq. Miles	% of Study Area
Prime Farmland	5,436	8.49	93.9%
Farmland of Statewide Importance	30	0.05	0.5%
Not Designated	326	0.51	5.6%
TOTAL	5,792	9.05	100%

Soils

There are 12 NRCS major soil texture types found in the Study Area. Soil types affect many aspects of the Study Area, from drainage and vegetation to the suitability of constructing buildings, bridges, and roads. <u>Table 8</u> shows the soil types, the acres per soil type, and the percent of the Study Area each soil type covers. <u>Map E</u> shows the soil types within the Study Area.

Table 8: Soil Types

Soil Type	Acres	Sq. Miles	% of Study Area
Sandy Loams	1628	2.54	28.1%
Clays	1204	1.88	20.8%
Sandy Clay Loams	810	1.27	14.0%
Clay Loams	511	0.80	8.8%
Loams	470	0.73	8.1%
Silt Loams	387	0.61	6.7%
Sands	344	0.54	5.9%
Silty Clays	280	0.44	4.8%
Water/Aquolls	73	0.11	1.3%
Silty Clay Loams	64	0.10	1.1%
Pits/Quarries	16	0.02	0.3%
Loamy Sands	6	0.01	0.1%
TOTAL	5,792	9.05	100%

The ten most prevalent specific soil types in the Study Area are:

- Canadian sandy loams (20.6%)
- Farnum sandy clay laoms (14.0%)
- Complex/Undifferentiated soils (13.4%)
- Blanket clays (7.9%)
- Nalim loams (7.6%)
- Waurika clays (6.8%)
- Farnum sandy loams (6.2%)
- Tabler clays (5.9%)
- Brewer silty clays (4.8%)
- Lesho clay loams (4.7%)



These soil types have somewhat limited to very limited characteristics for dwellings and small commercial buildings, somewhat to very limited for local roads and streets, and most are somewhat to very limited for septic tank absorption fields and sewage lagoons (Tabler has no limitations on sewage lagoons). These soil-type limitations for construction and development can be mediated during development, but typically come at a higher cost for development and long-term maintenance.

Wildlife, Vegetation & Habitat

The Kansas Comprehensive Wildlife Conservation (KCWC) Plan of 2005 identifies that the Study Area is in the Central Mixed Grass Prairie Conservation Region. Some of the prevalent wildlife habitats in the Study Area are Herbaceous Wetland, Aquatic, Deciduous Floodplain, Cropland, Riparian Shrubland, and Urban Areas. Listings of wildlife and vegetation commonly inhabiting these habitats can be found in the KCWC Plan.

Loss, conversion, or fragmentation of habitat is likely to happen with development. However, southern Sedgwick County and northern Sumner County offer similar habitats for wildlife and vegetation. The loss of small areas of habitat due to development will likely have minimal impact on wildlife and vegetation. Wildlife accustomed to human-altered environments should continue to thrive. Transportation projects that would greatly fragment habitat should consider incorporating best practices for wildlife crossings or motorist warnings.

Threatened & Endangered Species

The Study Area likely contains habitat of threatened and endangered species. The Federal Endangered Species Act and the Kansas Nongame and Endangered Species Conservation Act protect habitats of the identified endangered and/or threatened species. The US Fish and Wildlife Service and the Kansas Department of Wildlife, Parks, and Tourism compile a list of threatened and endangered species and identify areas where they are, or have been found.

Areas known to have current self-sustaining populations of these species are called Designated Critical Habitat (DCH). There are a few species that have DCH in the Study Area. There are also species that are historically known to live in the Study Area, but may not have been seen there recently. There are 14 of species that have DCH or have known historic ranges in Sedgwick and/or Sumner Counties. Developments and transportation projects that will impact listed species or their known habitat require coordination with federal and state agencies and require appropriate measures to avoid or mitigate negative impacts.

Air Quality

The Study Area falls within the Wichita Metropolitan Statistical Area (MSA). The MSA is monitored by the Environmental Protection Agency and the Kansas Department of Health and Environment for six criteria pollutants. Currently, the MSA is in attainment, meaning the area does not violate federal standards for air pollution. However, the region is close to violating the standard for ground level ozone, which would likely cause the area to be designated as a non-attainment area. The non-attainment designation may affect the development potential, the types of development that occur, how development occurs, and the transportation improvements that can be made within the Study Area.

SUMMARY


The existing land use and development show a primarily agricultural area with some residential areas distributed throughout the Study Area. There are few commercial, industrial, or manufacturing uses within the Study Area. The Casino Complex has changed the landscape, but has not yet spurred much development beyond the complex. However, spin-off development is expected to occur and will likely entail the conversion of agricultural uses to commercial development.


The existing utilities and services have been or will be improved to provide the Casino Complex with needed utilities and services. Much of the improvements include expanding capacity to the west side of the Arkansas River. Future expansion of the water, wastewater, and electric system will likely need to be expanded as growth continues on the west side of the Arkansas River.


There are natural environmental elements and historic resources in the Study Area that may affect how the Study Area will develop. These elements will impact and potentially hinder development in some areas. They may also require mitigation of impacts on environmental elements. The elements will also impact how transportation improvements are made within the Study Area. Certain processes must be followed within the environs of these environmental and historic resources.











The Kansas Star Casino development has spurred discussions about the potential growth in and around the Study Area and how the new growth will impact the transportation system. Analyzing future development and its impacts on the transportation system will aid in identifying needed transportation improvements in the Study Area.

DEVELOPMENT ANALYSIS

Prior to the development of the Casino Complex, the Study Area was mainly agricultural with some residential areas. The Casino Complex is expected to directly cause much of the increase in demand for residential and commercial uses. In addition, spin-off development caused by the Casino Complex is projected to increase demand for commercial and light industrial development and slightly increase the demand for residential development.

A separate study was developed for the CATP to analyze the future demand for certain types of development caused by the Casino Complex, including the attached Equine Center. The CATP used the data and conclusions of the Demographic, Economic, and Market Analysis (see **Appendix 2**) to determine the type and degree of development likely to occur and how it would impact the transportation system. It should be noted that during the planning process casino management expanded the use of the equine auditorium space to include concerts. Concert attendance should not differ significantly from the anticipated use. However, the analyses were completed before the decision was made. Differences in target audience, peak travel demand, ingress/egress patterns, etc. were unable to be factored into the study.

Population & Housing

The Casino market area added 653 residents from 1990 to 2010, showing an annual growth rate of 0.78%. Population within the market area is expected to increase, which will increase the demand for housing units. However, the Casino Complex and spin-off development is not expected to dramatically change residential market forces. The Casino Complex is projected to increase the total number of housing units in the market area from 1,710 in 2012 to 1,952 in 2040, showing an increase of 242 new housing units. Spin-off development will generate demand for an additional 20-27 households. Combining housing demand from the Casino Complex and spin-off development, the market area is projected to add 262 to 269 new households.

Commercial & Light Industrial

Based on literature and comparable locations, the Kansas Star Casino is not expected to spin-off significant land use development outside the Casino Complex. Uses that typically follow casino development are designed to intercept the casino patron traffic, such as gasoline service stations, fast food restaurants, convenience stores, and limited service hotels. The Casino

Complex has the potential to spur other developments based on the inclusion of the Equine Center. The Equine Center would act similar to other family-oriented activities at other casino complexes and could spur the demand for family-style restaurants and some retail development.

The market area is not a natural location for retail development since there is not a concentration of households and significant residential growth is not projected. However, the Casino Complex and I-35 provide the market area with the potential for growth in retail development based on increased traffic. Interchange-style retail developments, such as truck stops, are most likely over the next 30 years with a limited amount of service retail. The retail development is likely to occur along US-81 north of the Casino Complex.

Hotels typically locate near sales and traffic generators such as interchange locations, business centers, or a major traffic generator similar to the Casino Complex. The current 150-room hotel at the Casino Complex, as well as another 150 rooms planned, will nearly meet the anticipated demand for hotel rooms from the Casino Complex. By 2040, there is the potential demand for a 65 to 90-room limited service hotel in the market area targeted to Interstate traffic and the Casino Complex's activities, especially the Equine Center.

Light industrial development is likely to occur on US-81 north of the Casino Complex due to increased traffic from the Casino. Land here is relatively inexpensive but lacks utilities south of 79th St. North. However, given the market visibility on US-81, the market will likely support a light industrial development totaling 20,000 to 40,000 square feet supporting 20 to 40 employees.

Jobs

The number of jobs at the Casino Complex is expected to increase from 601 in 2012 to 870 in 2040. The number of jobs is also expected to grow for the entire market area. The Casino Complex is projected to increase the total number of jobs in the market area from 820 in 2012 to 1137 in 2040, showing an increase of 317 new jobs. Spin-off development spurred by the Casino Complex will generate demand for an additional 150 to 213 jobs. Combining Casino Complex and spin-off demand, the market area is projected to add 467 to 530 new jobs by 2040. **Table 9** shows the total jobs in 2012 within the market area and the projected number of jobs by 2040. The new jobs are expected to be at the Casino Complex with some of the new jobs in the Sedgwick County portion of the market area.

Table 9: Projected Retail & Non-Retail Job Growth

Job Type	2012	2040		
Retail	61	277	-	312
Non-Retail	759	1010	-	1038
Total	820	1287	-	1350

For the purposes of this Study, the market demand for development was assumed to be all within the Study Area. This essentially places all of the demand of the market area within the smaller Study Area. The type and degree of development identified by the development analysis was distributed into a future land use pattern set forth by other planning efforts that included the Study Area.

FUTURE LAND USE SCENARIO

The future land use scenario for the Study Area was based on other planning efforts, such as comprehensive and subarea plans. These plans provided the location of future land uses, with minor modifications based on the development analysis. The types of development, population, and number retail and non-retail jobs were distributed into the future land use scenario, which were then input into a travel demand model for traffic analysis (see **Chapter 6**). The future land uses are shown in **Table 10** and **Map F**.

Table 10: Future Land Use

Land Use	Acres	Sq. Miles	% of Land Area
Agriculture	2900	4.53	50.1%
Residential	1038	1.62	17.9%
Commercial/Office	787	1.23	13.6%
Manufacturing/Industrial	124	0.19	2.1%
Warehouse/Distribution	1	0.00	0.0%
Government/Institution	66	0.10	1.1%
Park/Recreation	50	0.08	0.9%
Open Space/Vacant	153	0.24	2.6%
Utility/Infrastructure	86	0.13	1.5%
Right-of-Way	587	0.92	10.1%
TOTAL	5792	9.05	100%

The areas surrounding the Casino Complex, the junction of US-81 and K-53, and the junction of I-35 and K-53 are the most likely to develop commercial uses. The roadway network provides excellent access to these areas and commercial development would capitalize on the increased traffic generated by the Casino and Equine Center activities.

The areas shown to be developed in the future land use scenario offer a general idea of the location of different types of development. These locations are well suited for development due to the draw of Casino Complex and the access provided by the roads. However, there are existing conditions that my pose challenges for development in these areas.

The areas of commercial development will be limited by soil suitability and a high water table. Some of the area east of Hydraulic Rd. as well as the area north of K-53 west of Hydraulic will likely be impacted by the flood zone. Development in the floodway will require detailed analysis demonstrating the

impacts of the proposed construction. Wetlands south of K-53 and east of Hydraulic Rd. may impact development as well. Section 404 permits and mitigation may be required if fill will placed in any wetlands.

The extension of potable water service and sanitary sewer to the west of the Arkansas River is expected to be able to serve new developments within the vicinity of the Casino Complex. Improvements in capacity and distribution of these systems will be necessary, but will likely be possible as the area develops. Electric service will likely be provided by Mulvane, but will require the city to update, improve, and/or extend the electric power system.


SUMMARY

A marginal increase in market demand for residential and light industrial is anticipated within the Study Area. The Casino and Equine Center (and possibly concert events) are expected to spur additional commercial development intended to intercept patron traffic. With the increase in industrial and commercial development, the number of jobs in the Study Area is expected to increase.

The roadway network provides good access within the Study Area and the increased traffic is expected to improve the commercial development potential. However, the future commercial development locations are not without their challenges. Poor soil suitability, flood zones, wetlands, water features, and a high water table may increase the cost of development and permitting may be required.

Another challenge will be extending services to developments. Potable water, sanitary sewer, and electric power will all need to be extended to the developments and improvements in capacity and distribution may be required. There have been investments in extending these services west of the Arkansas River and future capacity and distribution will likely be available for new developments.





Page Intentionally Left Blank



The Study Area includes various transportation infrastructure with specific operational characteristics. This chapter summarizes the existing transportation infrastructure, traffic operational characteristics, and roadway safety issues.

EXISTING TRANSPORTATION INFRASTRUCTURE

The transportation system currently provides vehicular travel options to access the Casino Complex, providing many opportunities for people and goods to be transported within and through the Study Area. There are many north/south and east/west arterials that provide regional and local access. The existing roads, bridges, railroads, airports, and bicycle and pedestrian facilities that are within or serve the Study Area are identified.

Streets & Highways

Interstate 35 (I-35) is the main north/south route through the Study Area, which is located just east of the Casino Complex. I-35 connects to Oklahoma and Texas to the south and Missouri, Iowa, and Minnesota to the north. I-35 is owned and operated by the Kansas Turnpike Authority (KTA) in the Study Area and is a tolled facility through the Study Area. This route provides the main connection to the Casino Complex, especially for visitors traveling longer distances. It also provides regional access from the Wichita Metro Area to the north. I-35 has two travel lanes in each direction through the Study Area at a posted speed of 75 miles per hour.

There is an interchange at mile marker 33 that provides almost direct access to the Casino Complex from northbound and southbound I-35. This interchange includes a toll plaza to access the Casino Complex as well as a toll plaza to access K-53 from I-35.

US-81 also provides north/south access to the Casino Complex, which carries more local trips. US-81 provides connections from Wichita and Haysville to the north to the Casino Complex. This route is located just west of the Casino Complex and includes three access points to the Casino Complex from US-81. US-81 is classified as a minor arterial through the Study Area and the area at the junction of US-81 and K-55. US-81 jogs to the west at the junction with K-55 before flowing north/south again four miles west of the junction.

K-53 flows east/west through the Study Area and functions similar to US-81, providing access for local traffic from areas to the west and east. K-53 connects the Casino Complex to Mulvane, located about five miles east of the Complex. There is one entry point on K-53 to access the Casino Complex. K-53 is classified as a minor arterial east of US-81 and a major collector west of US-81.

K-55 flows east/west six miles south of K-53, providing access east of US-81 into Cowley County. K-55 is classified as a minor arterial.

There are many north/south and east/west roads in the area, most of which are section line roads at 1-mile intervals. These roads provide access to the Casino Complex area and offer alternative routes for local trips beyond I-35, US-81, and K-53. The main roads and their classification are as follows:

- North/south
 - Seneca Street (local)
 - Hydraulic Road (major collector north of K-53, minor collector south of K-53)
 - Hillside Road (local)
 - Oliver Street (local north of K-53, major collector south of K-53)
 - Rock Road / North 2nd Avenue (minor arterial)
 - Webb (minor arterial)
- East/west
- 87th Street South (minor arterial)
- 95th Street South (minor arterial)
- 103rd Street South (major collector west of US-81, local east of US-81)
- 111th Street South (local)
- 119th Street South (major collector west of US-81, designated as K-53 east of US-81)
- 140th Street North (local)
- 130th Street North (local)
- 90th Avenue North (minor arterial)

Bridges

There are 21 bridge locations (23 bridge structures) in the Study Area. These bridges are at interchanges, over and underpasses of I-35/KTA and the railroad tracks, as well as bridges over waterways and drainage. The bridge locations include 17 state system bridges as well as six non-state system bridges. The Study Area also includes many culverts, which are not considered bridges. **Table 11** shows the bridges within the Study Area.

Railroads

There are a few railroad lines that pass through the far eastern portion of the Study Area near Mulvane. The Burlington Northern/Santa Fe owns two lines that pass through the eastern portion of the Study Area in Mulvane. One line runs northeast/southwest and the other runs northwest/southeast. The two lines converge just south of downtown Mulvane and the Study Area.

The closest passenger rail stop is located about 42 miles north of the Casino Complex in Newton, KS. The Southwest Chief route, which is operated by Amtrak, serves 33 stops from Los Angeles, CA to Chicago, IL. The route

Table 11: Bridges

	KDOT Bridge #	On	Dscrpt	At
	0087-B0466	US-81	over	Drainage southof 87th St. S.
	0087-B0157	US-81	over	Cowskin Creek
				Drainage between 111th St. S.
	0087-B0462	US-81	over	and K-53
	0087-B0219	111th St. S.	over	I-35
	0096-B0102	I-35	over	K-53
	0096-B0103	I-35	over	K-53
ten	0096-B0134	Casino Interchange	over	I-35
State System	0096-B0039	140th St. N.	over	I-35
te (0096-B0128	K-53	over	Cowskin Creek
Sta	0096-B0128	K-53	over	Drainage west of Hillside
	0096-B0106	K-53	over	Drainage west of Oliver
	0096-B0107	K-53	over	Arkansas River
	0096-B0108	K-53	over	Arkansas River Drainage
	0096-B0110	K-53	under	BNSF railroad
	0087-B0433	K-15 Southbound	over	BNSF railroad
	0087-B0434	K-15 Northbound	over	BNSF railroad
	0096-B0141	K-15	over	K-53 / 119th St. N.
	N/A	95th St. S.	over	Cowskin Creek
em				Drainage between Seneca and
yst	N/A	111th St. S.	over	US-81
Non-State System	N/A	111th St. S.	over	Cowskin Creek
tat				Drainage between 111th St. S.
S-uc	N/A	Washington	over	and K-53
N	N/A	Hydraulic	over	Cowskin Creek
	N/A	Hillside	over	Cowskin Creek

passes through California, Arizona, New Mexico, Colorado, Kansas, Missouri, Iowa, and Illinois.

Airports

There are no airports within the Study Area; however, Kendrigan Airport is located just outside the Study Area north of 130th Ave. North and east of I-35. This is a small privately owned airport and has little impact on future growth and development within the Study Area.

The major airport serving the area is Mid-Continent Airport located 20 miles northwest of the Casino Complex in Wichita, KS. There are currently five airlines that serve Mid-Continent with one more planned for June of 2013. These current airlines provide direct flights to eight major metropolitan areas, with one more planned for May of 2013.



Another airport that serves the Casino Area is the Wellington Municipal Airport located twelve miles southwest of the Casino Complex on US-81. This public airport has general aircraft services in close proximity to the Casino Complex.

Bicycle & Pedestrian Facilities

There are no dedicated pedestrian or bicycle facilities that provide access to the Casino Complex. There are sidewalks in the eastern portion of the Study Area along K-53 east of Industrial Dr. and throughout downtown Mulvane.

EXISTING TRAFFIC OPERATIONS & SAFETY

Traffic operations and roadway safety are both important components in establishing how well any roadway system is performing and how well that system may be expected to perform in the future. The following section describes the types of analyses performed in this Study for existing conditions, the data inputs required, and the findings.

Traffic Operations

Capacity analyses were performed for the existing study intersections listed below using lane geometry and traffic control device information collected from the field.

- US-81 and 87th Street
- US-81 and 95th Street
- US-81 and 111th Street
- US-81 and K-53
- US-81 and Kansas Star Drive
- US-81 and 142nd Street
- US 81 and K-55
- K-53 and Kansas Star Drive
- K-53 and KTA Connector
- K-53 and Hillside Road
- K-53 and Blair Street
- K-53 and Southbound K-15 Ramp
- K-53 and Northbound K-15 Ramp

The study intersections were evaluated based on the methodologies outlined in the Highway Capacity Manual (HCM), 2010 Edition, published by the Transportation Research Board. The operating conditions at an intersection are graded by the "level of service" experienced by drivers. Level of service (LOS) describes the quality of traffic operating conditions and is rated from "A" to "F". LOS A represents free-flow movement of traffic with minimal delays. LOS F generally indicates severely congested conditions with excessive delays

to motorists. Intermediate grades of B, C, D, and E reflect incremental increases in the average delay per stopped vehicle. Delay is measured in seconds per vehicle. <u>Table 12</u> shows the upper limit of delay associated with each level of service for signalized and unsignalized intersections.

Table 12: Intersection Level of Service Thresholds

Level of Service	Signalized	Unsignalized
Α	< 10 Seconds	< 10 Seconds
В	< 20 Seconds	< 15 Seconds
С	< 35 Seconds	< 25 Seconds
D	< 55 Seconds	< 35 Seconds
E	< 80 Seconds	< 50 Seconds
F	≥ 80 Seconds	≥ 50 Seconds

A summary of the AM and PM peak hour capacity analyses of the study intersections under existing traffic conditions is provided in **Table 13**. As shown in the table, all study intersection movements are operating with minimal delays and very good LOS under existing conditions. The lane configurations, intersection control devices, and traffic volumes used in the analysis for each location are illustrated in **Exhibit 1** through **Exhibit 3**.

Road Safety

Road safety was assessed for the segments of the US-81 and K-53 corridors within the Study Area based on crash history data provided by KDOT for the years 2009 through 2011. Crash rates and critical crash rates were calculated for each roadway segment and intersection. Crash rates are typically considered better measures of risk than crash frequencies alone, since they account for differences in traffic flow. The critical crash rate is calculated to identify those crash rates that are significantly worse than average for specific roadway types and traffic volumes. More detailed study may be warranted for locations where the crash rate is calculated to be higher than the critical crash rate.

Summarized in <u>Tables 14</u> and <u>15</u> are the route and intersection crash characteristics identified for the US-81 corridor.

There were thirty five crashes along the US-81 corridor and nine at intersection locations within the

Table 13: Intersection Operational Analysis (2012)

		A	.M. Peak H		P.M. Peak Hour		
Intersection	Movement	LOS*	Delay**	V/C***	LOS*	Delay**	V/C***
	Eastbound	В	10.7	0.04	В	11.3	0.03
US-81 and 87th Street	Westbound	Α	9.4	0.01	В	11.0	0.01
US-81 and 87th Street	Northbound left-turn	Α	0.1	0.00	Α	0.0	0.00
	Southbound left-turn	Α	0.2	0.00	Α	0.1	0.00
	Eastbound	В	10.6	0.02	В	11.8	0.01
US-81 and 95th Street	Westbound	В	10.3	0.03	В	12.6	0.11
02-81 and 32th 2treet	Northbound left-turn	Α	0.1	0.00	Α	0.1	0.00
	Southbound left-turn	А	0.5	0.00	Α	0.3	0.01
	Eastbound	В	10.1	0.00	В	11.5	0.01
LIC O1 and 111th Church	Westbound	Α	9.2	0.01	Α	0.0	0.00
US-81 and 111th Street	Northbound left-turn	Α	0.0	0.00	Α	0.0	0.00
	Southbound left-turn	Α	0.0	0.00	Α	0.1	0.00
	Eastbound	В	10.8	0.05	В	12.6	0.10
LIC 04 av -1 1/ 53	Westbound	В	10.8	0.12	В	13.7	0.18
US-81 and K-53	Northbound left-turn	Α	0.2	0.00	Α	0.6	0.01
	Southbound left-turn	Α	1.3	0.01	Α	1.7	0.03
US-81 and Kansas Star	Westbound	В	10.4	0.05	В	11.6	0.12
Drive	Southbound left-turn	А	7.7	0.01	Α	7.8	0.01
	Eastbound	В	11.4	0.01	В	13.9	0.01
UC 04 1 4 42 1 Ct 1	Westbound	Α	9.5	0.03	В	10.1	0.10
US-81 and 142nd Street	Northbound left-turn	Α	0.0	0.00	Α	0.0	0.00
	Southbound left-turn	Α	7.7	0.02	Α	7.7	0.03
	Westbound	Α	9.4	0.02	Α	10.0	0.04
US-81 and K-55	Northbound	Α	9.3	0.02	Α	9.9	0.02
	Southbound left-turn	Α	8.8	0.01	Α	9.1	0.03
K-53 and Kansas Star	Westbound left-turn	Α	7.5	0.01	Α	7.6	0.02
Drive	Northbound	Α	9.1	0.01	Α	9.2	0.03
V 52 I VTA C	Westbound left-turn	Α	5.6	0.12	Α	2.9	0.04
K-53 and KTA Connector	Northbound	Α	9.0	0.06	В	10.4	0.22
	Eastbound left-turn	Α	1.8	0.01	Α	0.9	0.02
V F2 and Hillside Dood	Westbound left-turn	Α	0.1	0.00	Α	0.5	0.01
K-53 and Hillside Road	Northbound	В	11.3	0.10	В	12.5	0.06
	Southbound	В	10.1	0.05	В	12.7	0.23
V 52 I DI 1 C1	Westbound	Α	9.7	0.02	В	10.9	0.02
K-53 and Blair Street	Southbound left-turn	Α	0.1	0.00	Α	0.8	0.01
K-53 and Southbound K-	Westbound left-turn	Α	0.0	0.00	Α	0.3	0.00
15 Ramp	Northbound	Α	8.9	0.00	Α	8.9	0.04
	Eastbound left-turn	Α	0.3	0.00	Α	0.3	0.00
K-53 and Northbound K-	Westbound left-turn	А	4.2	0.02	Α	3.5	0.02
15 Ramp	Northbound	А	9.5	0.03	Α	9.4	0.02
·	Southbound	A	8.5	0.00	Α	8.5	0.00
*Level of Service							

^{*}Level of Service





^{**}Delay in seconds per vehicle

three-year study period. In general, the crash rates at twenty three intersections within the three distinct roadway segments along the US-81 corridor were relatively low compared to the critical crash rates calculated.

Table 14: US-81 Route Characteristics

From	70	Miles	MPH	Lanes	Edge of Travel*	ADT**	Total Crashes	Crash Rate***	Critical Rate***
K-55	140th Ave.	5.06	55	2	4	3,500	13	0.67	2.07
140th Ave.	K-53	0.85	55	2	4	3,900	4	1.1	2.41
K-53	87th Street	4.04	55	2	4	3,300	18	1.23	2.16

^{*}Distance in feet from white edge line to edge of pavement

Table 15: US-81 Intersection Characteristics

Interception	ADT*	Total	Cuark Bata**	Critical
Intersection US-81 and K-55	ADT* 4,000	Crashes 4	Crash Rate** 9.13	Rate** 11.06
Brook St.	3,500	0	9.13	11.64
100th Ave.		0	0	11.64
110th Ave.	3,500	0	0	
	3,500		-	11.64
120th Ave.	3,500	0	0	11.64
130th Ave.	3,500	0	0	11.64
140th Ave.	3,500	1	2.61	11.64
142nd Ave.	4,000	0	0	11.06
143rd Ave.	4,000	0	0	11.06
144th Ave.	4,000	0	0	11.06
Kansas Star Drive	4,000	0	0	11.06
K-53	4,800	3	5.71	10.36
K-53 (5-years, 2007-2011)	4,800	8	9.13	8.76
11th St.	3,300	0	0	11.9
103rd St.	3,300	1	2.77	11.9
96th St.	3,300	0	0	11.9
95th St.	3,300	0	0	11.9
York Ln.	3,300	0	0	11.9
91st St.	3,300	0	0	11.9
Rhodes St.	3,300	0	0	11.9
Gordon Bennet Dr.	3,300	0	0	11.9
89th St.	3,300	0	0	11.9
87th St.	3,300	0	0	11.9

^{*}Average Daily Traffic

One location that did have a slightly higher crash rate of 9.13 than the critical rate of 8.76 is at the intersection of US-81 and K-53. Unlike all other intersections assessed, these crash rates are based on the number of crashes that have occurred within a five-year period from 2007 through 2011. There

were a total of eight crashes with five of them angle collisions. A review of the crash reports indicated that some of the drivers failed to stop at the posted stop signs. Although the number of crashes in this location is relatively low, an average of 1.6 per year, this location should be monitored for stop sign compliance and could be actively targeted by law enforcement officers as a special enforcement area with a zero tolerance policy for stop sign compliance.

Summarized in <u>Table 16</u> and <u>Table 17</u> are the route and intersection crash characteristics identified for the K-53 corridor.

Table 16: K-53 Route Characteristics

From	Q.	Miles	МРН	Lanes	Edge of Travel*	ADT**	Total Crashes	Crash Rate***	Critical Rate***
US-81	Oliver	3	55	2	4	3200	11	1.05	1.86
Oliver	Mulvane WCL	1.68	55	2	4	3450	0	0	2.08

^{*}Distance in feet from white edge line to edge of pavement

Table 17: K-53 Intersection Characteristics

Intersection	ADT*	Total Crashes	Crash Rate**	Critical Rate**
Kansas Star Dr.	2,600	0	0	13.1
Washington St.	2,600	0	0	13.1
KTA Ramp	3,600	1	2.54	11.51
Hydraulic Rd.	3,450	1	2.65	11.7
Easy Rd.	3,450	1	2.65	11.7
Hillside Rd.	3,450	0	0	11.7
Oliver Rd.	3,450	2	5.29	11.7
East St.	3,450	0	0	11.7
Estfan Rd.	3,450	0	0	11.7
146th Ave.	3,450	0	0	11.7
Industrial Dr.	3,450	0	0	11.7

^{*}Average Daily Traffic

There were a total of eleven crashes along the K-53 corridor and five at intersection locations within the three-year analysis period. All crash rates at intersections and within the various roadway segments were lower than the critical crash rates, indicating no significant crash risks. It is worth noting that there were six animal related crashes that occurred on K-53 between Hydraulic Rd. and Easy St. near a wooded area and a creek indicating a potential need for warning signage.

The railroad crossing 9406P at K-53 and BNSF tracks on the west side of Mulvane was also examined from a safety standpoint using the Hazard Index (HI). The Hazard Index is used by KDOT to objectively rate the relative hazard potential for all crossings and is based on highway traffic, train traffic, and existing warning devices. The HI formula is:

HI = (Average Daily Traffic) x (# trains per day at crossing) x (Weighted factor*)

*Weighted factor for existing warning device (0.1 for flashing lights and gates; 0.6 for flashing lights; 1.0 for crossbucks)

All at-grade railroad crossings in the WAMPO area were analyzed in the summer of 2007 in the Railroad Crossing Plan. According to the plan, the HI in 2007 was 14,865 and had 29 trains/day and 5,126 veh/day traveling through it and was ranked 29th in the WAMPO area. Current Hazard Index is 12,075 and has 35 trains/day and 3,450 veh/day traveling through it. Variations in train and traffic volumes should be expected due to seasonal or other variations in train and vehicular traffic patterns at a given instance. The Hazard Index shown is a general indicator as to the relative safety of the crossing and is relative to the other crossings in the WAMPO area. Analyzing all of the other crossing in the WAMPO area is outside the purview of this project, but reviewing the old report the crossing would most likely remain in a similar rank today.

SUMMARY

The existing vehicular transportation infrastructure provides adequate mobility through the Study Area and access to the Casino Complex. The roadways and intersections are currently operating at LOS B or higher during the AM and PM peak hours. This shows that the current roadway network is not causing substantial vehicular delay under current vehicular traffic patterns.

Safety on the roadways was considered and data shows most of the system is operating safely. There is only one intersection that appears to have a potential safety issue; US-81 and K-53 has a crash rate that is greater than the critical rate. Further study at this intersection is needed to assess safety concerns specific to this location.

Multimodal facilities are limited within the Study Area. However, there is access in near proximity to the Study Area via passenger rail and air travel. There are limited bicycle and pedestrian facilities in the Study Area, all of which are located in the far eastern portion. Due to the rural nature and sporadic developments, there is not a great demand for bicycle or pedestrian facilities.

The railroad tracks that cross the Study Area are an operational concern due to delays near at-grade intersections. The crossings also pose a safety concern, which can be evaluated using the Hazard Index. The crossing of the BNSF



^{**}Average Daily Traffic

^{***}Crash rate per million vehicle miles traveled


^{**}Crash rate per ten million entering vehicles


^{**}Average Daily Traffic

^{***}Crash rate per million vehicle miles traveled

^{**}Crash rate per ten million entering vehicles

fixhikit &nd \$\cdot 83 \) Intense coince Diffgthens 50 highest Hazard Index's in the WAMPO region in 2007. Review of current data would provide a better insight as to how this crossing ranks with other crossings in the region.















Exhibit 2: K-53 Intersection Diagrams












CHAPTER 6: FUTURE TRANSPORTATION CONDITIONS

The future development potential of the Study Area necessitates the need to assess the impacts of growth on the transportation system. A travel demand model was created for the CATP based on the regional WAMPO Model. The roadway network and Traffic Analysis Zones (TAZ) were built to a finer grain and WAMPO's planned projects through 2040 within the Study Area were added. This is considered the "Future No Build Scenario." The model was then used to assess the traffic impacts under future condtions.

TRAVEL DEMAND MODEL

WAMPO's Travel Demand Model was used as a base to forecast future year 2040 traffic volumes in the Study Area. This process started by building a Base Year sub-area model (2010) from the existing WAMPO model. The extent of the sub-area model is shown in **Exhibit 4**.

Exhibit 4: CATP Model Network



The model was also extended south of WAMPO's boundaries to encompass the entire Study Area. Existing base year demographic data and land use data from the Study were used to build trips based on destinations and attractions for each TAZ for daily, AM, and PM peak hour traffic volumes. The zones were then distributed using TransCAD's internal balancing model and calibrated to existing volumes.

A future year model was built which used the same roadway network as existing and then accounting for the proposed changes in land use as well as the anticipated changes in employment and residences for the area. The zones were again distributed using TransCAD's internal balancing model and checked for reasonableness.

A future year model updated with planned network improvements (from WAMPO's model) was then built using the same demographic and land use data as the future year model. The major network improvement that was in the model was the South Area Transportation Study Loop (SATS Loop), which runs from US-54 down 119th Street West to 95th St. South to Greenwich Road back to US-54. The portion of the loop in the model was updated to a five-lane arterial designation, and includes a bridge over the Arkansas River. In the sub-area model this extra river crossing draws traffic from both the 83rd St. bridge in Derby, as well as the K-53 river crossing. Hydraulic also sees additional traffic growth compared to the future year model, which is mainly drawn from US-81.

TRAFFIC ANALYSIS

Future year volumes and turning movements were required for the analysis. The existing and future year volumes were available from the model, as was existing turning movements. However, the future year turning movements were not produced by the model. To get future year turning movement, the base year turning movements were increased by a specific percent. This percent increase was calculated by using the percent increase in base year volumes to future year volumes. The turning movements were manually checked and balanced against the future year model volumes. A summary of the AM and PM peak hour capacity analyses of the study intersections under existing study network plus future volume traffic conditions is provided in **Table 18**.

SAFETY ANALYSIS

For the future no build volumes, the railroad crossing 9406P at K-53 and the BNSF tracks on the west side of Mulvane was also examined from a safety standpoint using the change in the Hazard Index as detailed previously.

Table 18: Intersection Operational Analysis (Future No Build Scenario)

	A.M. Peak Hour			our		P.M. Peak Ho	our
Intersection	Movement	LOS*	Delay**	V/C***	LOS*	Delay**	V/C***
	Eastbound	F	181.7	1.20	F	256.0	1.20
LIC 01 and 07th Charact	Westbound	F	95.6	1.00	F	>300	2.40
US-81 and 87th Street	Northbound left-turn	А	8.3	0.10	А	9.4	9.40
	Southbound left-turn	А	8.5	0.10	Α	9.1	9.10
	Eastbound	F	>300	0 Cap.	F	>300	0 Cap.
LIC O1 and OFth Charact	Westbound	F	>300	0 Cap.	F	>300	0 Cap.
US-81 and 95th Street	Northbound left-turn	А	8.2	0.20	А	9.5	0.20
	Southbound left-turn	А	8.3	0.20	Α	9.0	0.20
	Eastbound	F	95.6	1.00	F	213.1	1.20
LIC 01 and 111th Charact	Westbound	Е	35.9	0.60	F	213.1	1.20
US-81 and 111th Street	Northbound left-turn	А	8.3	0.00	А	9.3	0.00
	Southbound left-turn	А	8.1	0.00	Α	8.4	0.00
	Eastbound	F	61.6	0.90	F	>300	2.69
UC 04 IV 50	Westbound	F	147.1	1.10	F	>300	0 Cap.
US-81 and K-53	Northbound left-turn	А	8.0	0.00	А	8.6	0.00
	Southbound left-turn	А	8.3	0.10	Α	9.0	0.10
US-81 and Kansas Star	Westbound	С	20.9	0.50	F	216.9	1.40
Drive	Southbound left-turn	А	7.9	0.00	Α	8.5	0.10
	Eastbound	D	25.7	0.10	D	32.1	0.00
110.04	Westbound	С	22.5	0.50	В	14.1	0.20
US-81 and 142nd Street	Northbound left-turn	Α	0.0	0.00	А	0.0	0.10
	Southbound left-turn	А	8.0	0.10	А	8.4	0.00
	Westbound	В	13.9	0.10	В	11.9	0.10
US-81 and K-55	Northbound	А	9.5	0.10	Α	9.7	0.00
	Southbound left-turn	А	7.7	0.00	А	7.8	0.00
K-53 and Kansas Star Drive	Westbound left-turn	А	8.5	0.10	Α	8.6	0.10
K-55 dilu Kalisas Stal Dilve	Northbound	В	13.4	0.30	В	12.8	0.20
	Eastbound left-turn	А	8.2	0.10	Α	8.2	0.20
V 52 and Hydraulic	Westbound left-turn	А	7.9	0.00	Α	8.9	0.00
K-53 and Hydraulic	Northbound	F	96.2	0.90	Е	37.2	0.40
	Southbound	В	14.4	0.30	E	37.3	0.60
K-53 and KTA Connector	Westbound left-turn	А	9.6	0.20	Α	9.1	0.10
K-33 and KTA Connector	Northbound	E	36.8	0.70	Е	37.4	0.80
	Eastbound left-turn	А	7.9	0.00	Α	7.8	0.10
K-53 and Hillside Road	Westbound left-turn	А	7.7	0.00	Α	8.6	0.00
K-33 dilu filliside kodu	Northbound	В	14.3	0.20	С	22.6	0.20
	Southbound	В	11.5	0.10	С	24.1	0.40
K-53 and Blair Street	Westbound	В	11.6	0.10	В	12.0	0.00
K-55 dilu bidii Street	Southbound left-turn	А	7.7	0.00	А	8.0	0.00
K-53 and Southbound K-15	Westbound left-turn	А	0.0	0.00	Α	7.9	0.00
Ramp	Northbound	Α	9.1	0.00	В	10.3	0.10
	Eastbound left-turn	А	7.5	0.00	Α	7.4	0.00
K-53 and Northbound K-15	Westbound left-turn	А	7.6	0.10	Α	8.0	0.00
Ramp	Northbound	В	12.5	0.10	В	13.2	0.20
	Southbound	А	9.1	0.10	В	11.7	0.20
*Level of Service	**Delay in seconds per vehicle ***Volume/capacity ratio						

^{*}Level of Service



^{*}Delay in seconds per vehicle

^{***}Volume/capacity ratio

CHAPTER 6: FUTURE TRANSPORTATION CONDITIONS

Assuming the number of trains per day remaining at 35 trains/day, using the rounded "No build" ADT model volume of 6,000 veh/day traveling through it and that the lights and gates would remain the Hazard Index would be approximately 21,000, which would be similar to the existing WAMPO 2007 Crossing Study rankings of around 21st St. (Washington St. at BNSF). Given the nature of the assumptions given, using the Hazard Index as a future predictor of how safe the crossing will be is not exact, and is highly sensitive to the number of trains at the crossing. It does illustrate a rough comparison of how the 9406P crossing will function relative to its current Hazard Index and that of other regional crossings (i.e. Washington St. at BNSF).

OTHER PROJECT CONSIDERATIONS

There are two major regional transportation projects that are in the planning stages that have the potential to influence traffic in the Study Area. Although outside the CATP Study Area, these projects connect to routes within the Study Area and are within the CATP model network. Further discussion of these projects is included in the following chapter.

95th Street South

The South Area Transportation Study (SATS) assessed future mobility needs in southern Sedgwick County through an evaluation of various transportation improvements. SATS identified three alternatives, one of which was an arterial loop parkway using 95th St. South as the east/west route. 95th St. improvements, including a new bridge over the Arkansas River, are included in the Metropolitan Transportation Plan (MTP) 2035. This makes them eligible to receive federal transportation funds; however, funding has not been secured. The inclusion of 95th St. improvements also places them in the future WAMPO model network, which was used as the basis for the model developed for the CATP.

The inclusion of the 95th St. South project in the future year CATP model significantly changed traffic patterns surrounding the Study Area. The new bridge over the Arkansas River reroutes future traffic onto 95th Street, significantly impacting east/west travel in and aournd the Study Area.

Mulvane Alternative Route

Similar to the 95th St. improvements, the Mulvane Alternative Route (MAR) is another planned project that is included in the MTP 2035 as well as the future WAMPO model network. The MAR is a route to connect K-15 and K-53, bypassing Mulvane to the west with an overpass crossing the BNSF railroad. This future improvement is also included in the CATP future year model network.

Although this project did not significanly change travel patterns when included in the project area model, the MAR would improve travel delay caused by trains, traveler safety crossing railroad tracks, and route continuity.

BICYCLE & PEDESTRIAN FACILITY ANALYSIS

There are currently very few pedestrian and bicycle facilities within the Study Area and all are on the eastern portion of the area near downtown Mulvane. However, planning activities have identified one future bicycle route within the Study Area. The WAMPO Regional Pathway System Plan (RPSP) and the draft Sedgwick County Quad Cities Joint Area Plan identify potential facilities on both sides of the Arkansas River. Facilities along the river could bring the demand for more bicycle and pedestrian facilities in the Study Area. The RPSP corridors near the Study Area are shown on **Map G** on the next page.

If the demand for bicycle and pedestrian facilities increases in the Study Area, planning for the routing of these facilities will need to be completed. The CATP identifies very preliminary options for routing bicycle facilities. The focus is on bicycle facilities since demand for pedestrian facilities is not expected to increase due to the development types and low density development expected in the area. The CATP identifies primary north/south and east/west routes to provide bicycle access through the Study Area while trying to provide efficient and safe access to future development.

Corridors that would be good candidates for future bicycle corridors have been identified, as well as the opportunities they provide which make them good candidates. These corridors are for planning purposes only and will require further investigation to determine if bicycle facilities could be included.

The Arkansas River corridor, with multi-use paths along both sides of the river, is identified in the WAMPO Regional Pathway System Plan and the draft Sedgwick County Quad Cities Joint Area Plan. This corridor provides a north/south route to connect with a planned route on 83rd St. South connecting Derby, Haysville, and areas further north. This route would provide good north/south connectivity, connecting the Study Area to facilities further north at 83rd St. South while offering aesthetically pleasing views along the river.

As part of the South Area Parkway System, the planned redevelopment of the 95th St. South corridor offers the opportunity to start a bicycle corridor from a clean slate. The Derby-Mulvane Joint Area Plan, draft Sedgwick County Quad Cities Joint Area Plan, South Area Transportation Study, and Metropolitan Transportation Plan identify 95th St. South improvements to a parkway, including a new bridge over the Arkansas River. The Quad Cities Plan states that future bicycle/pedestrian infrastructure should be considered in the future design and development of 95th St. South. This corridor would provide good east/west connectivity.

The K-53 corridor offers both opportunities and challenges as a future bicycle corridor. K-53 provides a direct connection between downtown Mulvane and the Casino Complex. This is currently the only vehicular bridge over the Arkansas River south of 83rd St. South (4.5 miles north of K-53) and north of K-55 (6 miles south of K-53). But the bridge's shoulders are too narrow

for dedicated bicycle/pedestrian accommodations. If constructed with bicycle facilities, the planned bridge on 95th St. South would be a better east/west bicycle connection over the Arkansas River. Paved shoulders exist on segments of K-53, but there is a lack of continuity. The intersections would not create significant safety issues when including bicycle facilities. K-53 carries between 2,700 and 4,000 vehicles between US-81 and downtown Mulvane, with 5-10% being heavy commercial traffic. This route may pose some issues due to its state designation as well as the limited space under I-35.

North/south corridors beyond the Arkansas River corridor are limited. Oliver, Hillside, and Seneca are not paved north of K-53, which limit their appeal as bicycle corridors. Hydraulic is paved but has guard rails along both sides of the roadway with limited clearance on either side just north of K-53. US-81 is limited by its federal road designation, greater travel speeds, higher traffic volumes and projected traffic growth as development continues. US-81 is also a commercial and industrial corridor, which does not make it an ideal candidate for a bicycle corridor.

It is important to provide a design that facilitates safe and convenient travel for bicyclists. Appropriate signage is also and important element of bicycle facilities. **Exhibit 5** (page 26) shows example bicycle signage from the Manual on Uniform Traffic Control Devices (MUTCD) as well as proper use and location.

Bicycles are technically allowed on most state and US highways, but such routes are not normally thought of as ideal bicycle corridors, particularly outside of urbanized areas. As rural highways, both K-53 and US-81 fit this description within the Study Area. By definition, rural highway facilities are designed to provide safe travel for a moderate volume of motorized vehicles traveling at relatively high speeds. For these reasons, KDOT does not normally support constructing these types of roadways with on-road or adjacent bicycle facilities.

Despite providing direct connections between established communities and the casino, there are several specific issues beyond the generalized concerns with providing bicycle accommodations on K-53 and US-81. Paved shoulder space is narrow on both routes and lack continuity on K-53. The K-53 bridge over the Arkansas River has paved shoulders, but lacks the necessary width for pedestrian use, which is unlikely to change in the future. Also, the I-35 bridge over K-53 lacks sufficient span to allow for the construction of adjacent bicycle lanes.

PUBLIC TRANSPORTATION ANALYSIS

There is currently no fixed-route public transportation service within the Study Area. Wichita Transit operates fixed route service in the vicinity of the Study Area. The closest service is located 4 miles north of the Study Area (8 miles north of the Casino Complex) at US-81 and 55th St. South. Expansion of

CHAPTER 6: FUTURE TRANSPORTATION CONDITIONS

service is not planned at this time. However, the Metropolitan Transportation Plan 2035 discusses potential connections for commuter bus routes which could include routes along US-81, K-15, and/or I-35. Future expansion may be desired to connect the Casino Complex or other destinations that may develop.

SUMMARY

Under the Future No Build Scenario there are no anticipated capacity issues along mainline roadways. Current lane configurations and their inherent capacity should be sufficient to maintain adequate operational conditions through 2040.


Despite adequate roadway capacity within the Study Area, intersection capacity will likely become a concern as new development occurs and additional traffic begins using the transportation system. The greatest level of service impacts are anticipated at the following intersections:

- Arterial intersections north of K-53 along US-81
- Intersections and driveways in close proximity to Kansas Star Casino
- Future commercial and high-density development entrances onto US-81 and K-53

Future improvements to 95th St. South as the SATS Loop is developed will have significant impacts on traffic volumes and travel patterns within the Study Area. In particular, a new bridge crossing the Arkansas River will provide a new east/west route choice. The extent of these impacts will depend upon project timing, phasing, and the specific improvements included in each construction phase. Additionally, the likely changes in travel behaviors may affect future land development patterns in a way that has not been anticipated in current land use plans. Further study should be conducted to gain a more thorough understanding of probable impacts related to the expansion of 95th St. South.

The Casino and future ancillary development are not expected to generate significant bicycle or pedestrian traffic. Furthermore, neither the existing road system nor the Future No Build Scenario are ideal for these travel modes. There will be little demand for dedicated bicycle/pedestrian facilities with the Casino as a destination. However, as the regional bicycle/pedestrian network is expanded into the south portion of the Study Area, a connection to the immediate Casino vicinity should be considered.

Map G: WAMPO Regional Pathway System Plan Corridors





MUTCD BICYCLE SIGNAGE EXAMPLES*



W11-1

"The Bicycle Warning (W11-1) sign alerts the road user to unexpected entries into the roadway by bicyclists, and other crossing activities that might cause conflicts."

* Adapted from MUTCD Figure 9B-5 on page 801

- - page 796



W16-1P

"In situations where there is a need to warn motorists to watch for bicyclists traveling along the highway, the SHARE THE ROAD (W16-1P) plaque may be used in conjunction with the W11-1 sign."

- - page 798

"A W16-1P plaque shall not be used alone." - page 134




D11-1

"Bike Route Guide (D11-1) signs may be provided along designated bicycle routes..."

- - page 798

"The Bicycle Route Guide sign may be installed where no unique designation of routes is desired."

- - page 801





The ultimate goal of the Casino Area Transportation Plan is to preserve and enhance safe, efficient transportation within the Study Area. The analysis of existing and future conditions has identified concerns that might interfere with achieving this goal. This chapter contains recommended infrastructure improvements, specific actions, and policies for addressing projected transportation deficiencies.

RECOMMENDED TRANSPORTATION IMPROVEMENTS

The transportation analysis uncovered no current or future highway capacity deficiencies and only minimal safety concerns. The main issues are related to intersection capacity and operations plus the future impacts of providing highway access to new development. Therefore, recommended improvements focus on managing access to US-81 and K-53 while optimizing intersection performance. This strategy will help preserve operational efficiency as land is developed, particularly near Kansas Star Casino where most development can be expected. The specific location, timing, density, and land use of these developments will be determined largely by market demand.

The access management treatments and roundabouts recommended in the Concept Improvement Plan are two types of improvements frequently misunderstood by those outside of the transportation planning and design professions. In general, access management seeks to balance property access, traffic operations and safety with a variety of techniques. A roundabout is a specific type of intersection designed to minimize travel delay and turning movement conflicts. However, a roundabout is not the optimal solution for every intersection. Determining the proper access management technique or intersection configuration depends upon a number of site-specific conditions and traffic related factors at a given location. Final decisions on the appropriate improvement type at each location and actual design parameters (size, capacity, etc.) will be made based on engineering evaluations conducted prior to the design stage.

Appendix 5 provides further descriptions and explanations of common access management techniques including roundabouts. Additional information can also be found on the KDOT website at www.ksdot.org.

Recommended improvements were not prioritized because no critical or imminent concerns exist. Instead, the recommendation for each improvement location includes a "trigger." The triggers are events or performance measures that indicate when the improvement(s) should be constructed. Planning level cost estimates are provided for construction in 2013 dollars.

The recommendations are listed by intersection location along US-81 and K-53. Each listing includes a reference to the Concept Improvement Plan graphic (labeled **Exhibit 6** through **Exhibit 11**) that illustrates the recommendations.

LISTING OF RECOMMENDATIONS

1. US-81 & 87th St. South (Exhibit 6)

Recommended Access Management:

- Substantial compliance with KDOT's Access Management Policy with full access controls, except as approved by highway access permit.
- Relocation/consolidation of driveways and acquisition of existing access to meet access spacing requirements.
- Closure of driveways within the intersection functional area.
- Redesign and reconstruction of substandard access openings.

Recommended Improvements: Signalize the intersection and modify the lane configuration as illustrated in the Concept Improvement Plan.

Planning Level Cost Estimate: \$500,000

<u>Trigger:</u> Intersection meets traffic warrants for signalization.

<u>Discussion:</u> The recommended improvements are generally consistent with the South Broadway Corridor Plan prepared by WAMPO and the city of Haysville. Minor differences in lane configuration are attributed to analysis methodology. A roundabout was suggested as a possible alternative, but it could not be recommended without further study. Additional roundabout analysis was conducted during this project and determined to operate acceptably. However, signalization is recommended for reasons related to future 95th St. South improvements such as:

- The extent of impacts to traffic volumes and development patterns has not been fully studied, but would be expected to affect this intersection.
- Planned improvements are not programmed and timing is unknown.
- Roundabouts cost more, require more right-of-way, and are more difficult to retrofit than signalized intersections. The associated risks factored into the recommendation.

Future assessment of 95th St. South may alleviate these concerns and provide ample justification to construct a roundabout.

2. US-81 & 95th St. South (Exhibit 6)

Recommended Access Management:

- Substantial compliance with KDOT's Access Management Policy with full access controls, except as approved by highway access permit.
- Relocation/consolidation of driveways and acquisition of existing access to meet access spacing requirements.
- Closure of driveways within the intersection functional area.
- Redesign and reconstruction of substandard access openings.

Recommended Improvements: Signalize the intersection and modify the lane configuration as illustrated in the Concept Improvement Plan.

Planning Level Cost Estimate: \$625,000

<u>Trigger:</u> Intersection meets traffic warrants for signalization or construct with planned improvements to 95th St. South.

<u>Discussion:</u> As project details and impacts clarified, the recommended configuration should be reviewed and modified as appropriate.

3. US-81 & mid-mile between 111th Street South and K-53 (Exhibit 7)

Recommended Access Management:

- Full compliance with KDOT's Access Management Policy with full access controls along US-81 highway frontage, except where indicated in the Concept Improvement Plan as approved by highway access permit.
- Develop commercial sites with ample onsite circulation to reduce highway access needs.

<u>Option 1 Recommended Improvements:</u> Construct a one-lane roundabout to serve future development on both sides of US-81.

Option 1 Planning Level Cost Estimate: \$2,250,000

<u>Option 2 Recommended Improvements:</u> Construct a signalized intersection to serve future development on both sides of US-81. The lane configuration should be as illustrated in the Concept Improvement Plan.

Option 2 Planning Level Cost Estimate: \$500,000

<u>Trigger:</u> Submittal of development and/or highway access permit applications.

Discussion: Frontage properties along both sides of US-81 north of K-53 are planned for future commercial development (see **Map F** on pg. 15). Recommended improvements should be implemented by local agencies as conditions of development approval. Construction costs could then be allocated to the development as a reasonable traffic mitigation requirement.

4. Casino Vicinity Access Management (Exhibit 8)

Recommendations:

- Full compliance with KDOT's Access Management Policy for new development locations as a condition of Highway Access Permit approval.
- Substantial compliance with KDOT's Access Management Policy for previously developed locations where improvements are constructed.
- Full access controls along US-81 and K-53 highway frontages, except where indicated in the Concept Improvement Plan as approved by highway access permit.
- Relocation/consolidation of driveways to meet access spacing requirements.
- Redesign and reconstruction of substandard access openings.
- Develop the property immediately southwest of the US-81/K-53 intersection with ample onsite circulation to reduce highway access needs.



Planning Level Cost Estimate: N/A

<u>Trigger:</u> Submittal of development and/or highway access permit applications OR with adjacent intersection improvements, whichever is applicable.

<u>Discussion:</u> Preserving adequate access and intersection spacing will be critical to maintaining highway safety and operational efficiency. Recommended access management for new development should be implemented as conditions of development and highway access permit approval. Recommended access management adjacent to intersection improvements should be implemented at construction with costs allocated to the project budget.

5. US-81 & K-53 (Exhibit 8)

Recommended Access Management: See recommendation #4.

<u>Option 1 Recommended Improvements:</u> Replace the existing intersection with a one-lane roundabout.

Option 1 Planning Level Cost Estimate: \$2,250,000

Option 2 Recommended Improvements: Signalize the intersection and modify the lane configuration as illustrated in the Concept Improvement Plan.

Option 2 Planning Level Cost Estimate: \$550,000

<u>Trigger:</u> Intersection meets traffic warrants for recommended improvement.

<u>Discussion:</u> The intersection operates acceptably under current conditions. The existing intersection falls short of meeting warrants, but will meet warrants in the near-term as adjacent properties develop. Additionally, the safety analysis shows that the 5-year crash rate exceeded the critical rate. Both improvement options were examined and determined to operate acceptably. However, a roundabout would more effectively address the identified crash concern.

6. US-81 & Kansas Star Dr. (Exhibit 8)

Recommended Access Management: See recommendation #4.

<u>Option 1 Recommended Improvements:</u> Replace the existing intersection with a one-lane roundabout.

Option 1 Planning Level Cost Estimate: \$2,250,000

<u>Option 2 Recommended Improvements:</u> Signalize the intersection and modify the lane configuration as illustrated in the Concept Improvement Plan.

Option 2 Planning Level Cost Estimate: \$400,000

<u>Trigger:</u> Submittal of development and/or highway access permit applications for the property immediately southwest of the US-81/K-53 intersection *OR* intersection meets traffic warrants for recommended improvement, whichever comes first.

<u>Discussion:</u> The property immediately southwest of the US-81/K-53 intersection is planned for future commercial development to one-half mile west of the intersection (see <u>Map F</u> on pg. 15). Recommended improvements

should be implemented by local agencies as conditions of development approval. Construction costs could then be allocated to the development as a reasonable traffic mitigation requirement.

7. US-81 & K-55 (Exhibit 9)

Recommended Access Management:

- Full compliance with KDOT's Access Management Policy with full access controls along US-81 and K-55 highway frontages.
- Closure and/or realignment of private driveways as illustrated in the Concept Improvement Plan.
- Redesign and reconstruction of substandard access openings.

Option 1 Recommended Improvements: Replace the existing intersection with a one-lane roundabout.

Option 1 Planning Level Cost Estimate: \$2,800,000

<u>Option 2 Recommended Improvements:</u> Replace the existing intersection with a T-intersection configured as illustrated in the Concept Improvement Plan.

Option 2 Planning Level Cost Estimate: \$600,000

<u>Trigger:</u> Crash rate exceeds critical crash rate or crash severity is determined by KDOT to be excessive compared to similar locations.

<u>Discussion:</u> The intersection operates acceptably as currently configured through the 2040 study horizon and the crash rate is lower than the critical rate. However, a review of accident reports indicates multiple severe crashes. Additionally, several substantial skid marks were noted on US-81 during field observations, which is evidence of frequent evasive maneuvers. The speed differential between the through-movements on US-81 (posted 65 mph) and entering traffic from K-55 is a likely contributing factor. The atypical geometry provides sight lines at unusual angles. Drivers of entering US-81 likely misjudge the speed and distance of oncoming traffic.

This intersection should continue to be monitored as development occurs and traffic volumes increase. Either configuration above would improve sight distance with typical intersection geometrics more in line with driver expectations. A roundabout would provide safety advantages over the T-intersection.

8. K-53 & Washington St./Wyldewood Cellars Driveway (Exhibit 10)

Recommended Access Management:

- Full compliance with KDOT's Access Management Policy with full access controls along K-53 highway frontage, except as approved by highway access permit.
- Develop commercial sites immediately northeast of the US-81/K-53 intersection with ample onsite circulation to reduce highway access needs.

<u>Option 1 Recommended Improvements:</u> Relocate the Wyldewood Cellars driveway to Kansas Star Dr. and realign Washington St. to Kansas Star Dr.

Provide the stop controls and lane configurations illustrated in the Concept Improvement Plan.

Option 1 Planning Level Cost Estimate: \$300,000

Option 2 Recommended Improvements: Relocate the Wyldewood Cellars driveway and realign Washington St. to create a new intersection with K-53 approximately 400 feet west of the existing location. Provide the stop controls and lane configurations illustrated in the Concept Improvement Plan.

Option 2 Planning Level Cost Estimate: \$175,000

<u>Trigger:</u> None. The project should be initiated in the near-term as practicable rather than being monitored for a trigger event.

<u>Discussion:</u> This project should be considered the priority because it will address an existing issue. The existing intersection is located directly adjacent to the I-35 overpass, which severely restricts intersection sight lines. The location and design are not consistent with current design criteria/guidance. The intersection was not analyzed due to low traffic volumes. However, field observations and anecdotal evidence support the project's need as a potential safety concern.

Highway access to the winery property is restricted to the current driveway location. Actual frontage on the south side of K-53 is under casino ownership along the remainder of the north property line. Either recommendation option would require coordination between the two owners and negotiation of an access agreement or exchange of property.

Washington St. is public right-of-way between K-53 and 111th St. South. KDOT should initiate discussions with Sedgwick County regarding realignment of Washington St. Otherwise, the right-of-way could be vacated when the property is subdivided and realigned with development.

9. K-53 & KTA Connector/Hydraulic Rd. (Exhibit 11)

Recommended Access Management:

- Full compliance with KDOT's Access Management Policy and acquire full access controls, except as approved by highway access permit in the locations and configurations illustrated in the Concept Improvement Plan.
- Develop commercial sites between the KTA Connector and Hydraulic Rd. with ample onsite circulation to reduce highway access needs.

Recommended Improvements: Replace the existing KTA Connector intersection with a one-lane roundabout and realign the north leg of the existing Hydraulic Rd. intersection to connect with the roundabout.

Planning Level Cost Estimate: \$3,200,000

<u>Trigger (KTA Connector Improvements):</u> Northbound traffic queue exiting KTA Connector onto K-53 begins approaching KTA toll booth.





<u>Trigger (Hydraulic Rd. Improvements):</u> Realign with KTA intersection improvements OR when intersection meets traffic warrants for recommended improvements after construction of the KTA improvements.

<u>Discussion:</u> Both intersections operate acceptably under current conditions, but LOS deteriorates approaching the Future No Build scenario. Forecasted conditions show high peak hour (AM and PM) turning volumes entering and exiting the KTA Connector from K-53. Left turns into and right turns out of the KTA conflict during both peak hours. A significant portion of the left-turn volumes come from the north leg of the Hydraulic intersection. This Hydraulic Rd. to KTA movement interferes with the through traffic on K-53.

Signalization was investigated as an option for the KTA intersection, but resulted in unacceptable delay. It is possible that some combination of alternative improvements would work, but the configuration would likely require significant road realignments and right-of-way acquisition. The recommended roundabout is the simple solution. No other improvement options can be confidently recommended without detailed analysis in excess of current project allowances.

TRAFFIC ANALYSIS FOR FUTURE BUILD SCENARIO

The conditions that will exist in 2040 after recommended improvements are constructed is referred to as the Future Build Scenario. An intersection operational analysis of Study Area intersections was completed for the Future Build Scenario, including the alternate configurations shown in the Concept Improvement Plan. For consistency, the analysis included the same intersections previously assessed under existing conditions and the Future No Build Scenario even those with no recommended improvements. **Table 19** summarizes the analysis results.

As previously explained, LOS D is generally considered the lowest acceptable level of operational performance for highway intersections. The analysis indicated that all Study Area intersections are projected to operate acceptably in the Future Build Scenario, with most operating at LOS A or B. This includes the recommended and alternative configurations.

Table 19: Intersection Operational Analysis (Future Build Scenario)

		l A	A.M. Peak H	our	P.M. Peak Hour		
Intersection	Movement	LOS ²	Delay ³	V/C⁴	LOS ²	Delay ³	V/C ⁴
US-81 and 87th Street	All Movements (Signalized)	В	11.5	0.58	В	10.1	0.64
US-81 and 95th Street		С	22.3	0.31	D	38.0	0.93
03-61 dilu 95tii 3tieet	All Movements (Signalized) Eastbound	A	9.4	0.31	В	13.2	0.35
	Westbound	A	8.8	0.32	A	9.7	0.33
LIC O1 and 111th Charact	Northbound	A	9.9	0.29	В	11.7	0.28
US-81 and 111th Street	Southbound	В	10.6	0.43	С	20.7	0.37
		В	14.6	0.65		19.1	0.78
	All Movements (Signalized) ¹ Eastbound				A		
		В	13.1	0.48	С	20.3	0.58
115.04	Westbound Northbound	A B	7.9	0.29	В	10.3	0.36 0.76
US-81 and K-53	Southbound		9.3	0.49	С	23.1	0.76
		A		0.43	С	19.7	
	All Movements (Signalized) 1	В	17.7	0.67	В	19.0	0.77
	Westbound	A	8.1	0.32	В	12.9	0.52
US-81 and Kansas Star Drive	Northbound	A	7.5	0.37	A	8.9	0.41
	Southbound	В	11.6	0.56	С	19.2	0.74
	All Movements (Signalized) ¹	А	7.6	0.63	Α	1.3	0.35
	Eastbound	D	25.7	0.07	D	32.1	0.02
US-81 and 142nd Street	Westbound	С	22.5	0.48	В	14.1	0.20
	Northbound left-turn	Α	0.0	0.05	Α	0.0	0.00
	Southbound left-turn	А	8.0	0.00	А	8.4	0.14
	Westbound	А	7.1	0.17	Α	5.2	0.08
	Northbound	А	8.4	0.43	Α	6.4	0.29
US-81 and K-55	Southbound	Α	4.1	0.06	Α	3.9	0.04
03-01 and K-33	Southbound (Bypass Lane)	А	8.1	0.41	Α	5.2	0.18
	Westbound ¹	Α	8.4	0.05	Α	7.9	0.03
	Southbound left-turn ¹	С	18.1	0.30	В	11.8	0.10
K-53 and Kansas Star Drive	Westbound left-turn	А	8.5	0.10	Α	8.6	0.06
K-33 allu Kalisas Stal Dilve	Northbound	В	13.4	0.27	В	12.8	0.20
V E2 and Hydraulic	Westbound left-turn	А	7.9	0.01	Α	8.9	0.03
K-53 and Hydraulic	Northbound	В	14.5	0.35	В	14.0	0.13
	Eastbound	D	27.0	0.81	С	18.4	0.75
	Westbound	С	18.9	0.73	В	11.6	0.51
K-53 and KTA Connector	Northbound	Α	8.0	0.26	В	10.3	0.25
	Northbound (Bypass)	Α	7.1	0.22	С	15.1	0.54
	Southbound	В	11.1	0.34	Α	8.7	0.29
	Eastbound left-turn	А	7.9	0.02	Α	7.8	0.06
K-53 and Hillside Road	Westbound left-turn	Α	7.7	0.00	Α	8.6	0.01
K 33 and missiae Road	Northbound	В	14.3	0.17	С	22.6	0.20
	Southbound	В	11.5	0.09	С	24.1	0.42
K-53 and Blair Street	Westbound	В	12.0	0.03	В	11.6	0.09
איסט מווע שומוו אוופפנ	Southbound left-turn	А	8.1	0.02	Α	7.7	0.00
K-53 and Southbound K-15	Westbound left-turn	Α	0.0	0.00	Α	7.9	0.00
Ramp	Northbound	Α	9.1	0.02	В	10.3	0.10
	Eastbound left-turn	Α	7.5	0.00	Α	7.4	0.00
K-53 and Northbound K-15	Westbound left-turn	Α	7.6	0.05	А	8.0	0.04
Ramp	Northbound	В	12.5	0.09	В	13.2	0.16
	Southbound	Α	9.1	0.05	В	11.7	0.15

¹ Alternate Configuration

Sensitivity Analysis

Intersection performance below LOS B (i.e. C, D, E, F) under a future condition, indicates diminished capacity to absorb increases in traffic volume beyond the assumed rate of growth. To determine the degree of sensitivity to additional growth, a "Sensitivity Analysis" was conducted for Study Area intersections that exhibited performance below LOS B for the Future Build Scenario.

Table 20 shows the results of the Sensitivity Analysis. The degree of sensitivity is shown as the estimated percentage of increase beyond the assumed volumes each of these intersections could sustain before operating unacceptably (LOS E or F). The growth projections are shown as a percentage of total intersection traffic volume. The table also indicates the specific traffic movement directions would be affected.

Table 20: Sensitivity Analysis Results

	A.M. Peak Hour	P.M. Peak Hour
Intersection	% Increase and LOS*	% Increase and LOS*
US-81 and 95th Street	45% Increase Cause Eastbound & Westbound Approach to LOS E	10% Increase Cause Eastbound & Westbound Approach to LOS E
US-81 and 111th Street	65% Increase Cause Southbound Approach to LOS E	15% Increase Cause Southbound Approach to LOS E
US-81 and K-53	45% Increase Cause Eastbound Approach to LOS E	15% Increase Cause Northbound Approach to LOS E
US-81 and Kansas Star Drive	55% Increase Cause Southbound Approach to LOS E	20% Increase Cause Southbound Approach to LOS E
US-81 and 142nd Street	15% Increase Cause Westbound Approach to LOS E	5% Increase Cause Westbound Approach to LOS E
K-53 and KTA Connector	10% Increase Cause Eastbound Approach to LOS E	20% Increase Cause Northbound Approach to LOS E
K-53 and Hillside Road	75% Increase Cause Northbound Approach to LOS E	15% Increase Cause Southbound Approach to LOS E

^{*}Level of Service



²Level of Service

³ Delay in seconds per vehicle

⁴ Volume/capacity ratio

OTHER RECOMMENDATIONS

95th Street South

Future improvements to 95th St. South were modeled under future conditions as a planned facility under the Future No Build Scenario model network, although only the US-81 intersection is located within the Study Area. The result was a fairly significant change in travel patterns, which redistributed traffic volumes. The current phasing may not maximize project expenditures.

It is recommended that the SATS Loop projects, especially those on 95th Street South, be studied further to better understand the traffic and development impacts. This should include investigation of ancillary traffic impacts to other facilities, unanticipated effects on development patterns, and a reassessment of the order, extents, and specific improvements of each project phase.

Mulvane Alternative Route

Like the 95th St. improvements, the Mulvane Alternative Route (MAR) was also a planned project within the sub-area model network. Based on the Comprehensive Plan map provided by the city of Mulvane (see **Appendix 4**), this proposed project connects K-15 to K-53 with a bypass around Mulvane just west of downtown. Additionally, a new grade separated rail crossing would be located north of downtown.

The traffic analysis indicated that the project would have little impact on trip route choice within the Study Area and would provide negligible capacity benefits, but it would shorten travel time through Mulvane. However, there are project considerations that travel demand modeling cannot capture such as route continuity, political reasoning, and local preferences. The MAR would also provide access to approximately 400 acres of undeveloped property west of downtown Mulvane that are planned for future industrial uses. Expanding Mulvane's industrial base could be a tremendous boost to the local economy.

The benefits of the proposed rail crossing cannot be overstated. It would provide the only grade separated crossing of this high volume BNSF line within 35 miles south of Wichita. The extra routing option would minimize travel delay for local motorists and emergency responders who would otherwise be stopped by passing trains. Eliminating travel delay helps to reduce fuel consumption, lessen vehicle emissions, increase productivity, and improve safety – all of which benefit community health and prosperity. Additionally, the rail crossing hazard index will be significantly reduced as a result of much lower traffic volume using the existing at-grade crossing.

Generally, concept studies are required for new highway alignments. After purpose and need have been demonstrated, NEPA documentation is required for state and/or federal construction funding. For this reason, it is recommended that a study be conducted for the MAR project that would provide the degree of analysis typically required to determine a project's feasibility. This normally

consists of a comprehensive assessment of project engineering considerations, possible benefits, and potential impacts including:

- Examination of multiple alignment alternatives with traffic capacity, operational, and safety analyses
- Identification of a preferred alternative with:
- Clearly defined purpose and need statement
- Preliminary design concept including:
 - · Typical cross-section(s) and interchange/intersection configurations
 - \cdot Necessary improvements such as bridges, intersections, etc.
 - · Detailed cost estimate
- Preliminary assessment of environmental conditions and impacts
- Economic analysis

The additional analyses will likely be required before KDOT would commit resources to the design, construction, and designation of the MAR as a Kansas State Highway (K-53). Mulvane should fund such a study and hire a qualified consultant. Demonstrating this level of commitment to the project might be viewed favorably when regional, state, and federal programming decisions are made. Otherwise, the city of Mulvane could utilize the Local Consultation process to seek KDOT participation in funding an appropriate study.

Alternatively, Mulvane could pursue the MAR as a city arterial street using a combination of WAMPO and local funding/implementation mechanisms. It has been included in the Metropolitan Transportation Plan (MTP) 2035 and can be assumed to have met WAMPO's threshold for regional significance. Existing project information should suffice to proceed with implementation of the MAR as a city arterial roadway after minor revisions to the proposed alignment. It should be noted that federal funding through WAMPO might still be contingent upon additional study.

Local land use plans support the MAR project and it has many potential benefits to offer. However, given the lack of necessary data on benefits and impacts, this Plan cannot provide recommendations about MAR project implementation.

Vehicular Wayfinding Signage

The I-35 interchange at Exit 33 was modified to provide ample casino access while accommodating traffic destined for other locations. The retrofit design is an innovative solution to an unconventional situation. The facility meets current design criteria and signage/pavement marking standards, but navigation can be difficult for drivers unaccustomed to complex interchange configurations.

Stakeholder discussions and field observations also suggest driver confusion in selecting a casino entrance from US-81 and K-53. Erratic driving behavior associated with this confusion may influence traffic safety and operations

on US-81 and K-53. Enhanced wayfinding signage could minimize driver confusion, which would help improve traffic flow and travel safety.

Bicycle & Pedestrian Facilities

The Quad Cities Plan identifies 95th St. South as a potential bicycle/pedestrian route. Other plans and initiatives advocate for an interconnected regional bicycle and pedestrian network. These types of improvements would provide additional travel mode options and recreational opportunities along with corresponding economic and health benefits.

There could be localized bicycle and pedestrian demand at future commercial activity nodes. This would depend upon development density and the specific mix of uses. For example, truck stops and motels are frequently developed on properties near similarly situated casinos. Many truckers and travelers prefer to park once during a rest stop and walk to access nearby goods and services.

In light of these factors, the following are recommended:

- Identify appropriate non-highway system bicycle/pedestrian routes to the immediate casino vicinity and provide connections to the regional system if and when it expands into the Study Area.
- Local agencies should assess bicycle/pedestrian demand during the development process to the degree determined appropriate by local governing bodies. Possibilities may include:
- Site design guidance to prospective developers.
- Adding bicycle/pedestrian requirements into development regulations.

Public Transit Service

The CATP Study Area and Kansas Star Casino are not currently served by a fixed route transit provider. However, local party bus operators have found a market serving casino patrons and will probably continue to meet this demand. Future public transit demand will likely be limited to area employees. Route startup and operational costs would yield a poor return on investment. Therefore, public transit service expansion within the Study Area has not been a consideration of this Plan's analysis. Demand for public transit service should be periodically assessed and expanded into the Study Area when deemed feasible by coordinating agencies.

Ongoing Stakeholder Coordination


Continued coordination between KDOT and all stakeholders is critical to the successful implementation of recommended improvements. As further study takes place, preferred options are identified and individual projects designed, input should be actively sought from project partners, other local agencies and area residents who may be affected. All feedback provided should be given due consideration during the programming and design processes.




Exhibit 6: Concept Improvement Plan (US-81/87th St. South & 95th St. South Intersections)


NOTES:

- 1. The recommend improvements are concepts intended for illustrative purposes only. Actual improvements will depend on engineering considerations at the time of design and construction.
- 2. Existing conditions are based on as-built drawings and site observations. Field surveys were not conducted as part of this project.






LOCATION 1 - US-81/87TH ST. SOUTH INTERSECTION



LOCATION 2 - US-81/95TH ST. SOUTH INTERSECTION







Exhibit 7: Concept Improvement Plan (US-81 Mid-mile between 111th St. South & K-53)

NOTES:


- 1. The recommend improvements are concepts intended for illustrative purposes only. Actual improvements will depend on engineering considerations at the time of design and construction.
- Existing conditions are based on as-built drawings and site observations. Field surveys were not conducted as part of this project.






(81)

OPTION 1 - ROUNDABOUT



OPTION 2 - TRAFFIC SIGNAL










Exhibit 8: Concept Improvement Plan (Casino Vicinity Recommendations)

NOTES:

- 1. The recommend improvements are concepts intended for illustrative purposes only. Actual improvements will depend on engineering considerations at the time of design and construction.
- 2. Existing conditions are based on as-built drawings and site observations. Field surveys were not conducted as part of this project.







OPTION 1 - ROUNDABOUTS



OPTION 2 - TRAFFIC SIGNALS







KTA Toll Booth

KANSAS STAR CASINO

OPTION 1 - ROUNDABOUT NOT TO SCALE Realign Private Drive







Exhibit 9: Concept Improvement Plan (US-81/K-55 Intersection)


NOTES

- The recommend improvements are concepts intended for illustrative purposes only. Actual improvements will depend on engineering considerations at the time of design and construction.

 Existing conditions are based on as-built drawings.
- Existing conditions are based on as-built drawings and site observations. Field surveys were not conducted as part of this project.











Exhibit 10: Concept Improvement Plan (K-53/Washington St. & Winery Intersection)

NOTES:

- 1. The recommend improvements are concepts intended for illustrative purposes only. Actual improvements will depend on engineering considerations at the time of design and construction.
- 2. Existing conditions are based on as-built drawings and site observations. Field surveys were not conducted as part of this project.





35

LOCATION MAP

= sheet location extents

EXISTING CONDITIONS (A)

Wyldewood

Cellars

35

95th S

103rd S

 \leftarrow


Future Highway

Access Control Access Closure

or Consolidation

Develop Site with

Good Circulation



Private drive to Hydraulic Rd.

Access to future commercial development

Access to future

Access to future commercial development

Right in/Right out_ ONLY

Exhibit 11: Concept Improvement Plan (K-53/KTA Connector & Hydraulic Intersections)

- The recommend improvements are concepts intended for illustrative purposes only. Actual improvements will depend on engineering considerations at the time of design and construction.
- Existing conditions are based on as-built drawings and site observations. Field surveys were not conducted as part of this project.

EXISTING CONDITIONS





MIERSTANA 35

CONCEPT

Benefits cannot be derived from the transportation recommendations unless and until they are implemented. Implementation may be accomplished through a variety of strategies. This chapter¹ contains a listing and explanation of the numerous means for implementing the Plan that have been authorized by Kansas statutes.

INTERGOVERNMENTAL COORDINATION

The local and regional project partners together with KDOT should encourage continued coordination on access management and transportation issues in the future. The US-81/K-53 Casino Area Transportation Plan is a good example of what can be accomplished when governmental agencies coordinate to achieve common goals that benefit their communities. The momentum of this planning effort should be carried into the future. As each of these agencies move forward with plans, regulations, and projects, continued consultation should occur. This will help enable meeting the Plan's goals and will minimize negative development impacts on Study Area roadways.

INTERLOCAL COOPERATION AGREEMENT

An effective way to facilitate continued intergovernmental coordination is an Interlocal Cooperation Agreement. Through the exercise of home rule, by entering into an interlocal cooperation agreement, pursuant to K.S.A. 12-2901 et seq., and by utilizing powers granted to cities and counties by Kansas statutes, significant opportunities exist for cities and counties to cooperate with each other in the creation of financing strategies for the mainline highway enhancements and city connectors and local road projects within the corridor. There is potential for such cooperation in the use of financing mechanisms described in the Implementation Toolbox section.

K.S.A. 12-2901 et seq. authorizes all public agencies of the state (including KDOT) to jointly cooperate in the exercise of any power, or privileges, or authority exercised or capable of exercise by such agency, including economic development and public improvements, pursuant to an agreement in the form therein provided. See also, K.S.A. 75-5023.

K.S.A 12-2904 (f) dictates that each interlocal agreement, prior to it taking effect, shall be submitted to the attorney general for a determination of whether or not the agreement is in proper form and compatible with the laws of the state. In addition, K.S.A. 12-2905 requires that prior to the interlocal agreement taking effect, it be filed with the Register of Deeds of every county in which each agency signatory to the agreement is located. The agreement also must be filed with the Office of Secretary of State.

IMPLEMENTATION TOOLBOX

Substantial effort and expense has been put into the development of this Plan. Each of the planning partners have invested resources to:

- Collect and analyze all available, relevant background information regarding the Study Area to fully understand current conditions
- Study and extrapolate projections and data that may have an impact transportation on Study Area roadways
- Reach out to all interested stakeholders to obtain input and guidance on what has occurred, what exists and what they feel should be the transportation goals for the study area into the future
- Forge a consensus among KDOT, the community partners, and interested stakeholders on a plan that captures this shared vision for enhancements to the mainline highways and adjacent local street network and the interface between the two, including the type and location of points of access within the Study Area

Successfully completing this planning effort is a major accomplishment in and of itself. The dividends which will flow to the parties from having achieved this goal are inestimable.

That being said, the Casino Area Transportation Plan is just that: A PLAN. The real purpose for doing a plan is to, through comprehensive and thorough analysis, create a guide to decision-making by all the interested parties, so that the vision and details of the plan can become reality. To make the vision of the Plan a reality, KDOT and each of the community partners within the study area must take action to implement the Plan. This section of the Plan describes a series of techniques that can be used by the partners to help turn the maps, illustrations, policies, goals, strategies, and recommendations of the Plan into the actual facility improvements envisioned by the Plan. The tools described in this section, when put into place, have the supplemental benefit of establishing additional criteria against which state, county, municipal, and utility improvement plans and private development proposals can be evaluated, as each is brought forward through time. Having these supplemental criteria in place will give all parties greater assurance that all the resources the parties put toward creation of the Plan will achieve the vision for the Study Area.

The toolbox of techniques is divided under three major headings: Land Use and Regulatory Strategies, Access Management Strategies, and Financing Strategies. Each subsection contains a variety of tools that, if implemented correctly, can help realize the goals outlined in the Plan. Coordination between KDOT and the local partners is essential since authority for some of the tools are vested in the state and the authority for others is vested in the local governments. Jurisdictional responsibility is indicated for each strategy along with its estimated extent of use by jurisdictions in the area for local plan implementation: Most (>50%), Some (10% - 49%), or Few (<10%).

Planning & Regulatory Strategies

Comprehensive Planning (Most)

To help ensure that the land development decisions are consistent with and are made in accordance with the recommendations of the Plan, the planning partners should adopt the US-81/K-53 Casino Area Transportation Plan as a part of their comprehensive plans. K.S.A. 12-747 authorizes city and county planning agencies to adopt a comprehensive plan for the development of that community. There is specific authority to adopt area or sector plans covering only a portion of the area within a community's jurisdictional boundaries. The plan must show the commission's recommendation for the development or redevelopment of the territory included in the portion of the plan prepared. The planning commission must hold a hearing on the adoption of the this plan and make a recommendation to the governing body on its adoption. The plan does not become effective unless approved by the governing body.

The goal of a comprehensive plan is not only to serve as a guide to development for the planning commission and the governing body but also to owners and potential owners of property within the community's jurisdictional boundaries. That being the case, it is recommended that the amended comprehensive plan be posted on the city's website and at all other appropriate locations to assist in assuring that all interested parties are informed of the recommendations of the Casino Area Transportation Plan for areas included in its footprint map.

Responsible Jurisdiction: Local

Official Maps (Some)

An official map is a legally adopted map that conclusively shows the location and width of proposed roads or streets, public facilities, public areas, and drainage rights-of-way. It is also commonly referred to as a major street plan. Although the Kansas statutes do not specifically authorize cities or counties to adopt an official map, K.S.A. 12-747, in its description of the elements that should be covered in a comprehensive plan, clearly contemplates that the plan include the type of information that is traditionally included in an official map. It goes without saying that the lack of specific statutory authority to adopt an official map in no way precludes a city or county from acting pursuant to their home rule authority to do so. In addition, K.S.A. 12-765, discussed below, granting authority to cities and counties to establish building or setback lines, does authorize cities doing so to incorporate by reference an official map in the ordinance or resolution, as the case may be. The adoption of an official map as a part of the community's comprehensive plan or as a standalone document gives that community one additional point of reference and source of guidance when considering development applications relating to land that lies within the study area to determine whether the development proposed will have an impact on the improvements contemplated by the Plan.

Responsible Jurisdiction: Local



¹ This chapter is based on content provided by KDOT that was prepared by another consultant. The original content was revised to meet project needs.

Plan Consistency (Some)

To help ensure that the community's comprehensive plan is internally consistent and therefore effectively serves as a comprehensive guide to development within the community, upon adoption or in conjunction with the adoption of the Casino Area Transportation Plan, the community should review its existing comprehensive plan to assure that other portions of the plan support and are not in conflict with the recommendations of the CATP. If the community identifies inconsistencies, it should revise and readopt the comprehensive plan with revisions designed to eliminate those inconsistencies using the procedures outlined for the adoption of a comprehensive plan.

Responsible Jurisdiction: Local

Utility Planning (Most)

Utilities necessary to support development will be constructed within the Study Area. It is critical that these utilities be located at places that are consistent with the Plan, so they will not have to be relocated upon construction of enhancements to the mainline highway at future dates. The Study partners should, in coordination with all providers of utility services within its corporate boundaries, prepare and continually update a utility master plan. These utility master plans must be carefully coordinated with the CATP to ensure consistency between the two. The Study partners should carefully evaluate the Plan, when making decisions about the location of new utilities and related easements. In addition, the Study partners should establish a regular point of interface with each utility provider to ensure coordination between the parties in ongoing planning efforts and land acquisition and placement decisions.

Responsible Jurisdiction: KDOT/Local

Capital Improvement Program (Most)

The Capital Improvement Program (CIP) is a short- to medium-term document developed by local jurisdictions that provides a plan for capital needs and a plan to finance the projects to meet capital needs. The purpose is to identify projects to be completed as well as ensure the projects can be funded. Since the recommendations in this Plan are on state routes, coordination with the KDOT will be required, as the routes are their responsibility.

Responsible Jurisdiction: Local

Conformity of Public Improvements (Most)

K.S.A. 12-748 provides that whenever a planning commission has adopted a comprehensive plan for an area, no "public improvement, public facility or public utility," of a type covered by the recommendations of that plan, may be constructed without first being submitted to and approved by the planning commission as being in conformity with the plan. Public entities with plans

for construction of these improvements, facilities and utilities should consult with the representative of cities and counties with adopted comprehensive plans early in that entity's decision-making process and timely submit those plans to the appropriate planning commissions for this determination. This requirement applies to any public entity that is intending to do this type of construction within the jurisdictional boundaries of a city or county. This is an important way to ensure due consideration is given to the recommendations of the CATP once it is made a part of a community's comprehensive plan. Cities and counties that learn of plans for construction of this type, by another public entity within their boundaries, should be diligent in contacting the entity to make sure they are aware of this obligation and then to facilitate the contemplated review, thereby helping to ensure the Plan is fully considered in these situations. It is important to note that the governing body of the entity proposing this construction can over-ride a negative recommendation of a local community planning commission, but even in that instance, an important opportunity for review of the consistency between the proposed construction and the CATP by the parties is captured.

Responsible Jurisdiction: KDOT/Local

Development Moratoria (Few)

A public sector entity may, through passage of a development moratorium, temporarily halt the processing of applications for all or a specified type of development until a governmental activity is completed, such as the adoption of a plan or the passage of a revised ordinance on a specified subject. The Supreme Court has held that a reasonable moratorium fulfills a legitimate public purpose and is not per se a taking.

As vigilant as the planning partners may be at incorporating the CATP into local comprehensive plans and utilizing the regulatory strategies to implement the Plan, situations are bound to arise where development pressures become unmanageable. In those situations, development moratoria are a very effective tool to help stem those pressures while the community determines what approach will be most effective; be it an amendment to the comprehensive plan or passage of an ordinance/resolution establishing a new or updated regulatory implementation technique, such as an overlay district. The moratorium ceases the processing of applications during a legislatively established period of time needed to prepare and adopt strategies the community determines will best address the circumstance. It is important to note that adoption of moratoria is generally considered to be a zoning action. Accordingly, that ordinance/ resolution must be passed pursuant to the hearing and notice requirement of Article 7 of the Kansas Statutes. For that reason, it is critical that communities act quickly to get a moratorium in place once a situation calling for a "time out" is identified. One way to close the window on the rush of applications that might result from notice of the consideration of a moratorium ordinance is for the community's governing body to adopt a resolution directing staff to stop accepting applications until the moratorium ordinance takes effect. The

authority for adoption of a resolution of this type is found in the "pending ordinance" doctrine, which has been accepted by the courts of most states.

Responsible Jurisdiction: Local

Zoning (Most)

Zoning is one of the most prevalent and effective mechanisms for implementing a comprehensive plan. Zoning is a process utilized by local governments to classify land into areas and districts. These areas are generally referred to as "zones," and impose, in each area and district, restrictions related to building and structure designs, building and structure placement, and uses to which land, buildings, and structures within these districts may be put. This includes setbacks and height, lot coverage, and impervious cover restrictions. The authority to establish setbacks from rights-of-ways is not specifically mentioned, but is derived from the authority to set sizes of buildings, the percentage of each lot that may be occupied and the size of yard and other open space. The implicit authority to establish setbacks as a part of zoning district restrictions is located in K.S.A. 12-755. These statutory provisions provide authority to establish setbacks for more than just buildings. They may apply to any structure within the designated setback. Traditionally, however, though established at depths adequate to preserve rights-of-way for the local street network system, the normal front and side yard setbacks included in zoning ordinances and subdivision regulations are not generally sufficient in depth to preserve rights of way that may be necessary for enhancement to a mainline highway. Zoning ordinances may also make provisions for certain uses to be established community-wide or in individual zones only by issuance of a special or conditional use permit. Rezoning of parcels that have been previously zoned may be initiated by the local community or by a property

Responsible Jurisdiction: Local

Through the adoption of zoning ordinances, which are carefully tailored to implement the strategies and policies of the Casino Area Transportation Plan, development within the Study Area can be effectively managed to ensure successful implementation of the Plan. K.S.A. 12-755 and 12-756 authorize both cities and counties to adopt zoning ordinances, and K.S.A. 12-757 authorizes the rezoning of properties in those instances where changing a property's zoning classification is advisable or necessary to adapt original zoning to current situations.

If a rezoning application proposes a zoning classification that is determined to have the potential of adversely impacting the Study Area, copies of the application, along with the staff report, should be provided to KDOT for input, at the same time any other affected party is provided notice of the hearing on the application.

K.S.A. 12715b authorizes cities, with a couple of exceptions and under certain conditions, to adopt zoning regulations applicable to land located outside of its corporate limits, but only within three miles of those limits and only if the county has not adopted zoning regulations applicable to that area of the county. Written notice of a city's intent to adopt zoning outside its limits must be provided to the appropriate board of county commissioners. Similarly, each county that proposes to adopt zoning regulations affecting property within three miles of the corporate limits of a city must give written notice of its intent to that city's governing body.

Arguably, the most important Kansas Supreme Court case dealing with zoning is Golden v. the City of Overland Park. Golden sets out factors that planning commissions and governing bodies may consider when deciding whether to approve or deny a zoning application. One of those factors is consistency with the comprehensive plan. Each community within the Study Area, when acting on a development application related to land that lies within the Study Area, should consider whether the development proposed by that application is consistent with this Plan, as adopted into its comprehensive plan.

Site Plans (Some)

The term "site plan" is used here to describe a plan submitted during the course of the development approval process. It is also designed as a mechanism to inform the decision makers of the applicant's proposal for development of a property. The site planning process is generally a one step process that is required of developers that are not required to rezone their property prior to the issuance of a building permit. To institute this mechanism, the community would need to revise its land development codes to require that, in instances of proposed developments, where some other plan approval process is not required prior to issuance of a building permit, the applicant must submit a site plan for review and approval prior to building permit issuance. It would be common for certain types of development to be excluded from the site plan approval process, such as development of a single family house or similar smaller type developments that will have a minimal impact on facilities and services or on the landscape.

The usual site plan would be described as a plan for one or more lots on which is shown the existing and proposed conditions of the lot, including topography, vegetation, drainage, floodplains, wetlands, and waterways; landscaping and open spaces; walkways; means of ingress and egress; circulation; utility services; structures and buildings; signs and lighting; berms, buffers, and screening devices; surrounding development; and any other information that reasonably may be required for an informed decision to be made by the approving authority.

It is not uncommon for the site planning process to be divided formally or informally into two parts. In these circumstances, an initial submittal, often called a concept plan, is made to the technical staff for informal review. The

applicant meets with the approving authority's technical staff to discuss the plan and exchange views on what the applicant is proposing and what the technical staff believes will be acceptable to the approving authority. It can also serve as an opportunity to fine-tune the plan for formal submittal. Once that process is complete, a formal site plan, as described above, or a preliminary development plan is submitted for staff review and report.

The nature of the approval required for a site plan can vary greatly, depending on the expertise of staff and the appetite of the community to delegate approval authority to an administrative official. So, for example, a community could decide to vest plan approval authority for some categories of development in an administrative official, other categories of development in its planning commission and retain to the governing body still another category of development approvals. One would expect that administrative approval would be available for those categories of development that are determined to be of the least potential community impact, moving up to governing body approval on those that could have far reaching impacts, such as development at certain locations (key intersections) within the Study Area.

If the site plan posed in the application is determined to have the potential of adversely impacting the study area, copies of the application, along with the staff report, should be provided to KDOT for input, at the same time any other affected party is provided notice of the hearing on the application. If no hearing is required, this notice should be provided to KDOT in enough time before action on the application takes place to allow meaningful KDOT input.

Responsible Jurisdiction: Local

Subdivision Regulation (Most)

The subdivision of land through platting is the second most common method used by communities to manage the development of property within its jurisdiction. The control of the division of a parcel of land is effectuated by adopting subdivision regulations by ordinance or resolution that requires development be in accordance with set design standards and procedures adopted locally. K.S.A. 12 - 749 grants cities and counties the authority to adopt subdivision regulations. Subdivision regulations may include, but need not be limited to: efficient and orderly location of streets; reduction of vehicular congestion; reservation or dedication of land for open spaces; offsite and on-site public improvements; recreational facilities; flood protection; building lines; compatibility of design; storm water runoff; and any other services, facilities and improvements deemed appropriate. It is through the consideration and action on plats that communities are able to require that the distances which structures are set back from rights-of-way (a very important tool for preservation of rights-of-way for mainline highway), the layout of building lots, the points of ingress and egress from the lot(s) (effective in helping to manage access) and the public improvements associated with those lots do, in fact, conform to locally established standards, including adopted plans, such

as Transportation Plans. In some locations, subdivision regulation and plat approval may actually be the most significant regulatory tool for managing development. In some more rural areas, it is more common for counties to have adopted subdivision regulations than to have adopted zoning. In those unincorporated areas, there would be no local legislative authority to manage development through zoning restrictions. Accordingly, subdivision regulation would be those counties' primary land management tool.

Subdivision regulations usually specify what improvements the subdivider will be required to provide and the standards to which the improvements need to be constructed. A plat is a map prepared by a registered civil engineer or licensed land surveyor showing the boundaries and locations of individual properties and the streets of the proposed subdivision. The plat generally also shows land to be dedicated to a public sector entity for streets and easements for public utilities. K.S.A. 12-749 authorizes a planning commission to adopt and amend regulations regarding the subdivision of land, including payment of a fee in lieu of dedication of land. This same section also authorizes a county planning commission to establish subdivision regulations. Much like zoning, a city may adopt subdivision regulations that control the subdivision of land outside of its corporate boundaries, but only within three miles of that limit or one half the distance between two cities, whichever is less. Similar written notice requirements apply. The regulations must be considered by the planning commission at a public hearing, and the commission must forward its recommendation to the governing body for its approval. K.S.A. 12-750 lays out a process that must be followed where a city desires to adopt extraterritorial subdivision regulations and the county has its own regulations in effect as to that area. That process can result in the creation of a joint city/county committee for subdivision regulation.

K.S.A. 12-752 establishes the procedure for the consideration of and action on plats. Each plat must be submitted to the planning commission, which determines if the plat conforms to the subdivision regulations. If it finds that it does, it notifies the owners of that fact and endorses that fact on the plat. A dedication of land for public purposes must be accepted by the governing body before it takes effect.

Notices should be placed on plats prior to their recording with Registers of Deeds to help ensure that prospective purchasers of properties, which are included in the geographic area covered by the Transportation Plan, are informed of the ramifications on those properties of being within an the area covered by the Transportation Plan. In addition, if the preliminary plat application is determined to have the potential of adversely impacting the Corridor, copies of the application, along with the staff report, should be provided to KDOT for input, at the same time any other affected party is provided notice of the hearing on the application.

Responsible Jurisdiction: Local



Building Permits (Most)

The same section of Kansas Statutes discussed immediately above, prohibits the issuance of a building permit for the use or construction of any structure on any platted lot in an area governed by subdivision regulations, except in the manner provided by that section. It further authorizes subdivision regulations adopted by cities and counties to provide a procedure for the issuance of building permits that takes into account the need for adequate street rights-of-way, easements, improvements of public facilities and zoning regulations, if in existence

The issuance of a building permit is obviously the last step in the typical development approval process. Although courts hold that a building permit must be issued upon submission of a complete application, if all code provisions governing the process for building permit issuance have been fulfilled, this does not mean that communities cannot creatively incorporate building permit requirements into their governing code provisions. For example, it is common for the issuance of a building permit to be conditional upon the payment of a legislatively imposed fee, such as an impact fee.

In cities or counties that have not adopted zoning or subdivision regulations, local regulations governing the issuance of building permits may not only be the last step, but also the first step in the development approval process, thus markedly increasing the importance of this tool in the arsenal of techniques a community may employ to effectively manage land development. Even in communities that have adopted one or both regulatory tools, the procedure for the issuance of building permits still may play a very a critical role. K.S.A. 12-751 authorizes cities to adopt and enforce building codes outside that city's limits and allows compliance with subdivision regulations to be a condition of the issuance of a building permit.

Responsible Jurisdiction: Local

Variances (Most)

Kansas communities have authority to grant variances from the specific terms of the zoning restriction whenever doing so is not contrary to the public interest and where, due to special conditions, local enforcement of the provisions of the regulations in an individual case results in unnecessary hardship. K.S.A. 12-759. The board of zoning appeals has the authority to grant a variance to area and setback regulations applicable to that property. The grant of a variance from district restrictions, such as parking requirements and impervious cover requirements, may be an effective way to allow an important development proposal to proceed with minor modifications that keep it out of necessary rights-of-way and behind setback lines. At the same time, the grant of some variances could adversely impact the recommendations of the Plan. Therefore, it is recommended that the board of zoning appeals consult the Casino Area Transportation Plan, as incorporated into its comprehensive plan,

when considering any request for a variance to ensure that the decision is not in conflict with the Plan. Also, if the variance proposed is determined to have the potential of adversely impacting the Study Area, copies of the application, along with the staff report, should be provided to KDOT for input, as other affected parties are provided notice of the hearing on the application.

Responsible Jurisdiction: Local

Notice of Applicability of Plan (Few)

One tool to help ensure that individuals who own property within the Study Area and who are considering purchase and/or development of that property are aware that the land is included in the area covered by the Casino Area Transportation Plan is for the Study partners to require that all plats approved by them contain a statement, similar to the following, placed in the dedication section of each approved plat.

"The property shown on and described in this plat is and shall hereinafte
perpetually be subject to the US-81/K-53 Casino Area Transportation Plan
adopted by the Kansas Department of Transportation on, the
City of (insert city name), Kansas on,and (Sedgwick o
Sumner) County, Kansas on,, recorded in the Register o
Deeds for (Sedgwick or Sumner) County, Kansas, in Book, at Page
<i>"</i>

Another way to help ensure that those interested in developing land within the study area are aware of the Plan, is for project partners to amend all their development applications to highlight the existence of special planning areas in the city or county, including the areas covered by the Casino Area Transportation Plan.

This could be handled informally through an internal process established wherein all individuals who request a development application are routinely asked by staff the location of the property that will be the subject of the application to allow the staff member to inform the potential applicant when the proposed development is located in the Study Area. Alternately, it could be handled more formally by inserting a line on all applications with a space to be filled in identifying parcels covered by the Casino Area Transportation Plan. The latter is the recommended approach, as it avoids reliance on, what could be, revolving staff to ensure that knowledge of the relevance of the Plan is consistently imparted to applicants. That being said, development application forms cannot always be changed immediately, so the informal process may be employed until the opportunity arises to make the formal change.

Entities or persons interested in land development within the Study Area may also become informed of the existence of the Plan as a result of the requisite filing of the Interlocal Cooperation Agreement (entered into among all parties to the Study that resulted in the Casino Area Transportation Plan) in the register of deeds office in the county where that property is located. It should be noted that upon its filing the Interlocal Agreement will not be filed in the grantor/grantee index, so it would typically not show up on a title search. The agreement is filed under the names of the parties to the agreement.

Responsible Jurisdiction: Local

Notice and Opportunity to Provide Input (Some)

Since the Casino Area Transportation Plan is a joint cooperative effort between KDOT and the planning partners to create a transportation planning vision for the Study Area, all parties with an interest in potential development in the Study Area should be afforded an opportunity to provide input on that decision-making process during the requisite application and consideration procedures utilized by that community. Accordingly, the Study partners each should provide KDOT with appropriate notice of any development application (including rezoning and associated preliminary development plan applications, special or conditional use applications, site plan applications and preliminary plat applications and hearings on an amendment to that community's comprehensive plan), that could reasonably be expected to have the potential to adversely impact the Study Area. In addition, each community should provide KDOT with advance copies of all such proposed plan amendments or development applications and any related staff reports.

Responsible Jurisdiction: KDOT/Local

Land Acquisition (Most)

Public sector entities have the authority to acquire land for public improvements, including state highways and local roads and streets by gift, purchase, or condemnation. (K.S.A. 19-101 et seq., Article 12, Section 5 of the Kansas Constitution, K.S.A. 68-404) Sufficient land may be acquired to accommodate immediate construction needs, as well as for future needs. In appropriate circumstances, public sector entities can acquire interests in land for public improvements in advance of the date of the start of construction. Timely acquisition of necessary rights-of-way preserves opportunities to fully implement the goals of the Casino Area Transportation Plan and helps reduce the cost of full implementation. The primary objective of all the partners in implementing the Plan must be to continually coordinate with one another to identify opportunities to acquire the interests in land necessary to construct the transportation improvements envisioned by the Plan. Continuing coordination is critical, but it means nothing if the partners are not equally devoted to cooperation with one another in the identification of traditional and innovative new sources of revenue and in creative partnering on acquisition strategies.

Responsible Jurisdiction: KDOT/Local





Access Acquisition (Some)

Existing access points that are not consistent with the Casino Area Transportation Plan can often be eliminated though the KDOT's, city's or county's exercise of their police power. For that exercise to be appropriate however, adjacent landowners must be left with "reasonable" access after the inconsistent access point is removed. A private property owner does not have a legal right to direct access to the highway or to a particular local street. It is only required that a reasonable access is available to a property owner through some alternative means, such as access to a frontage or reverse frontage road, in the case of a highway or from some other adjacent street. That being said, situations will arise where this objective of reasonable access cannot be achieved solely though exercise of a public entity's police power. Situations will also exist where it is desirable to eliminate one or more existing access points to a particular parcel to achieve the access management objectives of the Plan, while still leaving that property owner with a point of direct access that is consistent with the Plan. In those, and in other instances, it may be advisable or even necessary to acquire inconsistent points of access through traditional negotiation or condemnation processes.

Acquisition of access rights can be applied to:

- Limiting access to designated locations or side streets
- Controlling access and sight distance at intersections or interchanges
- Introducing long term or permanent access control
- Controlling traffic and turning movements at locations where high numbers of conflicting movements occur

Responsible Jurisdiction: KDOT/Local

Land Dedication and In-Lieu Fees (Most)

One of the most, if not the most, critical recommendation of the Casino Area Transportation Plan is that both KDOT and the Study partners do everything within their power to preserve and acquire the right-of-way necessary to construct the enhancements to the highway mainline and to the adjacent and interfacing local street network. One of the goals of the plan is to maximize economic opportunities for both landowners and communities in the Study Area while, at the same time, appropriately managing direct access. New development that takes place within the Study Area, in most instances, will create a need for new transportation network facilities to accommodate the vehicle trips it generates.

Both federal and state law authorize the local jurisdictions, as a condition of development approval, that the landowner dedicate rights-of-way needed for network improvements in an amount that is roughly proportionate to the need for facilities generated by that development. A carefully calculated system of

fees-in-lieu of dedication also can be effectively utilized to ensure the timely purchase of sufficient rights-of-way. These in-lieu fees are authorized by K.S.A. 12-749. If the Study partners adopt well-designed, legally defensible right-of-way dedication and/or in-lieu fee programs, the significant costs of acquiring the right-of-way contemplated by the Casino Area Transportation Plan can be greatly minimized, thereby helping to ensure successful implementation of the Plan.

Responsible Jurisdiction: Local

Access Management Strategies

KDOT and local communities can undertake access management activities through its "governmental police powers," beyond common design techniques. These management strategies can be designed to apply equally to all parts of the transportation network within the Study Area. The following are several action steps the planning partners can take to manage access and help assure successful implementation of this Plan.

Approval of Access (Most)

As previously stated, the authority to allow access to a state highway or city connecting links is vested in KDOT (see the KDOT Access Management Policy). A request for access is approved and controlled through issuance of a Highway Permit. The Permit is the legal document that establishes the relationship between the landowner and KDOT. All points of access to the state highway system must be the subject of a Highway Permit. This includes when access connections or local streets and intersections are installed, relocated, improved, removed, or replaced on or along state highway system right-of-way. The permit will specify such things as the location of the point of access, issues related to the construction of the access, type of use allowed at the access point and other conditions and limitations of access at that point. The KDOT District Engineer has been delegated the authority to approve Highway Permits. A request for a Highway Permit must be made with the appropriate KDOT Area Office.

With respect to access to local streets within the Study Area, the authority to approve that access is vested in either the city or county that has jurisdiction at the requested location. This authority is derived from the government's inherent police power. The actual procedure for obtaining access will vary from community to community. Some communities may have adopted an access management policy that governs the location and other aspects of access to the public streets and road. In other instances, regulations governing access points may be located in the community's zoning district regulations or its subdivision regulations. On City Connecting Links, a Highway Permit must be obtained for work in the right-of-way. Executed copies of the permit, approved by KDOT and the city or county will be provided to the property owner.

Responsible Jurisdiction: KDOT/Local

Input to KDOT on Access/Coordination of Access Management (Most)

Because of the importance of access management on the mainline highway, and on the road and street network within the Study Area, and because the authority to permit and close access to the state highway system and its connecting links is vested exclusively in KDOT, (K.S.A. 68-413 and K.S.A. 68404(a)), it is critical that the study partners confer with KDOT respecting development applications that propose access points on the mainline highway and on portions of the local street network that are included in the Plan, particularly if that access is not consistent with points shown in the Casino Area Transportation Plan as future points of access.

Responsible Jurisdiction: KDOT/Local

Coordination with KDOT (Some)

The Casino Area Transportation Plan identifies existing access points on the highway that could be consolidated over time, as appropriate circumstances present themselves, to achieve access management objectives. Accordingly, the Study partners should cooperate with KDOT in identifying existing access points along the mainline and in closing those points, where doing so, will implement Plan goals. Each local government partner should establish points of contact with KDOT to facilitate the ability to quickly capitalize on opportunities as they arise. Early coordination with KDOT at the site plan and preliminary plat stages is important.

Responsible Jurisdiction: KDOT/Local

Shared Access (Some)

One meaningful way to help ensure that all property owners are afforded reasonable access to the mainline and to the local street network consistent with the full functionality of that network, is to encourage that joint access to that network by adjacent property owners be utilized to the maximum extent possible. Therefore, communities, when reviewing development applications. should consider, as a condition of approval of that application, the grant of a recorded easement by the applicant to adjoining property owners or such other conditions as are appropriate to further the Corridor access management objectives.

Responsible Jurisdiction: KDOT/Local

FINANCING STRATEGIES

The Casino Area Transportation Plan has been developed to maximize economic opportunity while enhancing the safety and efficiency of the transportation system. The full costs of the improvements to the mainline highway and adjacent street network necessary to achieve these Plan objectives are significant. Monies needed to complete these enhancements may not be



available from KDOT or from the Study partners when the enhancements are needed. Therefore, the successful implementation of the Plan will rely upon the following:

- Identification of all potential existing financing tools
- Creative analysis of how these tools can best be utilized individually and in concert with one another to maximize resources
- Investigation of possibilities for new options using home rule and delegated powers
- Developing federal and state statutory and regulatory amendments to eliminate funding obstacles and provide new approaches
- Seeking new legislative authority for innovative funding approaches

To achieve this sought-after success, it is imperative that all Study partners carefully and constantly coordinate with one another to identify potential sources of funds and work diligently, once sources are identified, to make certain that available funds are utilized in the most effective and efficient way to the benefit of all parties to this endeavor.

That having been said, there is a wide array of financing options available to cities and counties to finance infrastructure improvements. Notably, many of these same financing options can be used as economic incentives to encourage development to occur at a certain location, in a certain form, and/or in specified densities or intensities. These financing options include traditional mechanisms used by cities and counties to raise revenues and to pay for both the capital and operational expenses of government and other alternative financing strategies.

Traditional funding mechanisms include federal and state funds, real and personal property taxation (Article 12, Section 5 of the Kansas Constitution, K.S.A. 19-101 et seq. and K.S.A. 79-1801 et seq.), sales taxation (K.S.A. 12-187 et seq.), economic development tax exemptions (Article 11, Section 13, Kansas Constitution), special assessments (K.S.A. 12-6a01 et seq., and K.S.A. 12-601), and the Main Trafficway Act (K.S.A. 12-685). The latter two are both discussed in some detail immediately below.

K.S.A 12-6a Improvement Districts (Most)

Improvement Districts are the Kansas form of a traditional benefit district; a financing and development tool whereby cities and counties can establish a district, construct improvements and then issue general obligation bonds for construction of public improvements and assess the cost to those properties that are specifically benefited by the improvement. The bonds are then retired through payment of special assessments that are paid along with the benefited property owner's ad valorem property taxes by these benefiting properties. There is a very specific statutory process that must be followed to effectively utilize this strategy.

Improvement Districts are used by the city and county to assist in development of arterial roadways (usually associated with section line roads), water lines and sanitary sewers, among other public improvements. It is a responsible and fair method available to communities in Kansas to pay for the roads and infrastructure associated with new development, though its use is not limited to improvements to support only new development. For example it is often used as the financing mechanism for the construction of new sidewalks in existing developments. However, the method can be effectively used to ensure existing property owners do not pay for improvements from which they do not receive a special benefit.

With the number of roadway, sanitary sewers and water line improvements throughout a community, if the community did not utilize improvement districts, either the improvements would not be made or property owner's ad valorem property taxes would need to be raised to allow for the construction of these necessary improvements. Developers have the option to build the improvements in front of their land to meet city specifications, but in so doing, a hodge-podge of improvements would occur, and the improvements could be under construction at different times and cause much more disruption than the orderly process afforded by the creation and administration of Improvement Districts.

Responsible Jurisdiction: Local

Main Trafficways (Few)

K.S.A. 12-685 et seq. authorizes cities to designate by ordinance any existing or proposed street, boulevard, avenue or part thereof, within its jurisdictional boundaries as a main trafficway, if the primary function of the street is the movement of traffic between areas of concentrated activity within or outside the city. Once designated a main trafficway, the city is authorized to acquire by purchase or condemnation the land necessary for that facility and to improve or reimprove that trafficway. Virtually all aspects of the construction of these trafficways is authorized, including bridges, viaducts, overpasses, underpasses, culverts and drainage, trafficway illumination, traffic control devices and pedestrian ways. The cost for these improvements, including acquisition, can be paid for from the cities' general improvement fund, internal improvement fund or any other available funds or by the issuance of general obligation bonds. No vote of the public is required for issuance of bonds for these purposes. This method is often used in conjunction with the improvement district statute for street improvements.

Because the other traditional mechanisms are regularly utilized by KDOT, cities and counties to pay for capital projects, they will not be discussed in further detail; rather the remainder of this section is devoted to an explanation of several of the less-traditional mechanisms available to cities and counties to pay for improvements contemplated by the Plan and to incent development that is consistent with the Plan's recommendations. All of these financing

mechanisms are available to fund improvements contemplated by the Casino Area Transportation Plan and their use, as the situation dictates, should not be ignored.

Although not actually a source of additional revenue, the bonding authority of cities and counties is worth noting. Each is authorized to issue long-term debt to finance projects, with that debt to be repaid from a variety of traditional and some alternative revenue sources. Bonding authority is important for many reasons, but one key advantage of issuing bonds to finance public improvements is that it allows the issuing entity to pay for an improvement up front (before total project costs are available in hand) to get a project started or even completed in those instances where timing is critical in terms of events in the community and/or to take advantage of favorable financial markets. These improvements can then be paid for over time, generally up to 20 years, as tax revenues or other dedicated sources become available. This can be a huge advantage and can help the partners in their efforts to acquire land for and make the improvements contemplated by the Plan when actual situations in the study area dictate those actions occur.

Most alternative funding techniques are devised by one local government to meet a local need and their use than spreads from community to community. The techniques are refined based on trial-and-error. Many of these approaches do not have specific legislative authority, but are enabled through home rule, local police powers, or a broad reading of authority from another source, such as local planning.

State highway, road and street projects required to support new development, may be constructed utilizing economic incentives, such as tax increment financing, Star Bonds, sales tax reimbursement agreements, tax abatement, special assessment districts and transportation development districts, to name only several of the options. It is important that, wherever possible, local communities along the Corridor be cognizant of their ability to require that revenues from the grant of these incentives to developers be used to offset the cost of the construction of mainline highway improvements and related improvements to the local street network, as shown on the Transportation Plan. But, even more importantly, they must actually make the grant of these incentives conditional on a reasonable portion of these monies being used to pay the cost of Transportation Plan identified improvements.

These incentives also can be effectively used to influence the location, type/uses, form, architectural quality, configuration and density/intensity of development. It is important to utilize these incentives, not only to offset traditional public costs for these facilities, but also as incentives to shape development proposals, so they further Plan recommendations.

Responsible Jurisdiction: Local

Impact Fees (Few)

Impact fees are one-time regulatory fees assessed against new development to cover the costs for necessary capital facilities proportionate to the demand generated by the new development. The fee is imposed by a public sector entity on development activity as a condition of granting development approval, and generally is calculated at the platting stage and collected at the time a building permit is issued. Kansas has no impact fee statutory authority. Nevertheless, cities and counties can establish a system of impact fees using their home rule authority. This system of fees requires the development of a local legislative adopted scheme that includes the calculation methodology for the fee, and a system of credits, exemptions and appeals. The system would be adopted by ordinance or resolution, as the case would require. Impact fees must be used to add capacity attributable to new development; they cannot be used to pay for improvements necessitated by existing development. An impact fee must meet three requirements:

- The new facilities are a consequence of new development;
- There must be a proportionate relationship between the fee and the infrastructure demand; and
- The funds collected must be used to provide a substantial benefit to the new development.

In Kansas, impact fees may be collected either across the entire jurisdiction or in a designated geographic area. While they may be assessed at platting, impact fees are typically collected upon building permit issuance. A detailed calculation is necessary to ensure that the system, and particularly the fee charged property owners, is proportionate to the demand for new facilities that each unit of new development generates, i.e., its impact, in terms of facility capacity consumed. In funding transportation network facility improvements, the measuring stick for each development's impacts is the number of vehicle trips it will generate. Since streets are generally designed to accommodate the PM Peak trips, that is generally the time interval used.

The Kansas Supreme Court has recognized the legitimate use of impact fees in McCarthy v. City of Leawood (257 Kan. 566, 894 P.2d 836, 1995). In that case, the City of Leawood assessed the payment of impact fees on the issuance of building permits and plat approvals for properties within the K-150 (135th Street) Corridor. The purpose of the fee was to finance a portion of the improvements of K150. Back when first established in 1988, the fee was calculated based upon trip generation, at a rate of \$26.45 per trip. This rate was then multiplied by the average number of trips generated by a use to determine the individual fee. For example, residential uses were projected to generate 10 trips per day, multiplied by \$26.45 for a fee of \$264.50 per unit.

Responsible Jurisdiction: Local

Excise Tax (Few)

Technically, an excise tax is a broad term that covers every type of tax, except a property tax. As with all taxes, it is a method of raising revenue. It is distinguished by the fact that rather than being based on the value of property, it is levied on a certain activity or the exercise of a privilege - more accurately described as business done, income received, or privilege enjoyed. Typical examples of excise taxes include taxes on the purchase of gasoline, alcohol or cigarettes, business license taxes and on the rental of hotel rooms. In recent past, local governments in Kansas have innovatively used an excise tax to fund transportation network improvements that are required to support development. It is structured as a tax on activity of platting lots. The rate of the tax is based on the amount of square footage proposed to be constructed or on the number of vehicle trips the proposed development will generate on the street network. The key reason for its use has been that because it is a tax and not a regulatory fee, the rate is not required to satisfy the constitutional benefit or nexus requirements of regulatory fees imposed by local governments, such as impact fees discussed above. Kansas courts had upheld this financing approach.

In 2006, however, the Kansas Legislature amended K.S.A. 12-194 to make it uniformly applicable to all cities. By doing so, this provision became no longer subject to a charter ordinance or resolution whereby cites and counties could make its provisions inapplicable to that city or county and adopt supplemental provisions on the subject. This charter approach was the one that cities and had used to eliminate the legal impediment in K.S.A. 12-194 and use their ordinary home rule power to establish an excise tax system of this type. It had become known as a "development excise tax." That amendment, in addition to precluding local governments that did not have a development excise tax in place from adopting one, also included a provision that prevented cities and counties that had levied or imposed a development excise from increasing the rate of the tax without a majority vote of the electors, after July 1, 2006. Accordingly, this technique is only available to local governments that had a development excise tax in place before that date, and those that did have one in place cannot increase the rate charged without a vote.

Responsible Jurisdiction: Local

Transportation Development Districts (Few)

A Transportation Development District (TDD) (K.S.A. 12-17,140 at seq.) is a form of a special district enacted specifically to facilitate the construction, maintenance and financing of a broad array of transportation projects, ranging from streets, roads, highway access roads, interchanges and bridges to light rail and mass transit facilities. Most improvements related thereto, such as streetscape, utility relocations and other necessary associated infrastructure, can also be funded using this technique. While a regular special district can be used to address transportation issues, transportation development districts

allow greater funding flexibility, including authority to impose a transportation development district sales tax of up to 1% (K.S.A. 1217,145), in addition to the authority to levy special assessments. If a transportation development district is sought to be imposed, the governing body must hold a duly noticed public hearing in advance of adopting the resolution or ordinance creating the district and approving the method of financing projects within the district. The district may issue bonds backed by the revenues received from properties in the district from the imposed sales tax or special assessment.

One significant difficulty in utilizing this mechanism for improvements covering a larger area is that the district can only be formed through a petition signed by owners of all of the land area within the proposed district. So, if the improvement is adjacent to lands owned by different owners, it may be difficult to obtain the consent of all necessary owners. It may have its greatest utility for distinct segments of the improvements proposed by the Management Plan, such as mainline highway interchanges and access roads located within one tract of land that is designated in the Plan for more dense or intense development. This technique can also be used effectively to assist in the financing of key portions of the adjacent local street network. The statutory scheme allows for a good deal of flexibility in how the boundaries of the district are established, so long as all included property owners agree. For that reason, the community partners should keep this tool on the list of the ones that should be considered for funding, particularly in those instances where a property owner or several property owners want to develop an area of land at an access point with sales tax generating properties.

Responsible Jurisdiction: Local

Tax Increment Financing (Some)

Tax increment financing (K.S.A. 12-1770 et seq.) is a tool used by local governments to capture the future increases in property tax and all or a portion of the revenues received from transient guest, use, local sales taxes collected from taxpayers doing business within the district, and increased franchise fees, and to make revenues realized therefrom available as an incentive to development, by using the revenue to pay for, generally, public infrastructure necessary to implement a redevelopment project plan (K.S.A. 12-170a (o)). Project costs may not include costs related to a structure to be owned by or leased to a developer. TIF funding can provide funds either as collected (pay-as-you-go) or through special obligation tax increment bonds repaid over twenty years.

While there is specific enabling authority for the use of TIF, it is limited to "eligible" areas that fall within one of the following categories and the boundaries of which are designated by the local government as a redevelopment district:

- Blighted
- Blighted and in a 100-year flood-plain
- Intermodal transportation area
- Major commercial entertainment and tourism area Conservation (becoming blighted)
- Major tourism area
- Historic theater
- Enterprise zone
- Environmentally contaminated area

Therefore, not all property within a local government's jurisdictional boundaries may qualify to be included in a redevelopment area. Eligible project costs most certainly would include all transportation network public infrastructure as identified in the Casino Area Transportation Plan.

Responsible Jurisdiction: Local

Sales Tax and Revenue Bond Districts (Some)

This mechanism (K.S.A. 12-17, 160 et seq.) is the big brother/sister of tax increment financing. It's a "Super TIF," if you will. The entire mechanism works almost exactly like tax increment financing, except the districts are called STAR bond project districts and the individual projects in the district are called STAR bond projects. Each project must be approved by the Secretary of Commerce and include at least a \$50,000,000 of capital investment and evidence \$50,000,000 in project gross annual sales or, if outside a MSA, met the requirements of K.S.A 12-17,162 (w). It is the heightened level of incentives authorized in these districts that is key. Once a district is established and a project plan is approved, the approving city may issue special obligation bonds. Importantly, those bonds may be repaid from the portion of the city and county sales and use tax collected from taxpayers within the city portion of the district AND the sales tax increment revenues received from any state sales taxes collected from taxpayers in that district. This is in addition to the property tax increment and local sales, use and franchise fee that can be pledged to repayment of the special obligation bonds issued in a traditional tax increment financing project. The Secretary can set a limit on the amount of bonds that may be issued to pay eligible project costs.

Responsible Jurisdiction: Local, subject to approval by the State of Kansas

