

SUMMARY OF QUANTITIES

DATE: 08/21/2019
TIME: 02:50pm

LETTING DATE: September 18, 2019

PRIME CONTRACTORS SHALL NOTIFY KDOT OF THEIR
INTENT TO BID BY IDENTIFYING THEMSELVES AS A BID HOLDER

519092171 STATE PROJECT NO: U056-046 KA 2745-02 DBE GOAL: 8.5%
WORKING DAYS: 95 COMPLETION DATE:
COUNTY: JOHNSON
GRADING AND SURFACING. US-56 AND 199TH INTER THRU EDGERTON IN
JOHNSON COUNTY. LENGTH IS 0.462 MI.

QUANTITY	UNIT	ITEM DESCRIPTION
1.00	LS	CONTRACTOR CONSTRUCTION STAKING
1.00	EACH	FIELD OFFICE AND LABORATORY (TYPE A)
1.00	LS	MOBILIZATION
1.00	LS	MOBILIZATION (DBE)
1.00	LS	REMOVAL OF EXISTING STRUCTURES
1.00	LS	MAINTENANCE AND RESTORATION OF HAUL ROADS (SET PRICE)
1.00	CUYD	CONCRETE FOR SEAL COURSE (SET PRICE)
1.00	CUYD	FOUNDATION STABILIZATION (SET PRICE)
1.00	HOUR	FLAGGER (SET PRICE)
26.00	CUYD	FOUNDATION STABILIZATION
120.00	CUYD	GRANULAR BACKFILL (WINGWALLS)
65.00	SQYD	BRIDGE BACKWALL PROTECTION SYSTEM
1.00	LS	CLEARING AND GRUBBING
38,206.00	SQYD	SALVAGED TOPSOIL
13,008.00	CUYD	COMMON EXCAVATION (RURAL SMALL)
12,277.00	CUYD	COMMON EXCAVATION (CONTRACTOR FURNISHED)
2,894.00	CUYD	ROCK EXCAVATION
114.00	CUYD	ROCK EXCAVATION (NON-DURABLE SHALE)
3,873.00	CUYD	COMPACTION OF EARTHWORK (TYPE AA) (MR-5-5)
19,725.00	CUYD	COMPACTION OF EARTHWORK (TYPE A) (MR-5-5)
1.00	MGAL	WATER (GRADING) (SET PRICE)
8,540.00	LBS.	REINFORCING STEEL (GRADE 60)
81.70	CUYD	CONCRETE (GRADE 4.0) (RCB)
141.00	LNFT	CROSS ROAD PIPE (24")
4.00	EACH	END SECTION (24")
238.00	CUYD	SLOPE PROTECTION (RIPRAP STONE)
59.00	CUYD	BEDDING FOR SLOPE PROTECTION
1.00	CUYD	TEMPORARY SURFACING MATERIAL (AGGREGATE) (SET PRICE)
0.50	PMPs	MOWING
13.00	EACH	RIGHT-OF-WAY SURVEY MONUMENT
1.00	LS	CLEANING EXISTING STRUCTURE
975.00	LBS.	TEMPORARY FERTILIZER (15-30-15)
130.00	LBS.	TEMPORARY SEED (CANADA WILDRYE)
292.50	LBS.	TEMPORARY SEED (GRAIN OATS)
292.50	LBS.	TEMPORARY SEED (STERILE WHEATGRASS)
44.00	LBS.	SOIL EROSION MIX
823.00	SQYD	EROSION CONTROL (CLASS 1) (TYPE C)
1,003.00	SQYD	EROSION CONTROL (CLASS 2) (TYPE E)
1.00	CUYD	SEDIMENT REMOVAL (SET PRICE)
1.00	LNFT	TEMPORARY BERM (SET PRICE)
284.00	CUYD	TEMPORARY DITCH CHECK (ROCK)
422.00	LNFT	BIODEGRADABLE LOG (9")

KANSAS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

LETTING DATE: September 18, 2019

DATE: 08/21/2019
TIME: 02:50pm

519092171 CONT...

QUANTITY	UNIT	ITEM DESCRIPTION
562.00	LNFT	BIODEGRADABLE LOG (12")
1,410.00	LNFT	BIODEGRADABLE LOG (20")
422.00	LNFT	FILTER SOCK (12")
1,138.00	LNFT	FILTER SOCK (18")
818.00	LNFT	SILT FENCE
1.00	LS	SWPPP DESIGN
20.00	EACH	SWPPP INSPECTION
35.00	EACH	WATER POLLUTION CONTROL MANAGER
5,490.00	LBS.	MULCHING TACKING SLURRY
18.30	TON	MULCHING
1.00	MGAL	WATER (EROSION CONTROL) (SET PRICE)
47.00	LNFT	CURB, PROTECTION (SPECIAL) (AE)
2,990.00	TON	HMA OVERLAY (SR-12.5A) (PG 64-22)
3,269.00	TON	HMA OVERLAY (SR-12.5A) (PG 64-28)
10.00	TON	EMULSIFIED ASPHALT (SS-1HP)
478.00	TON	SURFACING MATERIAL (AB-3)
12,352.00	SQYD	AGGREGATE BASE (AB-3) (6")
7,518.00	SQYD	MILLING
1.00	MGAL	WATER (AGGREGATE BASE) (SET PRICE)
427.00	TON	PAVEMENT EDGE WEDGE (ROCK)
1.00	EACH	FIELD OFFICE AND LABORATORY (TYPE A)
1.00	MGAL	WATER (EARTHWORK COMPACTION) (SET PRICE)
6,259.00	TON	QUALITY CONTROL TESTING (HMA)
1.00	LS	ASPHALT DENSITY PAY ADJUSTMENT
1.00	LS	ASPHALT PAVEMENT SMOOTHNESS
1.00	LS	ASPHALT AIR VOID PAY ADJUSTMENT
1.00	EACH	ASPHALT CORE (SET PRICE)
332.00	LNFT	FENCE (BARBED WIRE) (TEMPORARY)
133.00	SQFT	SIGN (FLAT SHEET) (HIGH PERFORMANCE)
250.00	LNFT	SIGN POST (4" X 6" WOOD) (FLAT SHEET SIGN)
28.00	LNFT	SIGN POST (2" PERFORATED SQUARE STEEL TUBE)
3.00	LNFT	SIGN POST FOOTING (18" WOOD POST CONCRETE)
2.00	EACH	SIGN POST FOOTING (2" PERFORATED SQUARE STEEL TUBE)
10.00	EACH	SIGNING DELINEATOR (TYPE A) (WHITE RIGID "U" POST)
8,854.00	LNFT	PAVEMENT MARKING (MULTI-COMPONENT) (WHITE) (6")
9,822.00	LNFT	PAVEMENT MARKING (MULTI-COMPONENT) (YELLOW) (4")
403.00	LNFT	PAVEMENT MARKING (MULTI-COMPONENT) (YELLOW) (12")
42.00	LNFT	PAVEMENT MARKING (INTERSECTION GRADE) (WHITE) (24")
10.00	EACH	PAVEMENT MRK SYM (INTERSECTION GRADE) (WHITE) (RT ARROW)
9.00	EACH	PAVEMENT MRK SYM (INTERSECTION GRADE) (WHITE) (LEFT ARROW)
1.00	EACH	PAVEMENT MRK SYM (INTERSECTION GRADE) (WHITE)(RAILROAD XING)
1.00	LS	ELECTRIC LIGHTING SYSTEM
420.00	LBS.	FERTILIZER (13-13-13)
352.00	LBS.	FERTILIZER (15-30-15)
8.80	LBS.	SEED (BIG BLUESTEM GRASS) (KAW)
1.10	LBS.	SEED (BLUE GRAMA GRASS) (LOVINGTON)
9.50	LBS.	SEED (BUFFALO GRASS) (TREATED)
44.00	LBS.	SEED (CANADA WILD-RYE)
8.80	LBS.	SEED (INDIANGRASS) (OSAGE)
8.80	LBS.	SEED (LITTLE BLUESTEM GRASS) (ALDOUS)

KANSAS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

LETTING DATE: September 18, 2019

DATE: 08/21/2019
TIME: 02:50pm

519092171 CONT...

QUANTITY	UNIT	ITEM DESCRIPTION
94.50	LBS.	SEED (RYEGRASS) (PERENNIAL)
5.50	LBS.	SEED (PRAIRIE JUNE GRASS)
41.00	LBS.	SEED (SIDE OATS GRAMA) (EL RENO)
44.00	LBS.	SEED (STERILE WHEATGRASS)
3.10	LBS.	SEED (SWITCHGRASS) (BLACKWELL)
2.20	LBS.	SEED (TALL DROP)
94.50	LBS.	SEED (FESCUE) (TALL) (ENDOPHYTE-FREE)
30.20	LBS.	SEED (WESTERN WHEATGRASS) (BARTON)
45.30	LBS.	SEED (NATIVE WILDFLOWER MIX 1)
1,400.00	EADA	WORK ZONE SIGNS (0 TO 9.25 SQ.FT.)
2,800.00	EADA	WORK ZONE SIGNS (9.26 TO 16.25 SQ.FT.)
3,920.00	EADA	WORK ZONE BARRICADES (TYPE 3 - 4 TO 12 LIN. FT.)
8,540.00	EADA	CHANNELIZER (PORTABLE)
700.00	EADA	WORK ZONE WARNING LIGHT (TYPE "A" LOW INTENSITY)
560.00	EADA	WORK ZONE WARNING LIGHT (RED TYPE "B" HIGH INTENSITY)
289.90	STAL	PAVEMENT MARKING (TEMP) 4" SOLID (TYPE I)
8,920.00	LNFT	PAVEMENT MARKING REMOVAL
4.00	EACH	WORK ZONE SIGN (SPECIAL) (16.26 SQ.FT. & OVER)
1.00	EACH	INERTIAL BARRIER SYSTEM (TL-2)
1.00	EACH	INERTIAL BARRIER SYSTEM (TL-3)
3,325.00	LNFT	CONCRETE SAFETY BARRIER (TYPE F3) (TEMPORARY)
2,875.00	LNFT	CONCRETE SAFETY BARRIER (TYPE F3) (TEMPORARY - RELOCATE)
15.00	EACH	REPLACEMENT MODULES (IBS)
1.00	LS	TRAFFIC CONTROL (INITIAL SETUP)

*** END OF CONTRACT ***

SUMMARY OF QUANTITIES

DATE: 08/21/2019

LETTING DATE: September 18, 2019

TIME: 02:50pm

519092181 STATE PROJECT NO: 081 U 2335-01 DBE GOAL: 10.0%
 WORKING DAYS: 55 COMPLETION DATE:
 COUNTY: RILEY
 SIDEWALK IMPROVEMENTS. VARIOUS LOCATIONS IN MANHATTAN IN RILEY CO.
 LENGTH IS 0.563 MI.

QUANTITY	UNIT	ITEM DESCRIPTION
1.00	LS	CONTRACTOR CONSTRUCTION STAKING
1.00	LS	MOBILIZATION
1.00	LS	MOBILIZATION (DBE)
1.00	LS	REMOVAL OF EXISTING STRUCTURES
1.00	EACH	FIELD OFFICE AND LABORATORY (TYPE C)
1.00	CUYD	FOUNDATION STABILIZATION (SET PRICE)
1.00	LS	TRAFFIC CONTROL
1.00	HOUR	FLAGGER (SET PRICE)
1.00	LS	CLEARING AND GRUBBING
535.00	CUYD	COMMON EXCAVATION (URB)
255.00	CUYD	ROCK EXCAVATION
139.00	CUYD	COMPACTION OF EARTHWORK (TYPE AA) (MR-5-5)
235.00	CUYD	COMPACTION OF EARTHWORK (TYPE B) (MR-90)
158.00	CUYD	COMMON EXCAVATION (CONTRACTOR FURNISHED)
1.00	MGAL	WATER (GRADING) (SET PRICE)
1,207.00	SQYD	SIDEWALK CONSTRUCTION (4") (AE)
118.00	SQYD	SIDEWALK RAMP
5.50	CUYD	CONCRETE (GRADE 4.0) (AE)
2,000.00	LBS.	REINFORCING STEEL (GRADE 60)
5.00	LNFT	STORM SEWER (3") (PVC)
1.00	EACH	INLET (AREA) (SPECIAL)
3.00	EACH	INLET (AREA)
1.00	EACH	JUNCTION BOX
329.00	LNFT	STORM SEWER (24") (RCP)
1.00	EACH	ADJUSTMENT OF MANHOLES
19.00	LNFT	HANDRAIL (METAL) (3'- 0")
1.00	EACH	MAILBOX INSTALLATION (SET PRICE)
100.00	SQFT	LANDSCAPE RETAINING WALL
55.00	LBS.	TEMPORARY FERTILIZER (15-30-15)
22.00	LBS.	TEMPORARY SEED (CANADA WILDRYE)
49.50	LBS.	TEMPORARY SEED (GRAIN OATS)
49.50	LBS.	TEMPORARY SEED (STERILE WHEATGRASS)
0.20	LBS.	SOIL EROSION MIX
66.00	SQYD	EROSION CONTROL (CLASS 1) (TYPE C)
1.00	CUYD	SEDIMENT REMOVAL (SET PRICE)
1.00	LNFT	TEMPORARY BERM (SET PRICE)
472.00	LNFT	BIODEGRADABLE LOG (9")
165.00	LNFT	FILTER SOCK (8")
1.00	LS	SWPPP DESIGN
15.00	EACH	SWPPP INSPECTION
25.00	EACH	WATER POLLUTION CONTROL MANAGER
1,485.00	LBS.	MULCHING TACKING SLURRY
3.30	TON	MULCHING
1.00	MGAL	WATER (EROSION CONTROL) (SET PRICE)
1,146.00	LNFT	CURB AND GUTTER, COMBINED (AE)
195.00	LNFT	CURB AND GUTTER, COMBINED (AE) (SPECIAL)

KANSAS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

LETTING DATE: September 18, 2019

DATE: 08/21/2019
TIME: 02:50pm

519092181 CONT...

QUANTITY	UNIT	ITEM DESCRIPTION
810.00	SQYD	CONCRETE PAVEMENT (6" UNIFORM) (AE)
25.00	SQYD	CONCRETE PAVEMENT (4" UNIFORM) (AE)
1,132.00	SQYD	AGGREGATE BASE (AB-3) (6")
1.00	MGAL	WATER (AGGREGATE BASE) (SET PRICE)
1.00	TON	HMA-COMMERCIAL GRADE (CLASS A)
958.00	LNFT	FENCE (CONSTRUCTION) (TEMPORARY)
102.00	SQFT	SIGN (FLAT SHEET) (HIGH PERFORMANCE)
241.00	LNFT	SIGN POST (4" X 6" WOOD) (FLAT SHEET SIGN)
1.00	LS	SIGN (REMOVE AND RESET)
690.00	LNFT	PAVEMENT MARKING (EPOXY) (WHITE) (4")
576.00	LNFT	PAVEMENT MARKING (INTERSECTION GRADE) (WHITE) (24")
335.00	LNFT	PAVEMENT MARKING (INTERSECTION GRADE) (YELLOW) (4")
2.00	EACH	PAVEMENT MARKING SYMBOL (PAINT) (WHITE) (HANDICAP)
1,017.00	LNFT	PAVEMENT MARKING REMOVAL
1.00	LS	TRAFFIC SIGNAL
55.00	LBS.	FERTILIZER (15-30-15)
440.00	LBS.	SEED (FESCUE) (TALL TURF TYPE BLEND)
1.00	LS	ROADSIDE IMPROVEMENT

*** END OF CONTRACT ***

SUMMARY OF QUANTITIES

DATE: 08/21/2019

LETTING DATE: September 18, 2019

TIME: 02:50pm

519092191 STATE PROJECT NO: I070-105 KA 4946-01 DBE GOAL: 0.0%
 WORKING DAYS: 30 COMPLETION DATE:
 COUNTY: WYANDOTTE
 BRIDGE REPAIR. I-70, BR # 70-105-4.98 (534) LOCATED 3.75 MI E OF I-435 IN WY CO.
 LENGTH IS 0.050 MI.

QUANTITY	UNIT	ITEM DESCRIPTION
1.00	LS	MOBILIZATION
1.00	LS	MOBILIZATION (DBE)
1.00	CUYD	CONCRETE FOR SEAL COURSE (SET PRICE)
1.00	LS	REMOVAL OF EXISTING STRUCTURES
1.00	LS	TRAFFIC CONTROL
1.00	HOUR	FLAGGER (SET PRICE)
145.00	SQYD	EROSION CONTROL (CLASS 1) (TYPE C)
75.00	LNFT	FILTER SOCK (18")
75.00	LNFT	SILT FENCE
1.00	CUYD	SEDIMENT REMOVAL (SET PRICE)
1.00	LNFT	TEMPORARY BERM (SET PRICE)
1.00	MGAL	WATER (EROSION CONTROL) (SET PRICE)
1.00	LS	CLEARING AND GRUBBING
7.00	CUYD	FOUNDATION STABILIZATION
94.00	CUYD	GRANULAR BACKFILL (WINGWALLS)
41.20	CUYD	CONCRETE (GRADE 4.0) (AE)
5,350.00	LBS.	REINFORCING STEEL (GRADE 60)
34.00	EACH	DRILLING AND GROUTING
50.00	CUYD	SLOPE PROTECTION (SHOT ROCK)
10.00	SQFT	CONCRETE SURFACE REPAIR
1.00	LBS.	REINFORCING STEEL (REPAIR) (GRADE 60) (SET PRICE)
1.00	LS	SEEDING

*** END OF CONTRACT ***

SUMMARY OF QUANTITIES

DATE: 08/21/2019

LETTING DATE: September 18, 2019

TIME: 02:50pm

519092272 STATE PROJECT NO: I070-021 KA 5410-01 DBE GOAL: 0.0%
 WORKING DAYS: 60 COMPLETION DATE:
 COUNTY: DICKINSON
 PAVEMENT MARKING. I-70, FR RP 266.04 TO 289.5 EB AND WB IN DK CO. LENGTH IS
 29.80 MI. STATE TIE KA 5408-01.

QUANTITY	UNIT	ITEM DESCRIPTION
1.00	LS	MOBILIZATION
1.00	LS	MOBILIZATION (DBE)
1.00	LS	TRAFFIC CONTROL
1.00	HOUR	FLAGGER (SET PRICE)
238,069.00	LNFT	PAVEMENT MARKING (MULTI-COMPONENT) (WHITE) (6") (WET RECOVERABLE)
9,440.00	LNFT	PAVEMENT MARKING (MULTI-COMPONENT) (WHITE) (8") (WET RECOVERABLE)
1,866.00	LNFT	PAVEMENT MARKING (MULTI-COMPONENT) (WHITE) (12") (WET RECOVERABLE)
224.00	LNFT	PAVEMENT MARKING (MULTI-COMPONENT) (WHITE) (24") (WET RECOVERABLE)
5,693.00	LNFT	PAVEMENT MARKING (MULTI-COMPONENT) (YELLOW) (4") (WET RECOVERABLE)
167,643.00	LNFT	PAVEMENT MARKING (MULTI-COMPONENT) (YELLOW) (6") (WET RECOVERABLE)
65,565.00	LNFT	PAVEMENT MARKING (MULTI-COMPONENT) (BLACK) (6")
422,935.00	LNFT	PAVEMENT MARKING REMOVAL

*** END OF CONTRACT ***

SUMMARY OF QUANTITIES

DATE: 08/21/2019

LETTING DATE: September 18, 2019

TIME: 02:50pm

519092282 STATE PROJECT NO: K018-072 KA 5299-01 DBE GOAL: 5.0%
 WORKING DAYS: 35 COMPLETION DATE:
 COUNTY: OTTAWA
 MILLING AND HMA OVERLAY. K-18, FR N 170TH RD E TO DK CO LI IN OT CO.
 LENGTH IS 14.728 MI.

QUANTITY	UNIT	ITEM DESCRIPTION
1.00	LS	MOBILIZATION
1.00	LS	MOBILIZATION (DBE)
1.00	EACH	FIELD OFFICE AND LABORATORY (TYPE A)
1.00	LS	MAINTENANCE AND RESTORATION OF HAUL ROADS (SET PRICE)
1.00	LS	TRAFFIC CONTROL
1.00	HOUR	FLAGGER (SET PRICE)
6,819.00	TON	MILLING
20,239.00	TON	HMA OVERLAY (SR-12.5A) (PG 64-22)
20,239.00	TON	QUALITY CONTROL TESTING (HMA)
248,022.00	SQYD	EMULSIFIED ASPHALT
1.00	TON	MATERIAL FOR HMA PATCHING (SET PRICE)
1.00	LS	ASPHALT DENSITY PAY ADJUSTMENT
1.00	LS	ASPHALT AIR VOID PAY ADJUSTMENT
1.00	EACH	ASPHALT CORE (SET PRICE)
1.00	EACH	BOND CORE (SET PRICE)
2,406.00	TON	PAVEMENT EDGE WEDGE (ROCK)
1.00	MGAL	WATER (EARTHWORK COMPACTION) (SET PRICE)
770.00	STAL	PAVEMENT MARKING (TEMP) 4" BROKEN (3')(TYPE I)
770.00	STAL	PAVEMENT MARKING (TEMP) 4" BROKEN (3')(TYPE II)
156,353.00	LNFT	PAVEMENT MARKING (MULTI-COMPONENT) (WHITE) (6")
71,272.00	LNFT	PAVEMENT MARKING (MULTI-COMPONENT) (YELLOW) (4")
24.00	LNFT	PAVEMENT MARKING (INTERSECTION GRADE) (WHITE) (24")
2.00	EACH	PAVEMENT MRK SYM (INTERSECTION GRADE) (WHITE)(RAILROAD XING)
2,400.00	LNFT	PAVEMENT MARKING REMOVAL

*** END OF CONTRACT ***

SUMMARY OF QUANTITIES

DATE: 08/21/2019

LETTING DATE: September 18, 2019

TIME: 02:50pm

519092292 STATE PROJECT NO: I070-085 KA 5408-01 DBE GOAL: 0.0%
 WORKING DAYS: 60 COMPLETION DATE:
 COUNTY: SALINE
 PAVEMENT MARKING. I-70, FR RP 259.7 TO 266.04 EB AND WB IN SA CO. LENGTH IS
 6.340 MI. STATE TIE KA 5410-01.

QUANTITY	UNIT	ITEM DESCRIPTION
1.00	LS	MOBILIZATION
1.00	LS	MOBILIZATION (DBE)
1.00	LS	TRAFFIC CONTROL
1.00	HOUR	FLAGGER (SET PRICE)
16,738.00	LNFT	PAVEMENT MARKING (MULTI-COMPONENT) (WHITE) (6") (WET RECOVERABLE)
16,738.00	LNFT	PAVEMENT MARKING (MULTI-COMPONENT) (BLACK) (6")
16,738.00	LNFT	PAVEMENT MARKING REMOVAL
*** END OF CONTRACT ***		

SUMMARY OF QUANTITIES

DATE: 08/21/2019

LETTING DATE: September 18, 2019

TIME: 02:50pm

519092313 STATE PROJECT NO: K025-055 KA 5305-01 DBE GOAL: 0.0%
 WORKING DAYS: 30 COMPLETION DATE:
 COUNTY: LOGAN
 MILLING AND HMA OVERLAY. K25, FR E US40 JCT N TO TH/LG CO LI IN LG CO.
 LENGTH IS 2.260 MI. STATE TIE KA 5306-01.

QUANTITY	UNIT	ITEM DESCRIPTION
1.00	LS	MOBILIZATION
1.00	LS	MOBILIZATION (DBE)
1.00	LS	TRAFFIC CONTROL
1.00	HOUR	FLAGGER (SET PRICE)
119.30	STA.	MILLING
3,492.00	TON	HMA OVERLAY (SR-12.5A) (PG 64-22)
3,492.00	TON	QUALITY CONTROL TESTING (HMA)
32,099.00	SQYD	EMULSIFIED ASPHALT
1.00	TON	MATERIAL FOR HMA PATCHING (SET PRICE)
1.00	EACH	ASPHALT CORE (SET PRICE)
1.00	EACH	BOND CORE (SET PRICE)
1.00	LS	ASPHALT DENSITY PAY ADJUSTMENT
1.00	LS	ASPHALT AIR VOID PAY ADJUSTMENT
238.70	STAL	FLEXIBLE RAISED PAVEMENT MARKERS (4" BROKEN (3 FT.))

*** END OF CONTRACT ***

SUMMARY OF QUANTITIES

DATE: 08/21/2019

LETTING DATE: September 18, 2019

TIME: 02:50pm

519092323 STATE PROJECT NO: K009-074 KA 5307-01 DBE GOAL: 3.0%
 WORKING DAYS: 40 COMPLETION DATE:
 COUNTY: PHILLIPS
 MILLING AND HMA OVERLAY. K9, FR NT/PL CO LI E TO US183 JCT IN PL CO. LENGTH
 IS 17.501 MI. STATE TIE M 0072-01.

QUANTITY	UNIT	ITEM DESCRIPTION
1.00	LS	MOBILIZATION
1.00	LS	MOBILIZATION (DBE)
1.00	LS	MAINTENANCE AND RESTORATION OF HAUL ROADS (SET PRICE)
1.00	EACH	FIELD OFFICE AND LABORATORY (TYPE A)
1.00	LS	TRAFFIC CONTROL
1.00	HOUR	FLAGGER (SET PRICE)
924.10	STA.	MILLING
27,173.00	TON	HMA OVERLAY (SR-12.5A) (PG 64-22)
27,173.00	TON	QUALITY CONTROL TESTING (HMA)
53.00	TON	EMULSIFIED ASPHALT (SS-1H OR CSS-1H)
1.00	TON	MATERIAL FOR HMA PATCHING (SET PRICE)
1.00	EACH	ASPHALT CORE (SET PRICE)
1.00	LS	ASPHALT DENSITY PAY ADJUSTMENT
1.00	LS	ASPHALT AIR VOID PAY ADJUSTMENT
1,848.10	STAL	PAVEMENT MARKING (TEMP) 4" BROKEN (3')(TYPE I)
1,848.10	STAL	PAVEMENT MARKING (TEMP) 4" BROKEN (3')(TYPE II)
2,086.00	TON	PAVEMENT EDGE WEDGE (ROCK)
1.00	MGAL	WATER (EARTHWORK COMPACTION) (SET PRICE)
180,930.00	LNFT	PAVEMENT MARKING (MULTI-COMPONENT) (YELLOW) (4")
89,517.00	LNFT	PAVEMENT MARKING (MULTI-COMPONENT) (WHITE) (6")

*** END OF CONTRACT ***

SUMMARY OF QUANTITIES

DATE: 08/21/2019

LETTING DATE: September 18, 2019

TIME: 02:50pm

519092343 STATE PROJECT NO: 091 KA 5406-01 DBE GOAL: 0.0%
 WORKING DAYS: 15 COMPLETION DATE:
 COUNTY: SHERMAN
 PAVEMENT MARKING. K-27 FR RM 169.95 TO 170.79. US-24B FR .065 MI W OF K-27
 JCT E .203 MI TO .138 MI E OF K-27 JCT. IN SH CO. LENGTH IS 1.043 MI

QUANTITY	UNIT	ITEM DESCRIPTION
1.00	LS	MOBILIZATION
1.00	LS	MOBILIZATION (DBE)
1.00	LS	TRAFFIC CONTROL
1.00	HOUR	FLAGGER (SET PRICE)
25,012.00	LNFT	PAVEMENT MARKING REMOVAL
13,759.00	LNFT	PAVEMENT MARKING (PATTERNED COLD PLASTIC) (WHITE) (6")
10,715.00	LNFT	PAVEMENT MARKING (PATTERNED COLD PLASTIC) (YELLOW) (4")
377.00	LNFT	PAVEMENT MARKING (PATTERNED COLD PLASTIC) (YELLOW) (12")
26.00	EACH	PAVEMENT MRK SYM (INTERSECTION GRADE) (WHITE) (LEFT ARROW)
161.00	LNFT	PAVEMENT MARKING (INTERSECTION GRADE) (WHITE) (24")

*** END OF CONTRACT ***

SUMMARY OF QUANTITIES

DATE: 08/21/2019

LETTING DATE: September 18, 2019

TIME: 02:50pm

519092353 STATE PROJECT NO: I070-091 KA 5407-01 DBE GOAL: 0.0%
 WORKING DAYS: 30 COMPLETION DATE:
 COUNTY: SHERMAN
 PAVEMENT MARKING. I-70, FR KS/CO STATE LI E TO .5 MI E OF RS-1668 (CARUSO)
 IN SH CO. LENGTH IS 12.810 MI.

QUANTITY	UNIT	ITEM DESCRIPTION
1.00	LS	MOBILIZATION
1.00	LS	MOBILIZATION (DBE)
1.00	LS	TRAFFIC CONTROL
1.00	HOUR	FLAGGER (SET PRICE)
343,463.00	LNFT	PAVEMENT MARKING REMOVAL
33,607.00	LNFT	PAVEMENT MARKING (PATTERNED COLD PLASTIC) (WHITE) (6")
33,607.00	LNFT	PAVEMENT MARKING (PATTERNED COLD PLASTIC) (BLACK) (6")
148,139.00	LNFT	PAVEMENT MARKING (MULTI-COMPONENT) (WHITE) (6")
14,752.00	LNFT	PAVEMENT MARKING (MULTI-COMPONENT) (WHITE) (8")
1,608.00	LNFT	PAVEMENT MARKING (MULTI-COMPONENT) (WHITE) (12")
189.00	LNFT	PAVEMENT MARKING (INTERSECTION GRADE) (WHITE) (24")
146,185.00	LNFT	PAVEMENT MARKING (MULTI-COMPONENT) (YELLOW) (6")

*** END OF CONTRACT ***

SUMMARY OF QUANTITIES

DATE: 08/21/2019

LETTING DATE: September 18, 2019

TIME: 02:50pm

519092363 STATE PROJECT NO: K009-092 KA 3100-01 DBE GOAL: 2.5%
 WORKING DAYS: CCD COMPLETION DATE: 11/20/20
 COUNTY: SMITH
 GRADING, BRIDGE AND SURFACING. BRIDGE 033 OVER CEDAR CR ON K-9 IN
 SMITH CO. LENGTH IS 0.082 MI.

QUANTITY	UNIT	ITEM DESCRIPTION
1.00	LS	CONTRACTOR CONSTRUCTION STAKING
1.00	EACH	FIELD OFFICE AND LABORATORY (TYPE C)
1.00	CUYD	FOUNDATION STABILIZATION (SET PRICE)
1.00	LS	MOBILIZATION
1.00	LS	MOBILIZATION (DBE)
1.00	LS	REMOVAL OF EXISTING STRUCTURES
1.00	LS	MAINTENANCE AND RESTORATION OF HAUL ROADS (SET PRICE)
1.00	CUYD	CONCRETE FOR SEAL COURSE (SET PRICE)
1.00	LS	CURING ENVIRONMENT
1.00	HOURL	FLAGGER (SET PRICE)
1.00	LS	CLEARING AND GRUBBING
18,134.00	CUYD	COMMON EXCAVATION (RURAL SMALL)
7,624.00	CUYD	COMMON EXCAVATION (CONTRACTOR FURNISHED)
95.00	CUYD	ROCK EXCAVATION
130.00	CUYD	COMPACTION OF EARTHWORK (TYPE AA) (MR-5-5)
17,529.00	CUYD	COMPACTION OF EARTHWORK (TYPE A) (MR-5-5)
1.00	MGAL	WATER (GRADING) (SET PRICE)
26,228.00	SQYD	SALVAGED TOPSOIL
525.00	LNFT	GUARDRAIL, STEEL PLATE (MGS)
1.00	CUYD	TEMPORARY SURFACING MATERIAL (AGGREGATE) (SET PRICE)
0.20	PMP	MOWING
9.00	EACH	RIGHT-OF-WAY SURVEY MONUMENT
8.00	EACH	GUARDRAIL END TERMINAL (MGS-SRT)
8.00	EACH	GUARDRAIL END TERMINAL (MGS-FLEAT)
765.00	LBS.	TEMPORARY FERTILIZER (16-20- 0)
102.00	LBS.	TEMPORARY SEED (CANADA WILD RYE)
229.50	LBS.	TEMPORARY SEED (GRAIN OATS)
229.50	LBS.	TEMPORARY SEED (STERILE WHEATGRASS)
14.30	LBS.	SOIL EROSION MIX
1,285.00	SQYD	EROSION CONTROL (CLASS 2) (TYPE E)
1.00	CUYD	SEDIMENT REMOVAL (SET PRICE)
1.00	LNFT	TEMPORARY BERM (SET PRICE)
142.00	CUYD	TEMPORARY DITCH CHECK (ROCK)
735.00	LNFT	BIODEGRADABLE LOG (9")
980.00	LNFT	BIODEGRADABLE LOG (12")
382.00	LNFT	BIODEGRADABLE LOG (20")
735.00	LNFT	FILTER SOCK (12")
379.00	LNFT	FILTER SOCK (18")
1,180.00	SQYD	GEOTEXTILE (EROSION CONTROL)
9.00	LNFT	SILT FENCE
1.00	LS	SWPPP DESIGN
30.00	EACH	SWPPP INSPECTION
55.00	EACH	WATER POLLUTION CONTROL MANAGER
4,590.00	LBS.	MULCHING TACKING SLURRY
15.30	TON	MULCHING
1.00	MGAL	WATER (EROSION CONTROL) (SET PRICE)

KANSAS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

LETTING DATE: September 18, 2019

DATE: 08/21/2019
TIME: 02:50pm

519092363 CONT...

QUANTITY	UNIT	ITEM DESCRIPTION
500.00	CUYD	CLASS I EXCAVATION
254.00	CUYD	CLASS II EXCAVATION
313.10	CUYD	CONCRETE (GRADE 4.0) (AE) (SA)
183.20	CUYD	CONCRETE (GRADE 4.0) (AE)
77,810.00	LBS.	REINFORCING STEEL (GRADE 60) (EPOXY COATED)
20,920.00	LBS.	REINFORCING STEEL (GRADE 60)
1,147.50	LNFT	PRESTRESSED CONCRETE BEAM (K3+2)
1,904.00	LNFT	PILES (STEEL) (HP10X42)
471.00	LNFT	PRE-DRILLED PILE HOLES
88.00	SQYD	BRIDGE BACKWALL PROTECTION SYSTEM
94.00	CUYD	ABUTMENT AGGREGATE DRAIN
1,450.00	SQYD	BRIDGE DECK GROOVING
141.00	CUYD	SLOPE PROTECTION (SHOT ROCK)
1.00	LS	ERECT AND REMOVE ROLLED BEAM DETOUR BRIDGE
95.00	SQYD	CONCRETE PAVEMENT (10" UNIFORM) (AE) (BR APP)
1,384.00	TON	HMA-COMMERCIAL GRADE (CLASS A)
1.00	EACH	FIELD OFFICE AND LABORATORY (TYPE A)
905.00	TON	HMA-COMMERCIAL GRADE (CLASS A)
255.00	LBS.	FERTILIZER (16-20- 0)
8.80	LBS.	SEED (BIG BLUESTEM GRASS) (KAW)
5.10	LBS.	SEED (BLUE GRAMA GRASS) (LOVINGTON)
55.90	LBS.	SEED (BUFFALO GRASS) (TREATED)
8.80	LBS.	SEED (INDIANGRASS) (OSAGE)
11.00	LBS.	SEED (LITTLE BLUESTEM GRASS) (ALDOUS)
32.10	LBS.	SEED (SIDE OATS GRAMA) (EL RENO)
51.00	LBS.	SEED (STERILE WHEATGRASS)
4.40	LBS.	SEED (SWITCHGRASS) (BLACKWELL)
21.80	LBS.	SEED (WESTERN WHEATGRASS) (BARTON)
32.60	LBS.	SEED (NATIVE WILDFLOWER MIX 2)
6,300.00	EADA	WORK ZONE SIGNS (0 TO 9.25 SQ.FT.)
4,500.00	EADA	WORK ZONE SIGNS (9.26 TO 16.25 SQ.FT.)
2,250.00	EADA	WORK ZONE BARRICADES (TYPE 3 - 4 TO 12 LIN. FT.)
6,750.00	EADA	CHANNELIZER (PORTABLE)
1,800.00	EADA	WORK ZONE WARNING LIGHT (TYPE "A" LOW INTENSITY)
136.00	STAL	PAVEMENT MARKING (TEMP) 4" SOLID (TYPE I)
40.00	STAL	PAVEMENT MARKING (TEMP) 4" SOLID (TYPE II)
2,200.00	LNFT	PAVEMENT MARKING REMOVAL
30.00	EACH	RIGID RAISED PAVEMENT MARKER (TYPE I)
1.00	LS	TRAFFIC CONTROL (INITIAL SETUP)

*** END OF CONTRACT ***

SUMMARY OF QUANTITIES

DATE: 08/21/2019

LETTING DATE: September 18, 2019

TIME: 02:50pm

519092373 STATE PROJECT NO: K025-097 KA 5306-01 DBE GOAL: 0.0%
 WORKING DAYS: 30 COMPLETION DATE:
 COUNTY: THOMAS
 MILLING AND HMA OVERLAY. K25, FR TH/LG CO LI TO SCL OF COLBY IN TH CO.
 LENGTH IS 15.519 MI. STATE TIE KA 5305-01.

QUANTITY	UNIT	ITEM DESCRIPTION
1.00	LS	MOBILIZATION
1.00	LS	MOBILIZATION (DBE)
1.00	LS	MAINTENANCE AND RESTORATION OF HAUL ROADS (SET PRICE)
1.00	EACH	FIELD OFFICE AND LABORATORY (TYPE A)
1.00	LS	TRAFFIC CONTROL
1.00	HOUR	FLAGGER (SET PRICE)
819.40	STA.	MILLING
23,817.00	TON	HMA OVERLAY (SR-12.5A) (PG 64-22)
23,817.00	TON	QUALITY CONTROL TESTING (HMA)
218,908.00	SQYD	EMULSIFIED ASPHALT
1.00	TON	MATERIAL FOR HMA PATCHING (SET PRICE)
1.00	EACH	ASPHALT CORE (SET PRICE)
1.00	EACH	BOND CORE (SET PRICE)
1.00	LS	ASPHALT DENSITY PAY ADJUSTMENT
1.00	LS	ASPHALT AIR VOID PAY ADJUSTMENT
1,638.80	STAL	FLEXIBLE RAISED PAVEMENT MARKERS (4" BROKEN (3 FT.))

*** END OF CONTRACT ***

SUMMARY OF QUANTITIES

DATE: 08/21/2019

LETTING DATE: September 18, 2019

TIME: 02:50pm

519092383 STATE PROJECT NO: U040-100 KA 5303-01 DBE GOAL: 3.0%
 WORKING DAYS: 35 COMPLETION DATE:
 COUNTY: WALLACE
 MILLING AND HMA OVERLAY. US40, FR ECL OF SHARON SPRINGS E TO WALG CO
 LI IN WA CO. LENGTH IS 15.387 MI. STATE TIE M 0071-01.

QUANTITY	UNIT	ITEM DESCRIPTION
1.00	LS	MOBILIZATION
1.00	LS	MOBILIZATION (DBE)
1.00	LS	MAINTENANCE AND RESTORATION OF HAUL ROADS (SET PRICE)
1.00	EACH	FIELD OFFICE AND LABORATORY (TYPE A)
1.00	LS	TRAFFIC CONTROL
1.00	HOUR	FLAGGER (SET PRICE)
812.40	STA.	MILLING
24,239.00	TON	HMA OVERLAY (SR-12.5A) (PG 64-22)
24,239.00	TON	QUALITY CONTROL TESTING (HMA)
47.00	TON	EMULSIFIED ASPHALT (SS-1H OR CSS-1H)
1.00	TON	MATERIAL FOR HMA PATCHING (SET PRICE)
1.00	EACH	ASPHALT CORE (SET PRICE)
1.00	LS	ASPHALT DENSITY PAY ADJUSTMENT
1.00	LS	ASPHALT AIR VOID PAY ADJUSTMENT
1,632.30	STAL	PAVEMENT MARKING (TEMP) 4" BROKEN (3')(TYPE I)
1,632.30	STAL	PAVEMENT MARKING (TEMP) 4" BROKEN (3')(TYPE II)
1,846.00	TON	PAVEMENT EDGE WEDGE (ROCK)
1.00	MGAL	WATER (EARTHWORK COMPACTION) (SET PRICE)
44,962.00	LNFT	PAVEMENT MARKING (MULTI-COMPONENT) (YELLOW) (4")
161,237.00	LNFT	PAVEMENT MARKING (MULTI-COMPONENT) (WHITE) (6")

*** END OF CONTRACT ***

SUMMARY OF QUANTITIES

DATE: 08/21/2019

LETTING DATE: September 18, 2019

TIME: 02:50pm

519092414 STATE PROJECT NO: U059-002 KA 4812-02 DBE GOAL: 5.0%
 WORKING DAYS: 70 COMPLETION DATE:
 COUNTY: ANDERSON
 GRADING, GUARDRAIL, SEEDING. US-59 FR NCL GARNETT N TO AN/FR CO LI IN AN
 CO. LENGTH IS 6.776 MI.

QUANTITY	UNIT	ITEM DESCRIPTION
1.00	LS	MOBILIZATION
1.00	LS	MOBILIZATION (DBE)
1.00	CUYD	FOUNDATION STABILIZATION (SET PRICE)
1.00	EACH	FIELD OFFICE AND LABORATORY (TYPE C)
1.00	CUYD	CONCRETE FOR SEAL COURSE (SET PRICE)
1.00	LS	CONTRACTOR CONSTRUCTION STAKING
1.00	LS	REMOVAL OF EXISTING STRUCTURES
1.00	LS	TRAFFIC CONTROL
1.00	HOUR	FLAGGER (SET PRICE)
1.00	LS	CLEANING EXISTING STRUCTURE
7.00	CUYD	FOUNDATION STABILIZATION
12.00	CUYD	GRANULAR BACKFILL (WINGWALLS)
1.00	LS	CLEARING AND GRUBBING
210.00	CUYD	COMMON EXCAVATION (RURAL SMALL)
11,074.00	CUYD	COMMON EXCAVATION (CONTRACTOR FURNISHED)
9,250.00	CUYD	COMPACTION OF EARTHWORK (TYPE A) (MR-5-5)
1.00	MGAL	WATER (GRADING) (SET PRICE)
19,185.00	SQYD	SALVAGED TOPSOIL
4.00	LNFT	RESETTING PIPE CULVERT
17.90	CUYD	CONCRETE (GRADE 4.0) (RCB)
2,120.00	LBS.	REINFORCING STEEL (GRADE 60)
6.00	LNFT	CROSS ROAD PIPE (30") (RCP)
8.00	LNFT	CROSS ROAD PIPE (48") (ACSP)
1.00	EACH	END SECTION (30") (RC)
1.00	EACH	END SECTION (48") (ACS)
1,275.00	LNFT	GUARDRAIL, STEEL PLATE (MGS)
168.75	LNFT	GUARDRAIL, STEEL PLATE
685.00	TON	PAVEMENT EDGE WEDGE (ROCK)
1.00	MGAL	WATER (EARTHWORK COMPACTION) (SET PRICE)
12.00	EACH	GUARDRAIL END TERMINAL (MGS-MSKT)
12.00	EACH	GUARDRAIL END TERMINAL (MGS-SOFTSTOP)
1.00	EACH	GUARDRAIL END TERMINAL (SRT)
1.00	EACH	GUARDRAIL END TERMINAL (FLEAT)
597.00	LBS.	TEMPORARY FERTILIZER (15-30-15)
79.60	LBS.	TEMPORARY SEED (CANADA WILD RYE)
179.10	LBS.	TEMPORARY SEED (GRAIN OATS)
179.10	LBS.	TEMPORARY SEED (STERILE WHEATGRASS)
230.80	LBS.	SOIL EROSION MIX
9,097.00	SQYD	EROSION CONTROL (CLASS 1) (TYPE C)
1,109.00	SQYD	EROSION CONTROL (CLASS 2) (TYPE F)
1.00	CUYD	SEDIMENT REMOVAL (SET PRICE)
1.00	LNFT	TEMPORARY BERM (SET PRICE)
5.00	CUYD	TEMPORARY DITCH CHECK (ROCK)
891.00	LNFT	BIODEGRADABLE LOG (9")
1,188.00	LNFT	BIODEGRADABLE LOG (12")
830.00	LNFT	BIODEGRADABLE LOG (20")

KANSAS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

LETTING DATE: September 18, 2019

DATE: 08/21/2019
TIME: 02:50pm

519092414 CONT...

QUANTITY	UNIT	ITEM DESCRIPTION
891.00	LNFT	FILTER SOCK (12")
645.00	LNFT	FILTER SOCK (18")
100.00	SQYD	GEOTEXTILE (EROSION CONTROL)
555.00	LNFT	SILT FENCE
1.00	LS	SWPPP DESIGN
15.00	EACH	SWPPP INSPECTION
20.00	EACH	WATER POLLUTION CONTROL MANAGER
1,710.00	LBS.	MULCHING TACKING SLURRY
5.70	TON	MULCHING
1.00	MGAL	WATER (EROSION CONTROL) (SET PRICE)
410.00	LBS.	FERTILIZER (13-13-13)
154.40	LBS.	FERTILIZER (15-30-15)
3.90	LBS.	SEED (BIG BLUESTEM GRASS) (KAW)
1.00	LBS.	SEED (BLUE GRAMA GRASS) (LOVINGTON)
9.20	LBS.	SEED (BUFFALO GRASS) (TREATED)
19.30	LBS.	SEED (CANADA WILD-RYE)
3.90	LBS.	SEED (INDIANGRASS) (OSAGE)
3.90	LBS.	SEED (LITTLE BLUESTEM GRASS) (ALDOUS)
92.30	LBS.	SEED (RYEGRASS) (PERENNIAL)
5.30	LBS.	SEED (PRAIRIE JUNE GRASS)
25.10	LBS.	SEED (SIDE OATS GRAMA) (EL RENO)
19.30	LBS.	SEED (STERILE WHEATGRASS)
1.40	LBS.	SEED (SWITCHGRASS) (BLACKWELL)
1.00	LBS.	SEED (TALL DROP)
92.30	LBS.	SEED (FESCUE) (TALL) (ENDOPHYTE-FREE)
20.00	LBS.	SEED (WESTERN WHEATGRASS) (BARTON)
19.90	LBS.	SEED (NATIVE WILDFLOWER MIX 1)

*** END OF CONTRACT ***

SUMMARY OF QUANTITIES

DATE: 08/21/2019

LETTING DATE: September 18, 2019

TIME: 02:50pm

519092424 STATE PROJECT NO: U069-019 KA 1554-03 DBE GOAL: 5.0%
 WORKING DAYS: 385 COMPLETION DATE:
 COUNTY: CRAWFORD
 GRADING, BRIDGE AND SURFACING. US-69 FR .2 MI N OF US-69/K-47 JCT N TO 3 MI
 N OF ARMA N CL IN CRAWFORD CO. LENGTH IS 5.29 MI.

QUANTITY	UNIT	ITEM DESCRIPTION
1.00	LS	CONTRACTOR CONSTRUCTION STAKING
1.00	EACH	FIELD OFFICE AND LABORATORY (TYPE A)
3,500.00	HOUR	TRAINEES HIGHWAY CONSTRUCTION (SET PRICE)
1.00	CUYD	FOUNDATION STABILIZATION (SET PRICE)
1.00	LS	MOBILIZATION
1.00	LS	MOBILIZATION (DBE)
1.00	LS	REMOVAL OF EXISTING STRUCTURES
1.00	LS	MAINTENANCE AND RESTORATION OF HAUL ROADS (SET PRICE)
1.00	CUYD	CONCRETE FOR SEAL COURSE (SET PRICE)
1.00	LS	CURING ENVIRONMENT
1.00	HOUR	FLAGGER (SET PRICE)
1.00	LS	CLEANING EXISTING STRUCTURE
337.00	CUYD	FOUNDATION STABILIZATION
457.00	CUYD	GRANULAR BACKFILL (WINGWALLS)
1.00	LS	CLEARING AND GRUBBING
192,148.00	CUYD	COMMON EXCAVATION (RURAL LARGE)
125,062.00	CUYD	COMMON EXCAVATION (CONTRACTOR FURNISHED)
70,535.00	CUYD	ROCK EXCAVATION
33,033.00	CUYD	ROCK EXCAVATION (NON-DURABLE SHALE)
92,924.00	CUYD	COMPACTION OF EARTHWORK (TYPE AA) (MR-0-5)
2,049.00	CUYD	COMPACTION OF EARTHWORK (TYPE AA) (MR-5-5)
208,930.00	CUYD	COMPACTION OF EARTHWORK (TYPE A) (MR-5-5)
1.00	MGAL	WATER (GRADING) (SET PRICE)
447,178.00	SQYD	SALVAGED TOPSOIL
680.60	CUYD	CONCRETE (GRADE 4.0) (RCB)
142.00	CUYD	CONCRETE (GRADE 4.0) (AE) (RCB)
42,410.00	LBS.	REINFORCING STEEL (GRADE 60)
57,800.00	LBS.	REINFORCING STEEL (GRADE 60) (EPOXY COATED)
792.00	SQYD	BRIDGE BACKWALL PROTECTION SYSTEM
4,351.00	LNFT	CROSS ROAD PIPE (15") (RCP)
2,972.00	LNFT	CROSS ROAD PIPE (18") (RCP)
94.00	LNFT	CROSS ROAD PIPE (18") (CAP)
146.00	LNFT	CROSS ROAD PIPE (24") (RCP)
304.00	LNFT	CROSS ROAD PIPE (24")
78.00	LNFT	CROSS ROAD PIPE (30") (RCP)
82.00	LNFT	CROSS ROAD PIPE (30")
474.00	LNFT	CROSS ROAD PIPE (3.0 SQ.FT.) (RCPHE)
63.00	EACH	END SECTION (15") (RC)
2.00	EACH	END SECTION (15")
2.00	EACH	END SECTION (15") (TYPE IV)
31.00	EACH	END SECTION (18") (RC)
4.00	EACH	END SECTION (24") (RC)
8.00	EACH	END SECTION (24")
2.00	EACH	END SECTION (24") (TYPE IV)
2.00	EACH	END SECTION (30")
1.00	EACH	END SECTION (42") (RC)

KANSAS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

LETTING DATE: September 18, 2019

DATE: 08/21/2019
TIME: 02:50pm

519092424 CONT...

QUANTITY	UNIT	ITEM DESCRIPTION
1.00	EACH	END SECTION (48") (RC)
10.00	EACH	END SECTION (3.0 SQ.FT.) (TYPE IV)
66.00	LNFT	ENTRANCE PIPE (15") (RCP)
20.00	LNFT	ENTRANCE PIPE (15")
68.00	LNFT	ENTRANCE PIPE (24") (RCP)
45.00	LNFT	ENTRANCE PIPE (24")
524.00	SQYD	RIPRAP (LIGHT STONE) (100 LB)
665.00	SQYD	RIPRAP (LIGHT STONE) (200 LB)
161.00	SQYD	RIPRAP (HEAVY STONE) (1/4 TON)
30.00	SQYD	RIPRAP (HEAVY STONE)
812.50	LNFT	GUARDRAIL, STEEL PLATE (MGS)
903.25	LNFT	GUARDRAIL, REMOVAL OF STEEL PLATE
40.00	EACH	INLET (TYPE I DITCH)
10.00	EACH	INLET (TYPE II DITCH)
40.00	EACH	INLET (GUTTER)
6.00	EACH	INLET (MANHOLE) (SPECIAL)
12.00	EACH	CONCRETE HEADWALL
2.00	EACH	MANHOLE (REINFORCED CONCRETE)
4,063.00	LNFT	GUTTERS (AE)
346.00	LNFT	SLOTTED DRAIN (15")
780.00	LNFT	SLOTTED DRAIN (18")
5,964.00	SQYD	CONCRETE DITCH LINING
385.00	TON	AGGREGATE DITCH LINING (6")
6.00	LNFT	STORM SEWER (15") (RCP)
525.00	LNFT	STORM SEWER (24") (RCP)
398.00	LNFT	STORM SEWER (30") (RCP)
82.00	LNFT	STORM SEWER (42") (RCP)
96.00	LNFT	STORM SEWER (48") (RCP)
308.00	LNFT	STORM SEWER (10.0 SQ.FT.) (RCPHE)
1.00	CUYD	TEMPORARY SURFACING MATERIAL (AGGREGATE) (SET PRICE)
862.00	LNFT	6" PIPE UNDERDRAINS (FH)
742.00	LNFT	6" PIPE UNDERDRAINS (GK)
3.00	EACH	BARRICADE (TYPE III) (FIXED)
1.00	EACH	MAILBOX INSTALLATION (SET PRICE)
10.60	PMPS	MOWING
8.00	EACH	MONUMENT BOX
129.00	EACH	RIGHT-OF-WAY SURVEY MONUMENT
19.00	EACH	GUIDEPOSTS
5.00	EACH	GUARDRAIL END TERMINAL (MGS-SRT)
5.00	EACH	GUARDRAIL END TERMINAL (MGS-FLEAT)
18,375.00	LBS.	TEMPORARY FERTILIZER (15-30-15)
2,450.00	LBS.	TEMPORARY SEED (CANADA WILD RYE)
5,312.50	LBS.	TEMPORARY SEED (GRAIN OATS)
5,312.50	LBS.	TEMPORARY SEED (STERILE WHEATGRASS)
439.60	LBS.	SOIL EROSION MIX
6,010.00	SQYD	EROSION CONTROL (CLASS 1) (TYPE C)
13,555.00	SQYD	EROSION CONTROL (CLASS 2) (TYPE E)
1.00	CUYD	SEDIMENT REMOVAL (SET PRICE)
1.00	LNFT	TEMPORARY BERM (SET PRICE)
952.00	CUYD	TEMPORARY DITCH CHECK (ROCK)

KANSAS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

LETTING DATE: September 18, 2019

DATE: 08/21/2019
TIME: 02:50pm

519092424 CONT...

QUANTITY	UNIT	ITEM DESCRIPTION
108.00	EACH	TEMPORARY INLET SEDIMENT BARRIER
2,403.00	LNFT	BIODEGRADABLE LOG (9")
3,204.00	LNFT	BIODEGRADABLE LOG (12")
4,240.00	LNFT	BIODEGRADABLE LOG (20")
2,403.00	LNFT	FILTER SOCK (12")
4,218.00	LNFT	FILTER SOCK (18")
68.00	LNFT	SILT FENCE
1.00	LS	SWPPP DESIGN
75.00	EACH	SWPPP INSPECTION
125.00	EACH	WATER POLLUTION CONTROL MANAGER
53,370.00	LBS.	MULCHING TACKING SLURRY
355.50	TON	MULCHING
1.00	MGAL	WATER (EROSION CONTROL) (SET PRICE)
152.00	CUYD	CLASS I EXCAVATION
359.90	CUYD	CONCRETE (GRADE 4.0) (AE) (SA)
135.60	CUYD	CONCRETE (GRADE 4.0) (AE)
93,380.00	LBS.	REINFORCING STEEL (GRADE 60) (EPOXY COATED)
20,760.00	LBS.	REINFORCING STEEL (GRADE 60)
1,020.00	LNFT	PRESTRESSED CONCRETE BEAM (K4)
335.00	LNFT	PILES (STEEL) (HP12X53)
91.00	LNFT	DRILLED SHAFT (42") (CASED)
92.00	SQYD	BRIDGE BACKWALL PROTECTION SYSTEM
42.00	CUYD	ABUTMENT AGGREGATE DRAIN
2,014.00	CUYD	SLOPE PROTECTION (RIPRAP STONE)
1.00	EACH	SONIC TEST (DRILLED SHAFT) (SET PRICE)
89.00	LNFT	CORE HOLE (INVESTIGATIVE)
877.00	SQYD	BRIDGE DECK GROOVING
10.00	SQYD	AREA PREPARED FOR PATCHING
5.00	SQYD	AREA PREPARED FOR PATCHING (FULL DEPTH)
1.00	LBS.	REINFORCING STEEL (REPAIR) (GRADE 60) (EPOXY) (SET PRICE)
1,038.00	SQYD	MULTI-LAYER POLYMER CONCRETE OVERLAY
122,575.00	SQYD	CEMENT TREATED BASE
122,575.00	SQYD	QUALITY CONTROL TESTING (CTB)
122,575.00	SQYD	ASPHALT TREATED BASE
26,705.00	TON	QUALITY CONTROL TESTING (HMA)
1.00	EACH	FIELD OFFICE AND LABORATORY (TYPE A)
1.00	EACH	ASPHALT CORE (SET PRICE)
1.00	LS	ASPHALT AIR VOID PAY ADJUSTMENT
1.00	LS	ASPHALT DENSITY PAY ADJUSTMENT
107,085.00	SQYD	CONCRETE PAVEMENT (9" UNIFORM) (AE) (NRDJ)
622.00	SQYD	CONCRETE PAVEMENT (10" UNIFORM) (AE) (BR APP)
56,093.00	SQYD	CONCRETE PAVEMENT (6" UNIFORM) (AE) (PLAIN)
73.40	CUYD	BRIDGE APPROACH SLAB FOOTING
163,178.00	SQYD	QUALITY CONTROL TESTING (PCCP)
1.00	EACH	CONCRETE CORE (SET PRICE)
1.00	LS	CONCRETE PAVEMENT COMPOSITE PAY ADJUSTMENT
1.00	LS	CONCRETE PAVEMENT SMOOTHNESS
6,276.00	TON	PAVEMENT EDGE WEDGE (ROCK)
1.00	MGAL	WATER (EARTHWORK COMPACTION) (SET PRICE)
1,517.00	TON	LIME

KANSAS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

LETTING DATE: September 18, 2019

DATE: 08/21/2019
TIME: 02:50pm

519092424 CONT...

QUANTITY	UNIT	ITEM DESCRIPTION
1.00	MGAL	WATER (TREATED SUBGRADE) (SET PRICE)
122,575.00	SQYD	MANIPULATION (LIME TREATED SUBGRADE)
56,093.00	SQYD	GRANULAR BASE (7")
1.00	MGAL	WATER (GRANULAR BASE) (SET PRICE)
7,300.00	TON	HMA OVERLAY (SR-12.5A) (PG 70-28)
1,678.00	TON	HMA OVERLAY (SR-12.5A) (PG 64-22)
1,114.00	TON	HMA OVERLAY (SR-12.5A) (PG 64-22) (SHOULDER)
2,645.00	TON	HMA OVERLAY (SR-12.5A) (PG 58-28) (SHOULDER)
7,993.00	TON	HMA-COMMERCIAL GRADE (CLASS A)
12,737.00	TON	QUALITY CONTROL TESTING (HMA)
14.00	TON	EMULSIFIED ASPHALT (SS-1HP)
1.00	EACH	ASPHALT CORE (SET PRICE)
1.00	EACH	FIELD OFFICE AND LABORATORY (TYPE A)
1.00	LS	ASPHALT DENSITY PAY ADJUSTMENT
1.00	LS	ASPHALT AIR VOID PAY ADJUSTMENT
1.00	LS	ASPHALT PAVEMENT SMOOTHNESS
6,661.00	TON	MILLING
116.00	TON	LIME
1.00	MGAL	WATER (LIME TREATED SUBGRADE) (SET PRICE)
9,367.00	SQYD	MANIPULATION (LIME TREATED SUBGRADE)
17,356.00	SQYD	AGGREGATE BASE (AB-3) (6")
2,258.00	TON	SURFACING MATERIAL (SA-1)
9.00	TON	CALCIUM CHLORIDE
1.00	MGAL	WATER (AGGREGATE BASE) (SET PRICE)
56,699.00	LNFT	FENCE (SINGLE WIRE CABLE)
169.00	EACH	POSTS (CORNER) (SINGLE WIRE CABLE)
68.00	EACH	POSTS (END) (SINGLE WIRE CABLE)
33.00	EACH	POSTS (PULL) (SINGLE WIRE CABLE)
1,274.00	SQFT	SIGN (FLAT SHEET) (HIGH PERFORMANCE)
1,079.00	SQFT	SIGN (REINFORCED PANEL) (HIGH PERFORMANCE)
1,447.00	LNFT	SIGN POST (4" X 6" WOOD) (FLAT SHEET SIGN)
56.00	LNFT	SIGN POST (2 LB/FT "U" STEEL)
449.00	LNFT	SIGN POST (W 6 X 9 STEEL BEAM)
40.00	EACH	SIGN POST STUB AND BREAKAWAY BASE PLATE (W 6 X 9)
40.00	EACH	SIGN POST BREAKAWAY BASE PLATE (W 6 X 9)
240.00	LNFT	SIGN POST FOOTING (24" STEEL BEAM POST CONCRETE)
4.00	EACH	SIGNING OBJECT MARKER (TYPE 2)
5.00	EACH	SIGNING DELINEATOR (TYPE A) (WHITE RIGID "U" POST)
53.00	EACH	SIGNING DELINEATOR (TYPE B) (WHITE RIGID "U" POST)
55.00	EACH	SIGNING DELINEATOR (TYPE B) (YELLOW RIGID "U" POST)
79,607.00	LNFT	PAVEMENT MARKING (MULTI-COMPONENT) (WHITE) (6")
498.00	LNFT	PAVEMENT MARKING (MULTI-COMPONENT) (YELLOW) (4")
52,761.00	LNFT	PAVEMENT MARKING (MULTI-COMPONENT) (YELLOW) (6")
98.00	LNFT	PAVEMENT MARKING (INTERSECTION GRADE) (WHITE) (24")
39.00	EACH	PAVEMENT MRK SYM (INTERSECTION GRADE) (WHITE) (LEFT ARROW)
28.00	EACH	PAVEMENT MRK SYM (INTERSECTION GRADE) (WHITE) (RT ARROW)
1.00	EACH	PAVEMENT MRK SYM (INTERSECTION GRADE)(WHITE)MERGE LEFT ARROW
111,720.00	LNFT	PAVEMENT MARKING REMOVAL
9,300.00	LBS.	FERTILIZER (13-13-13)
6,080.00	LBS.	FERTILIZER (15-30-15)

KANSAS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

LETTING DATE: September 18, 2019

DATE: 08/21/2019
TIME: 02:50pm

519092424 CONT...

QUANTITY	UNIT	ITEM DESCRIPTION
152.00	LBS.	SEED (BIG BLUESTEM GRASS) (KAW)
23.30	LBS.	SEED (BLUE GRAMA GRASS) (LOVINGTON)
209.30	LBS.	SEED (BUFFALO GRASS) (TREATED)
760.00	LBS.	SEED (CANADA WILD-RYE)
152.00	LBS.	SEED (INDIANGRASS) (OSAGE)
152.00	LBS.	SEED (LITTLE BLUESTEM GRASS) (ALDOUS)
2,092.50	LBS.	SEED (RYEGRASS) (PERENNIAL)
120.90	LBS.	SEED (PRAIRIE JUNE GRASS)
771.80	LBS.	SEED (SIDE OATS GRAMA) (EL RENO)
760.00	LBS.	SEED (STERILE WHEATGRASS)
53.20	LBS.	SEED (SWITCHGRASS) (BLACKWELL)
38.00	LBS.	SEED (TALL DROP)
2,092.50	LBS.	SEED (FESCUE) (TALL) (ENDOPHYTE-FREE)
583.00	LBS.	SEED (WESTERN WHEATGRASS) (BARTON)
782.80	LBS.	SEED (NATIVE WILDFLOWER MIX 1)
18,560.00	EADA	WORK ZONE SIGNS (0 TO 9.25 SQ.FT.)
75,400.00	EADA	WORK ZONE SIGNS (9.26 TO 16.25 SQ.FT.)
6,380.00	EADA	WORK ZONE SIGNS (16.26 SQ.FT. & OVER)
85,840.00	EADA	WORK ZONE BARRICADES (TYPE 3 - 4 TO 12 LIN. FT.)
116,000.00	EADA	CHANNELIZER (PORTABLE)
141,520.00	EADA	WORK ZONE WARNING LIGHT (TYPE "A" LOW INTENSITY)
8,120.00	EADA	WORK ZONE WARNING LIGHT (RED TYPE "B" HIGH INTENSITY)
1,160.00	EADA	ARROW DISPLAY
1,164.00	STAL	PAVEMENT MARKING (TEMP) 4" SOLID (TYPE I)
40.00	STAL	PAVEMENT MARKING (TEMP) 4" SOLID (TYPE II)
2.00	EACH	INERTIAL BARRIER SYSTEM (TL-3)
15.00	EACH	REPLACEMENT MODULES (IBS)
525.00	LNFT	CONCRETE SAFETY BARRIER (TYPE F3) (TEMPORARY)
30,000.00	LNFT	PAVEMENT MARKING REMOVAL
1.00	LS	TRAFFIC CONTROL (INITIAL SETUP)

*** END OF CONTRACT ***

SUMMARY OF QUANTITIES

DATE: 08/21/2019

LETTING DATE: September 18, 2019

TIME: 02:50pm

519092515 STATE PROJECT NO: U281-005 KA 5314-01 DBE GOAL: 3.5%
 WORKING DAYS: 45 COMPLETION DATE:
 COUNTY: BARTON
 SURFACE RECYCLE, UBAS AND CHIP SEAL. U281, FR SF/BT CO LI TO SCL OF
 GREAT BEND IN BT CO. LENGTH IS 6.586 MI. STATE TIE KA 5312-01.

QUANTITY	UNIT	ITEM DESCRIPTION
1.00	LS	MOBILIZATION
1.00	LS	MOBILIZATION (DBE)
1.00	EACH	FIELD OFFICE AND LABORATORY (TYPE A)
1.00	TON	MATERIAL FOR HMA PATCHING (SET PRICE)
1.00	LS	TRAFFIC CONTROL
1.00	HOUR	FLAGGER (SET PRICE)
133.00	SQYD	MILLING
3,051.00	TON	HMA SURFACE (ULTRATHIN BONDED) (TYPE A) (PG 70-28)
85.00	TON	EMULSIFIED ASPHALT (EMULSION BONDING LIQUID)
3,051.00	TON	QUALITY CONTROL TESTING (HMA)
348.00	STA.	SURFACE RECYCLING (1.5")
101.00	TON	ASPHALT REJUVENATING AGENT
142.00	TON	EMULSIFIED ASPHALT (CRS-1HP) (SEAL)
348.00	STA.	MANIPULATION (CHIP SEAL)
665.00	CUYD	COVER MATERIAL (CM-L-2)
1.00	MGAL	WATER (FLEXIBLE PAVEMENT) (SET PRICE)
390.00	STAL	PAVEMENT MARKING (TEMP) 4" BROKEN (3')(TYPE I)
737.00	STAL	PAVEMENT MARKING (TEMP) 4" BROKEN (3')(TYPE II)
1.00	LS	SURFACE RECYCLING PAY ADJUSTMENT
3.00	TON	EMULSIFIED ASPHALT (SS-1HP)
327.00	STA.	RUMBLE STRIPS (MILLED) (ASPHALT) (CENTERLINE)
25,306.00	LNFT	PAVEMENT MARKING (THERMOPLASTIC) (YELLOW) (4")
70,780.00	LNFT	PAVEMENT MARKING (THERMOPLASTIC) (WHITE) (6")

*** END OF CONTRACT ***

SUMMARY OF QUANTITIES

DATE: 08/21/2019

LETTING DATE: September 18, 2019

TIME: 02:50pm

519092525 STATE PROJECT NO: 008 N 0655-01 DBE GOAL: 10.0%
 WORKING DAYS: 220 COMPLETION DATE:
 COUNTY: BUTLER
 GRADING, BRIDGE & SURFACING. ANDOVER: 159TH ST E BR OVER I-35/KTA &
 159TH ST E FR KTA TO CENTRAL IN BUTLER CO. LENGTH IS 0.992 MI.

QUANTITY	UNIT	ITEM DESCRIPTION
1.00	LS	CONTRACTOR CONSTRUCTION STAKING
1.00	EACH	FIELD OFFICE AND LABORATORY (TYPE A)
1.00	LS	MOBILIZATION
1.00	LS	MOBILIZATION (DBE)
1.00	LS	REMOVAL OF EXISTING STRUCTURES
1.00	CUYD	FOUNDATION STABILIZATION (SET PRICE)
1.00	CUYD	CONCRETE FOR SEAL COURSE (SET PRICE)
1.00	LS	CURING ENVIRONMENT
1.00	HOUR	FLAGGER (SET PRICE)
1.00	LS	CLEARING AND GRUBBING
1.00	LS	CLEANING EXISTING STRUCTURE
7,552.00	CUYD	COMMON EXCAVATION (URB)
11,908.00	CUYD	COMMON EXCAVATION (URB)
11,549.00	CUYD	COMMON EXCAVATION (CONTRACTOR FURNISHED)
480.00	CUYD	COMMON EXCAVATION (CONTRACTOR FURNISHED)
1,121.00	CUYD	ROCK EXCAVATION
1,996.00	CUYD	ROCK EXCAVATION
16,236.00	CUYD	COMPACTION OF EARTHWORK (TYPE AA) (MR-0-5)
1,353.00	CUYD	COMPACTION OF EARTHWORK (TYPE AA) (MR-0-5)
1,297.00	CUYD	TOPSOIL
886.00	CUYD	TOPSOIL
1.00	MGAL	WATER (GRADING) (SET PRICE)
10.00	EACH	INLET (TYPE 22 CURB)
14.00	EACH	INLET (TYPE 22 CURB)
1.00	EACH	INLET (DROP)
7.00	EACH	INLET (DRAINAGE) (SPECIAL)
1.00	EACH	MANHOLE (REINFORCED CONCRETE)
1.00	EACH	ADJUSTMENT OF CURB INLETS
105.00	CUYD	SLOPE PROTECTION (RIPRAP STONE)
219.00	TON	AGGREGATE DITCH LINING (4")
349.00	LNFT	STORM SEWER (18")
309.00	LNFT	STORM SEWER (18")
414.00	LNFT	STORM SEWER (18") (RCP)
115.00	LNFT	STORM SEWER (18") (RCP)
52.00	LNFT	STORM SEWER (24")
322.00	LNFT	STORM SEWER (24")
438.00	LNFT	STORM SEWER (30")
382.00	LNFT	STORM SEWER (30") (RCP)
2.00	EACH	END SECTION (18")
1.00	EACH	END SECTION (24")
306.00	LNFT	CROSS ROAD PIPE (36") (RCP)
54.00	LNFT	ENTRANCE PIPE (12") (RCP)
100.00	LNFT	ENTRANCE PIPE (12") (CSP)
2.00	EACH	END SECTION (12") (RC)
3.00	EACH	END SECTION (36") (RC)
1.00	EACH	END SECTION (12") (CS)

KANSAS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

LETTING DATE: September 18, 2019

DATE: 08/21/2019
TIME: 02:50pm

519092525 CONT...

QUANTITY	UNIT	ITEM DESCRIPTION
1.00	EACH	RESETTING END SECTION
1,695.00	SQYD	SIDEWALK CONSTRUCTION (6") (AE)
4,671.00	SQYD	SIDEWALK CONSTRUCTION (6") (AE)
40.00	SQYD	SIDEWALK RAMP
147.00	SQYD	SIDEWALK RAMP
1.00	CUYD	TEMPORARY SURFACING MATERIAL (AGGREGATE) (SET PRICE)
1.00	EACH	MAILBOX INSTALLATION (SET PRICE)
28.00	LNFT	HANDRAIL (METAL) (4'- 6")
4.00	EACH	ADJUSTMENT OF VALVE BOX (WATER)
1.00	LS	ADJUSTMENT OF EXISTING STRUCTURES
2.90	CUYD	FLOWABLE FILL (LOW STRENGTH)
1.00	LS	TRANSPORTING SALVAGEABLE MATERIAL
478.50	LNFT	GUARDRAIL, REMOVAL OF STEEL PLATE
5,564.00	SQFT	RETAINING WALL (MSEW)
435.00	LBS.	TEMPORARY FERTILIZER (16-20- 0)
255.00	LBS.	TEMPORARY FERTILIZER (16-20- 0)
58.00	LBS.	TEMPORARY SEED (CANADA WILD RYE)
34.00	LBS.	TEMPORARY SEED (CANADA WILD RYE)
130.50	LBS.	TEMPORARY SEED (GRAIN OATS)
76.50	LBS.	TEMPORARY SEED (GRAIN OATS)
130.50	LBS.	TEMPORARY SEED (STERILE WHEATGRASS)
76.50	LBS.	TEMPORARY SEED (STERILE WHEATGRASS)
3.30	LBS.	SOIL EROSION MIX
150.00	SQYD	EROSION CONTROL (CLASS 1) (TYPE D)
1.00	CUYD	SEDIMENT REMOVAL (SET PRICE)
1.00	LNFT	TEMPORARY BERM (SET PRICE)
1.00	EACH	TEMPORARY INLET SEDIMENT BARRIER
120.00	LNFT	BIODEGRADABLE LOG (20")
144.00	LNFT	FILTER SOCK (8")
264.00	LNFT	FILTER SOCK (8")
1,800.00	LNFT	SILT FENCE
2,100.00	LNFT	SILT FENCE
1.00	LS	SWPPP DESIGN
40.00	EACH	SWPPP INSPECTION
65.00	EACH	WATER POLLUTION CONTROL MANAGER
2,610.00	LBS.	MULCHING TACKING SLURRY
1,530.00	LBS.	MULCHING TACKING SLURRY
8.70	TON	MULCHING
5.10	TON	MULCHING
1.00	MGAL	WATER (EROSION CONTROL) (SET PRICE)
184.10	CUYD	CONCRETE (GRADE 4.0) (AE)
432.50	CUYD	CONCRETE (GRADE 4.0) (AE) (SA)
145,970.00	LBS.	REINFORCING STEEL (GRADE 60) (EPOXY COATED)
2,020.00	LBS.	STRUCTURAL STEEL (A709) (GR 36)
123,305.00	LBS.	STRUCTURAL STEEL (A709) (GR 50W)
150,644.00	LBS.	STRUCTURAL STEEL (M270) (GR 50WT3)
3,200.00	EACH	WELDED STUD SHEAR CONNECTORS
8.00	EACH	BEARING (STEEL REINFORCED ELASTOMERIC)
539.00	LNFT	PILES (STEEL) (HP12X53)
97.00	LNFT	TEST PILES (SPECIAL) (HP12X53)

KANSAS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

LETTING DATE: September 18, 2019

DATE: 08/21/2019
TIME: 02:50pm

519092525 CONT...

QUANTITY	UNIT	ITEM DESCRIPTION
16.00	EACH	CAST STEEL PILE POINTS
151.00	LNFT	DRILLED SHAFT (66") (CASED)
1.00	EACH	SONIC TEST (DRILLED SHAFT) (SET PRICE)
46.00	LNFT	CORE HOLE (INVESTIGATIVE)
357.00	CUYD	ABUTMENT AGGREGATE DRAIN
153.00	SQYD	BRIDGE BACKWALL PROTECTION SYSTEM
26.00	CUYD	SLOPE PROTECTION (AGGREGATE)
1.00	LS	FALSEWORK INSPECTION
884.00	SQYD	BRIDGE DECK GROOVING
180.00	LNFT	BRIDGE HANDRAIL (METAL) (0'-10")
180.00	LNFT	FENCE (CHAIN LINK) (6'-0") (SPECIAL)
2,282.00	LNFT	CURB AND GUTTER, COMBINED (AE)
3,142.00	LNFT	CURB AND GUTTER, COMBINED (AE)
106.00	LNFT	CURB, EDGE (8.0") (AE)
275.00	LNFT	GUTTERS (AE)
195.00	SQYD	CONCRETE PAVEMENT (6" UNIFORM) (AE)
852.00	SQYD	CONCRETE PAVEMENT (8" UNIFORM) (AE)
1,680.00	SQYD	CONCRETE PAVEMENT (8" UNIFORM) (AE)
4,538.00	SQYD	CONCRETE PAVEMENT (9" UNIFORM) (AE) (NRDJ)
7,080.00	SQYD	CONCRETE PAVEMENT (9" UNIFORM) (AE) (NRDJ)
541.00	SQYD	CONCRETE PAVEMENT (10" UNIFORM) (AE) (BR APP)
6,859.00	SQYD	AGGREGATE BASE (AB-3) (8")
11,979.00	SQYD	AGGREGATE BASE (AB-3) (8")
1.00	MGAL	WATER (AGGREGATE BASE) (SET PRICE)
63.40	CUYD	BRIDGE APPROACH SLAB FOOTING
102.00	LNFT	CONCRETE SAFETY BARRIER (TYPE IV) (SPECIAL)
1.00	LS	CONCRETE PAVEMENT SMOOTHNESS
1.00	EACH	CONCRETE CORE (SET PRICE)
4,538.00	SQYD	QUALITY CONTROL TESTING (PCCP)
7,080.00	SQYD	QUALITY CONTROL TESTING (PCCP)
1.00	LS	CONCRETE PAVEMENT COMPOSITE PAY ADJUSTMENT
627.00	TON	HMA-COMMERCIAL GRADE (CLASS A)
226.00	TON	HMA-COMMERCIAL GRADE (CLASS A)
1.00	EACH	FIELD OFFICE AND LABORATORY (TYPE A)
444.00	LNFT	FENCE (WOVEN WIRE) (TYPE B)
5.00	EACH	POSTS (CORNER) (WOVEN WIRE TYPE B)
8.00	EACH	POSTS (END) (WOVEN WIRE TYPE B)
3.00	EACH	POSTS (PULL) (WOVEN WIRE TYPE B)
47.20	SQFT	SIGN (FLAT SHEET) (HIGH PERFORMANCE)
99.60	SQFT	SIGN (FLAT SHEET) (HIGH PERFORMANCE)
165.00	LNFT	SIGN POST (2-1/4" PERFORATED SQUARE STEEL TUBE)
183.00	LNFT	SIGN POST (2-1/4" PERFORATED SQUARE STEEL TUBE)
16.00	EACH	SIGN POST FOOTING (2-1/4" PERFORATED SQUARE STEEL TUBE)
16.00	EACH	SIGN POST FOOTING (2-1/4" PERFORATED SQUARE STEEL TUBE)
1.00	LS	SIGN (REMOVE AND RESET)
940.00	LNFT	PAVEMENT MARKING (MULTI-COMPONENT) (WHITE) (6")
1,073.00	LNFT	PAVEMENT MARKING (MULTI-COMPONENT) (WHITE) (6")
3,305.00	LNFT	PAVEMENT MARKING (MULTI-COMPONENT) (YELLOW) (4")
4,170.00	LNFT	PAVEMENT MARKING (MULTI-COMPONENT) (YELLOW) (4")
360.00	LNFT	PAVEMENT MARKING (MULTI-COMPONENT) (YELLOW) (6")

SUMMARY OF QUANTITIES

DATE: 08/21/2019

LETTING DATE: September 18, 2019

TIME: 02:50pm

519092525 CONT...

QUANTITY	UNIT	ITEM DESCRIPTION
21.00	LNFT	PAVEMENT MARKING (MULTI-COMPONENT) (YELLOW) (12")
573.00	LNFT	PAVEMENT MARKING (INTERSECTION GRADE) (WHITE) (24")
8.00	EACH	PAVEMENT MRK SYM (INTERSECTION GRADE) (WHITE) (LEFT ARROW)
19.00	EACH	PAVEMENT MRK SYM (INTERSECTION GRADE) (WHITE) (LEFT ARROW)
9.00	EACH	PAVEMENT MRK SYM (INTERSECTION GRADE) (WHITE) (RT ARROW)
1,168.00	LNFT	PAVEMENT MARKING REMOVAL
1.00	LS	TRAFFIC SIGNAL
280.00	LBS.	FERTILIZER (13-13-13)
339.00	LBS.	FERTILIZER (16-20- 0)
507.00	LBS.	FERTILIZER (16-20- 0)
3.00	LBS.	SEED (BLUE GRAMA GRASS) (LOVINGTON)
1.80	LBS.	SEED (BLUE GRAMA GRASS) (LOVINGTON)
42.30	LBS.	SEED (BUFFALO GRASS) (TREATED)
28.00	LBS.	SEED (BUFFALO GRASS) (TREATED)
63.00	LBS.	SEED (RYEGRASS) (PERENNIAL)
3.60	LBS.	SEED (PRAIRIE JUNE GRASS)
8.80	LBS.	SEED (SIDE OATS GRAMA) (EL RENO)
63.00	LBS.	SEED (FESCUE) (TALL) (ENDOPHYTE-FREE)
8.40	LBS.	SEED (WESTERN WHEATGRASS) (BARTON)
2,950.00	SQYD	SOD (TALL TURF TYPE FESCUE) (STRIPS)
5,178.00	SQYD	SOD (TALL TURF TYPE FESCUE) (STRIPS)
16,740.00	EADA	WORK ZONE SIGNS (0 TO 9.25 SQ.FT.)
20,460.00	EADA	WORK ZONE SIGNS (9.26 TO 16.25 SQ.FT.)
18,600.00	EADA	WORK ZONE BARRICADES (TYPE 3 - 4 TO 12 LIN. FT.)
1,240.00	EADA	WORK ZONE BARRICADES (PEDESTRIAN)
24,180.00	EADA	CHANNELIZER (FIXED)
46,500.00	EADA	CHANNELIZER (PORTABLE)
9,300.00	EADA	WORK ZONE WARNING LIGHT (TYPE "A" LOW INTENSITY)
2,170.00	EADA	WORK ZONE WARNING LIGHT (RED TYPE "B" HIGH INTENSITY)
620.00	EADA	ARROW DISPLAY
620.00	EADA	PORTABLE CHANGEABLE MESSAGE SIGN
168.40	STAL	PAVEMENT MARKING (TEMP) 4" SOLID (TYPE I)
220.00	LNFT	PAVEMENT MARKING REMOVAL
1.00	LS	TRAFFIC SIGNAL INSTALLATION (TEMPORARY)
1.00	LS	TRAFFIC CONTROL (INITIAL SETUP)
1,625.00	LNFT	CONCRETE SAFETY BARRIER (TYPE F3) (TEMPORARY)
600.00	LNFT	CONCRETE SAFETY BARRIER (TYPE F3) (TEMPORARY - RELOCATE)
2.00	EACH	IMPACT ATTENUATOR (TEMPORARY)
18.00	EACH	REPLACEMENT MODULES (IMPACT ATTENUATOR)

*** END OF CONTRACT ***

SUMMARY OF QUANTITIES

DATE: 08/21/2019

LETTING DATE: September 18, 2019

TIME: 02:50pm

519092545 STATE PROJECT NO: K061-078 KA 5405-01 DBE GOAL: 0.0%
 WORKING DAYS: 30 COMPLETION DATE:
 COUNTY: RENO
 PAVEMENT MARKING. K61, FR N OF K61/E 30TH AVE INTSCT N TO RN/MP CO LI IN
 RN CO. LENGTH IS 8.625 MI.

QUANTITY	UNIT	ITEM DESCRIPTION
1.00	LS	MOBILIZATION
1.00	LS	MOBILIZATION (DBE)
1.00	LS	TRAFFIC CONTROL
1.00	HOUR	FLAGGER (SET PRICE)
91,031.00	LNFT	PAVEMENT MARKING (MULTI-COMPONENT) (WHITE) (6")
6,355.00	LNFT	PAVEMENT MARKING (MULTI-COMPONENT) (WHITE) (8")
1,084.00	LNFT	PAVEMENT MARKING (MULTI-COMPONENT) (WHITE) (12")
4,419.00	LNFT	PAVEMENT MARKING (MULTI-COMPONENT) (YELLOW) (4")
86,339.00	LNFT	PAVEMENT MARKING (MULTI-COMPONENT) (YELLOW) (6")
137.00	LNFT	PAVEMENT MARKING (MULTI-COMPONENT) (YELLOW) (12")
70.00	LNFT	PAVEMENT MARKING (INTERSECTION GRADE) (WHITE) (24")
12.00	EACH	PAVEMENT MRK SYM (INTERSECTION GRADE) (WHITE) (LEFT ARROW)
3.00	EACH	PAVEMENT MRK SYM (INTERSECTION GRADE) (WHITE) (RT ARROW)
189,435.00	LNFT	PAVEMENT MARKING REMOVAL
115.00	STAL	FLEXIBLE RAISED PAVEMENT MARKERS (4" BROKEN (8 FT.))

*** END OF CONTRACT ***

SUMMARY OF QUANTITIES

DATE: 08/21/2019

LETTING DATE: September 18, 2019

TIME: 02:50pm

519092565 STATE PROJECT NO: I135-087 KA 5043-01 DBE GOAL: 0.0%
 WORKING DAYS: 110 COMPLETION DATE:
 COUNTY: SEDGWICK
 BRIDGE REPAIR. BR 012 ON NB I-135 OVER K-15, BNSH RR, CANAL & GROVE ST IN
 WICHITA IN SEDGWICK CO.

QUANTITY	UNIT	ITEM DESCRIPTION
1.00	LS	MOBILIZATION (DBE)
1.00	LS	MOBILIZATION
1.00	LS	REMOVAL OF EXISTING STRUCTURES
1.00	HOUR	FLAGGER (SET PRICE)
135.00	LNFT	EXPANSION JOINT (STRIP SEAL ASSEMBLY)
7.90	CUYD	CONCRETE (GRADE 4.0) (AE) (SA)
940.00	LBS.	REINFORCING STEEL (GRADE 60) (EPOXY COATED)
12.00	EACH	BEARING (STEEL REINFORCED ELASTOMERIC)
1,104.00	SQYD	CONCRETE MASONRY COATING
199.00	SQYD	SUBSTRUCTURE WATERPROOFING MEMBRANE
1,700.00	SQFT	CONCRETE SURFACE REPAIR
1.00	LS	BRIDGE DRAINAGE SYSTEM
1.00	LS	TEMPORARY SHORING
1.00	LBS.	REINFORCING STEEL (REPAIR) (GRADE 60) (SET PRICE)
220.00	SQYD	AREA PREPARED FOR PATCHING
5.00	SQYD	AREA PREPARED FOR PATCHING (FULL DEPTH)
658.00	LNFT	PAVEMENT MARKING (PATTERNED COLD PLASTIC) (WHITE) (6")
2,630.00	LNFT	PAVEMENT MARKING (MULTI-COMPONENT) (WHITE) (6")
2,630.00	LNFT	PAVEMENT MARKING (MULTI-COMPONENT) (YELLOW) (6")
500.00	EADA	WORK ZONE SIGNS (0 TO 9.25 SQ.FT.)
2,640.00	EADA	WORK ZONE SIGNS (9.26 TO 16.25 SQ.FT.)
830.00	EADA	WORK ZONE SIGNS (16.26 SQ.FT. & OVER)
1,490.00	EADA	WORK ZONE BARRICADES (TYPE 3 - 4 TO 12 LIN. FT.)
9,080.00	EADA	CHANNELIZER (PORTABLE)
990.00	EADA	WORK ZONE WARNING LIGHT (TYPE "A" LOW INTENSITY)
170.00	EADA	ARROW DISPLAY
118.50	STAL	PAVEMENT MARKING (TEMP) 4" SOLID (TYPE I)
1,650.00	LNFT	CONCRETE SAFETY BARRIER (TYPE F3) (TEMPORARY)
1,650.00	LNFT	CONCRETE SAFETY BARRIER (TYPE F3) (TEMPORARY - RELOCATE)
1.00	EACH	INERTIAL BARRIER SYSTEM (TL-3)
15.00	EACH	REPLACEMENT MODULES (IBS)
7,960.00	LNFT	PAVEMENT MARKING REMOVAL
1.00	LS	TRAFFIC CONTROL (INITIAL SETUP)

*** END OF CONTRACT ***

SUMMARY OF QUANTITIES

DATE: 08/21/2019
 TIME: 02:50pm

LETTING DATE: September 18, 2019

519092575 STATE PROJECT NO: U281-093 KA 5312-01 DBE GOAL: 3.0%
 WORKING DAYS: 45 COMPLETION DATE:
 COUNTY: STAFFORD
 SURFACE RECYCLE, UBAS AND CHIP SEAL. U281, FR K19 JCT TO SF/BT CO LI IN SF
 CO. LENGTH IS 7.086 MI. STATE TIE KA 5314-01.

QUANTITY	UNIT	ITEM DESCRIPTION
1.00	LS	MOBILIZATION
1.00	LS	MOBILIZATION (DBE)
1.00	EACH	FIELD OFFICE AND LABORATORY (TYPE A)
1.00	TON	MATERIAL FOR HMA PATCHING (SET PRICE)
1.00	LS	TRAFFIC CONTROL
1.00	HOUR	FLAGGER (SET PRICE)
133.00	SQYD	MILLING
3,051.00	TON	HMA SURFACE (ULTRATHIN BONDED) (TYPE A) (PG 70-28)
85.00	TON	EMULSIFIED ASPHALT (EMULSION BONDING LIQUID)
3,051.00	TON	QUALITY CONTROL TESTING (HMA)
348.00	STA.	SURFACE RECYCLING (1.5")
101.00	TON	ASPHALT REJUVENATING AGENT
142.00	TON	EMULSIFIED ASPHALT (CRS-1HP) (SEAL)
348.00	STA.	MANIPULATION (CHIP SEAL)
665.00	CUYD	COVER MATERIAL (CM-L-2)
1.00	MGAL	WATER (FLEXIBLE PAVEMENT) (SET PRICE)
390.00	STAL	PAVEMENT MARKING (TEMP) 4" BROKEN (3')(TYPE I)
737.00	STAL	PAVEMENT MARKING (TEMP) 4" BROKEN (3')(TYPE II)
1.00	LS	SURFACE RECYCLING PAY ADJUSTMENT
4.00	TON	EMULSIFIED ASPHALT (SS-1HP)
327.00	STA.	RUMBLE STRIPS (MILLED) (ASPHALT) (CENTERLINE)
25,306.00	LNFT	PAVEMENT MARKING (THERMOPLASTIC) (YELLOW) (4")
70,780.00	LNFT	PAVEMENT MARKING (THERMOPLASTIC) (WHITE) (6")

*** END OF CONTRACT ***

SUMMARY OF QUANTITIES

DATE: 08/21/2019

LETTING DATE: September 18, 2019

TIME: 02:50pm

519092636 STATE PROJECT NO: K096-036 KA 5316-01 DBE GOAL: 3.0%
 WORKING DAYS: 55 COMPLETION DATE:
 COUNTY: GREELEY
 HILL AND HMA OVERLAY. K-96 FR KS/CO ST LI TO WCL OF TRIBUNE IN GL CO.
 LENGTH IS 15.631 MI

QUANTITY	UNIT	ITEM DESCRIPTION
1.00	LS	MOBILIZATION
1.00	LS	MOBILIZATION (DBE)
1.00	LS	MAINTENANCE AND RESTORATION OF HAUL ROADS (SET PRICE)
1.00	EACH	FIELD OFFICE AND LABORATORY (TYPE A)
1.00	LS	TRAFFIC CONTROL
1.00	HOUR	FLAGGER (SET PRICE)
14,966.00	TON	MILLING
29,946.00	TON	HMA OVERLAY (SR-12.5A) (PG 64-22)
29,946.00	TON	QUALITY CONTROL TESTING (HMA)
275,372.00	SQYD	EMULSIFIED ASPHALT
1.00	TON	MATERIAL FOR HMA PATCHING (SET PRICE)
1.00	LS	ASPHALT AIR VOID PAY ADJUSTMENT
1.00	LS	ASPHALT DENSITY PAY ADJUSTMENT
1.00	EACH	ASPHALT CORE (SET PRICE)
1.00	EACH	BOND CORE (SET PRICE)
6,190.00	TON	PAVEMENT EDGE WEDGE (ROCK)
1.00	MGAL	WATER (EARTHWORK COMPACTION) (SET PRICE)
825.30	STAL	PAVEMENT MARKING (TEMP) 4" BROKEN (3')(TYPE I)
825.30	STA.	RUMBLE STRIPS (MILLED) (ASPHALT) (CENTERLINE)
165,063.00	LNFT	PAVEMENT MARKING (MULTI-COMPONENT) (WHITE) (6")
20,633.00	LNFT	PAVEMENT MARKING (MULTI-COMPONENT) (YELLOW) (4")

*** END OF CONTRACT ***

SUMMARY OF QUANTITIES

DATE: 08/21/2019
TIME: 02:50pm

LETTING DATE: September 18, 2019

519092646 STATE PROJECT NO: K027-038 KA 5319-01 DBE GOAL: 3.0%
 WORKING DAYS: 55 COMPLETION DATE:
 COUNTY: HAMILTON
 SURFACE RECYCLE AND UBAS. K-27 FR ST/HM CO LI N TO E US50 JCT IN HM CO.
 LENGTH IS 16.865 MI. STATE TIE KA 5315-01

QUANTITY	UNIT	ITEM DESCRIPTION
1.00	LS	MOBILIZATION
1.00	LS	MOBILIZATION (DBE)
1.00	LS	MAINTENANCE AND RESTORATION OF HAUL ROADS (SET PRICE)
1.00	EACH	FIELD OFFICE AND LABORATORY (TYPE A)
1.00	LS	SURFACE RECYCLING PAY ADJUSTMENT
1.00	LS	TRAFFIC CONTROL
1.00	HOUR	FLAGGER (SET PRICE)
1,930.00	TON	MILLING
1,930.00	TON	HMA-COMMERCIAL GRADE (CLASS A)
1.00	TON	MATERIAL FOR HMA PATCHING (SET PRICE)
99.90	STAL	PAVEMENT MARKING (TEMP) 4" BROKEN (3')(TYPE I)
857.20	STA.	SURFACE RECYCLING (2")
418.00	TON	ASPHALT REJUVENATING AGENT
10,089.00	TON	HMA SURFACE (ULTRATHIN BONDED) (TYPE B) (PG 70-28)
10,089.00	TON	QUALITY CONTROL TESTING (HMA)
241.00	TON	EMULSIFIED ASPHALT (EMULSION BONDING LIQUID)
1,714.40	STAL	PAVEMENT MARKING (TEMP) 4" BROKEN (3')(TYPE II)
857.20	STAL	FLEXIBLE RAISED PAVEMENT MARKERS (4" BROKEN (3 FT.))
857.20	STA.	RUMBLE STRIPS (MILLED) (ASPHALT) (CENTERLINE)
173,105.00	LNFT	PAVEMENT MARKING (THERMOPLASTIC) (WHITE) (6")
43,401.00	LNFT	PAVEMENT MARKING (THERMOPLASTIC) (YELLOW) (4")
48.00	LNFT	PAVEMENT MARKING (THERMOPLASTIC) (WHITE) (24")
50.00	LNFT	PAVEMENT MARKING (THERMOPLASTIC) (YELLOW) (12")
2.00	EACH	PAVEMENT MRK SYM (THERMOPLASTIC) (WHITE) (X-ING)

*** END OF CONTRACT ***

SUMMARY OF QUANTITIES

DATE: 08/21/2019

LETTING DATE: September 18, 2019

TIME: 02:50pm

519092656 STATE PROJECT NO: K027-094 KA 5315-01 DBE GOAL: 2.0%
 WORKING DAYS: 55 COMPLETION DATE:
 COUNTY: STANTON
 SURFACE RECYCLE AND UBAS. K-27 FR 500 FT N OF S US160 JCT N TO ST/HM CO
 LI IN ST CO. LENGTH IS 11.92 MI. STATE TIE KA 5319-01

QUANTITY	UNIT	ITEM DESCRIPTION
1.00	LS	MOBILIZATION
1.00	LS	MOBILIZATION (DBE)
1.00	LS	MAINTENANCE AND RESTORATION OF HAUL ROADS (SET PRICE)
1.00	EACH	FIELD OFFICE AND LABORATORY (TYPE A)
1.00	LS	SURFACE RECYCLING PAY ADJUSTMENT
1.00	LS	TRAFFIC CONTROL
1.00	HOUR	FLAGGER (SET PRICE)
1.00	TON	MATERIAL FOR HMA PATCHING (SET PRICE)
629.40	STA.	SURFACE RECYCLING (2")
307.00	TON	ASPHALT REJUVENATING AGENT
7,381.00	TON	HMA SURFACE (ULTRATHIN BONDED) (TYPE B) (PG 70-28)
7,381.00	TON	QUALITY CONTROL TESTING (HMA)
176.00	TON	EMULSIFIED ASPHALT (EMULSION BONDING LIQUID)
1,258.80	STAL	PAVEMENT MARKING (TEMP) 4" BROKEN (3')(TYPE II)
629.40	STAL	FLEXIBLE RAISED PAVEMENT MARKERS (4" BROKEN (3 FT.))
629.40	STA.	RUMBLE STRIPS (MILLED) (ASPHALT) (CENTERLINE)
125,875.00	LNFT	PAVEMENT MARKING (THERMOPLASTIC) (WHITE) (6")
26,945.00	LNFT	PAVEMENT MARKING (THERMOPLASTIC) (YELLOW) (4")

*** END OF CONTRACT ***

SUMMARY OF QUANTITIES

DATE: 08/21/2019

LETTING DATE: September 18, 2019

TIME: 02:50pm

519094131 STATE PROJECT NO: 075 C 4922-01 DBE GOAL: 1.0%
 WORKING DAYS: 110 COMPLETION DATE:
 COUNTY: POTTAWATOMIE
 GRADING, BRIDGE & SURFACING. 3 MI N OF DULUTH IN POTTAWATOMIE CO.
 LENGTH IS 0.027 MI.

QUANTITY	UNIT	ITEM DESCRIPTION
1.00	LS	REMOVAL OF EXISTING STRUCTURES
1.00	EACH	FIELD OFFICE AND LABORATORY (TYPE C)
1.00	LS	CONTRACTOR CONSTRUCTION STAKING
1.00	LS	MOBILIZATION
1.00	LS	MOBILIZATION (DBE)
1.00	CUYD	FOUNDATION STABILIZATION (SET PRICE)
1.00	CUYD	CONCRETE FOR SEAL COURSE (SET PRICE)
1.00	LS	CURING ENVIRONMENT
1.00	LS	TRAFFIC CONTROL
1.00	HOURL	FLAGGER (SET PRICE)
1.00	LS	CLEARING AND GRUBBING
12,045.00	CUYD	COMMON EXCAVATION (RURAL SMALL)
4,080.00	CUYD	ROCK EXCAVATION
4,768.00	CUYD	COMPACTION OF EARTHWORK (TYPE B) (MR-90)
1.00	MGAL	WATER (GRADING) (SET PRICE)
100.00	LNFT	GUARDRAIL, STEEL PLATE
55.00	LNFT	ENTRANCE PIPE (18")
45.00	LNFT	CROSS ROAD PIPE (36")
4.00	EACH	END SECTION (18")
2.00	EACH	END SECTION (36")
6.00	STA.	ERADICATION OF TRAVELED WAY
4.00	EACH	SIGNING OBJECT MARKER (TYPE 3)
1.00	CUYD	TEMPORARY SURFACING MATERIAL (AGGREGATE) (SET PRICE)
1,445.00	TON	SURFACING MATERIAL (AB-3)
4.00	EACH	GUARDRAIL END TERMINAL (MGS-SRT)
4.00	EACH	GUARDRAIL END TERMINAL (MGS-FLEAT)
547.50	LBS.	TEMPORARY FERTILIZER (15-30-15)
73.00	LBS.	TEMPORARY SEED (CANADA WILD RYE)
164.50	LBS.	TEMPORARY SEED (GRAIN OATS)
164.50	LBS.	TEMPORARY SEED (STERILE WHEATGRASS)
32.00	LBS.	SOIL EROSION MIX
1,422.00	SQYD	EROSION CONTROL (CLASS 1) (TYPE C)
1.00	CUYD	SEDIMENT REMOVAL (SET PRICE)
1.00	LNFT	TEMPORARY BERM (SET PRICE)
128.00	LNFT	BIODEGRADABLE LOG (9")
128.00	LNFT	BIODEGRADABLE LOG (12")
256.00	LNFT	BIODEGRADABLE LOG (20")
256.00	LNFT	SILT FENCE
1.00	LS	SWPPP DESIGN
25.00	EACH	SWPPP INSPECTION
40.00	EACH	WATER POLLUTION CONTROL MANAGER
3,015.00	LBS.	MULCHING TACKING SLURRY
10.10	TON	MULCHING
1.00	MGAL	WATER (EROSION CONTROL) (SET PRICE)
188.00	CUYD	CLASS I EXCAVATION
93.00	CUYD	CLASS II EXCAVATION

SUMMARY OF QUANTITIES

DATE: 08/21/2019

LETTING DATE: September 18, 2019

TIME: 02:50pm

519094131 CONT...

QUANTITY	UNIT	ITEM DESCRIPTION
293.80	CUYD	CONCRETE (GRADE 4.0) (AE) (SW)
133.90	CUYD	CONCRETE (GRADE 4.0) (AE)
96,290.00	LBS.	REINFORCING STEEL (GRADE 60)
604.00	LNFT	PILES (STEEL) (HP10X42)
16.00	EACH	CAST STEEL PILE POINTS
190.00	LNFT	PRE-DRILLED PILE HOLES
583.00	CUYD	SLOPE PROTECTION (SHOT ROCK)
163.00	SQYD	GEOTEXTILE FABRIC
730.00	LBS.	FERTILIZER (13-13-13)
1.80	LBS.	SEED (BLUE GRAMA GRASS) (LOVINGTON)
16.40	LBS.	SEED (BUFFALO GRASS) (TREATED)
164.30	LBS.	SEED (RYEGRASS) (PERENNIAL)
9.50	LBS.	SEED (PRAIRIE JUNE GRASS)
23.00	LBS.	SEED (SIDE OATS GRAMA) (EL RENO)
164.30	LBS.	SEED (FESCUE) (TALL) (ENDOPHYTE-FREE)
21.90	LBS.	SEED (WESTERN WHEATGRASS) (BARTON)

*** END OF CONTRACT ***

SUMMARY OF QUANTITIES

DATE: 08/21/2019

LETTING DATE: September 18, 2019

TIME: 02:50pm

519094232 STATE PROJECT NO: 079 C 4923-01 DBE GOAL: 1.0%
 WORKING DAYS: 90 COMPLETION DATE:
 COUNTY: REPUBLIC
 GRADING, BRIDGE & SURFACING. 1 MI E OF WARWICK IN REPUBLIC CO. LENGTH
 IS 0.086 MI.

QUANTITY	UNIT	ITEM DESCRIPTION
1.00	LS	REMOVAL OF EXISTING STRUCTURES
1.00	EACH	FIELD OFFICE AND LABORATORY (TYPE C)
1.00	LS	CONTRACTOR CONSTRUCTION STAKING
1.00	LS	MOBILIZATION
1.00	LS	MOBILIZATION (DBE)
1.00	CUYD	FOUNDATION STABILIZATION (SET PRICE)
1.00	CUYD	CONCRETE FOR SEAL COURSE (SET PRICE)
1.00	LS	CURING ENVIRONMENT
1.00	LS	TRAFFIC CONTROL
1.00	HOURL	FLAGGER (SET PRICE)
1.00	LS	CLEARING AND GRUBBING
388.00	CUYD	COMMON EXCAVATION (RURAL SMALL)
1,091.00	CUYD	COMMON EXCAVATION (CONTRACTOR FURNISHED)
1,035.00	CUYD	COMPACTION OF EARTHWORK (TYPE B) (MR-90)
1.00	MGAL	WATER (GRADING) (SET PRICE)
100.00	LNFT	GUARDRAIL, STEEL PLATE
62.00	LNFT	CROSS ROAD PIPE (24")
2.00	EACH	END SECTION (24")
1.20	STA.	ERADICATION OF TRAVELED WAY
1.00	CUYD	TEMPORARY SURFACING MATERIAL (AGGREGATE) (SET PRICE)
318.00	TON	SURFACING MATERIAL (AB-3)
4.00	EACH	GUARDRAIL END TERMINAL (MGS-SRT)
4.00	EACH	GUARDRAIL END TERMINAL (MGS-FLEAT)
60.60	LBS.	SOIL EROSION MIX
2,650.00	SQYD	EROSION CONTROL (CLASS 1) (TYPE C)
1.00	CUYD	SEDIMENT REMOVAL (SET PRICE)
1.00	LNFT	TEMPORARY BERM (SET PRICE)
35.00	LNFT	BIODEGRADABLE LOG (9")
35.00	LNFT	BIODEGRADABLE LOG (12")
40.00	LNFT	BIODEGRADABLE LOG (20")
40.00	LNFT	SILT FENCE
1.00	MGAL	WATER (EROSION CONTROL) (SET PRICE)
110.00	CUYD	CLASS I EXCAVATION
75.00	CUYD	CLASS II EXCAVATION
359.80	CUYD	CONCRETE (GRADE 4.0) (AE) (SW)
77.00	CUYD	CONCRETE (GRADE 4.0) (AE)
101,480.00	LBS.	REINFORCING STEEL (GRADE 60)
970.00	LNFT	PILES (STEEL) (HP10X42)
2.00	EACH	CONTRACTOR FURNISHED PDA
26.00	EACH	CAST STEEL PILE POINTS
426.00	CUYD	SLOPE PROTECTION (SHOT ROCK)
196.00	SQYD	GEOTEXTILE FABRIC
58.18	SQFT	SIGN (FLAT SHEET) (HIGH PERFORMANCE)
95.00	LNFT	SIGN POST (2" PERFORATED SQUARE STEEL TUBE)
9.00	EACH	SIGN POST FOOTING (2" PERFORATED SQUARE STEEL TUBE)
4.00	EACH	SIGNING OBJECT MARKER (TYPE 3)

KANSAS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

LETTING DATE: September 18, 2019

DATE: 08/21/2019
TIME: 02:50pm

519094232 CONT...

QUANTITY	UNIT	ITEM DESCRIPTION
1.00	LS	SIGN (REMOVE AND RESET)
1.00	LS	SEEDING
		*** END OF CONTRACT ***

SUMMARY OF QUANTITIES

DATE: 08/21/2019

LETTING DATE: September 18, 2019

TIME: 02:50pm

519094494 STATE PROJECT NO: 019 C 4911-01 DBE GOAL: 1.0%
 WORKING DAYS: 60 COMPLETION DATE:
 COUNTY: CRAWFORD
 GRADING, BRIDGE & SURFACING. 580TH ST BETWEEN 20TH & 30TH ST OVER
 HICKORY CR IN CRAWFORD CO. LENGTH IS 0.152 MI.

QUANTITY	UNIT	ITEM DESCRIPTION
1.00	LS	REMOVAL OF EXISTING STRUCTURES
1.00	EACH	FIELD OFFICE AND LABORATORY (TYPE C)
1.00	LS	MOBILIZATION
1.00	LS	MOBILIZATION (DBE)
1.00	CUYD	FOUNDATION STABILIZATION (SET PRICE)
1.00	CUYD	CONCRETE FOR SEAL COURSE (SET PRICE)
1.00	LS	CONTRACTOR CONSTRUCTION STAKING
1.00	LS	CURING ENVIRONMENT
1.00	LS	TRAFFIC CONTROL
1.00	HOURL	FLAGGER (SET PRICE)
1.00	LS	CLEARING AND GRUBBING
1,545.00	CUYD	COMMON EXCAVATION (RURAL SMALL)
1,546.00	CUYD	COMMON EXCAVATION (CONTRACTOR FURNISHED)
2,318.00	CUYD	COMPACTION OF EARTHWORK (TYPE B) (MR-90)
1.00	MGAL	WATER (GRADING) (SET PRICE)
289.00	CUYD	SLOPE PROTECTION (RIPRAP STONE)
100.00	LNFT	GUARDRAIL, STEEL PLATE
4.00	EACH	SIGNING OBJECT MARKER (TYPE 3)
1.00	CUYD	TEMPORARY SURFACING MATERIAL (AGGREGATE) (SET PRICE)
699.00	TON	SURFACING MATERIAL (AB-3)
68.10	LBS.	SOIL EROSION MIX
2,978.00	SQYD	EROSION CONTROL (CLASS 1) (TYPE C)
1.00	CUYD	SEDIMENT REMOVAL (SET PRICE)
1.00	LNFT	TEMPORARY BERM (SET PRICE)
30.00	LNFT	BIODEGRADABLE LOG (9")
30.00	LNFT	BIODEGRADABLE LOG (12")
340.00	LNFT	BIODEGRADABLE LOG (20")
1.00	MGAL	WATER (EROSION CONTROL) (SET PRICE)
73.00	CUYD	CLASS I EXCAVATION
31.00	CUYD	CLASS II EXCAVATION
42.00	CUYD	CONCRETE (GRADE 4.0) (AE) (SW)
8,030.00	LBS.	REINFORCING STEEL (GRADE 60)
63,630.00	LBS.	STRUCTURAL STEEL (M270) (GR 50WT2)
488.00	LNFT	PILES (STEEL) (HP10X42)
1,730.00	LNFT	PILE (CORRUGATED METAL SHEET GALVANIZED)
196.00	CUYD	SLOPE PROTECTION (RIPRAP STONE)
1.00	EACH	BRIDGE PROJECT MARKER
1.00	LS	SEEDING

*** END OF CONTRACT ***

SUMMARY OF QUANTITIES

DATE: 08/21/2019

LETTING DATE: September 18, 2019

TIME: 02:50pm

519094525

STATE PROJECT NO: 048 C 4915-01

DBE GOAL:

1.0%

WORKING DAYS: 125 COMPLETION DATE:

COUNTY: KINGMAN

GRADING, BRIDGE & SURFACING. 0.5 MI S & 2.2 MI W OF MURDOCK ON SE 80TH AVE OVER S FORK CR IN KINGMAN CO. LENGTH IS 0.213 MI.

QUANTITY	UNIT	ITEM DESCRIPTION
1.00	LS	CONTRACTOR CONSTRUCTION STAKING
1.00	EACH	FIELD OFFICE AND LABORATORY (TYPE C)
1.00	CUYD	FOUNDATION STABILIZATION (SET PRICE)
1.00	LS	MOBILIZATION
1.00	LS	MOBILIZATION (DBE)
1.00	LS	REMOVAL OF EXISTING STRUCTURES
1.00	CUYD	CONCRETE FOR SEAL COURSE (SET PRICE)
1.00	LS	CURING ENVIRONMENT
1.00	LS	TRAFFIC CONTROL
1.00	HOUR	FLAGGER (SET PRICE)
1.00	LS	CLEARING AND GRUBBING
1,013.00	CUYD	COMMON EXCAVATION (RURAL SMALL)
2,934.00	CUYD	COMMON EXCAVATION (CONTRACTOR FURNISHED)
2,921.00	CUYD	COMPACTION OF EARTHWORK (TYPE B) (MR-90)
1.00	MGAL	WATER (GRADING) (SET PRICE)
2.00	EACH	END SECTION (2.5 SQ.FT.) (RCHE)
36.00	LNFT	CROSS ROAD PIPE (2.5 SQ.FT.) (RCPHE)
100.00	LNFT	GUARDRAIL, STEEL PLATE
1.00	CUYD	TEMPORARY SURFACING MATERIAL (AGGREGATE) (SET PRICE)
289.00	CUYD	LIGHT TYPE SURFACING (SA-1)
4.00	EACH	SIGNING OBJECT MARKER (TYPE 3)
4.00	EACH	GUARDRAIL END TERMINAL (SRT)
4.00	EACH	GUARDRAIL END TERMINAL (FLEAT)
11.90	LBS.	SOIL EROSION MIX
522.00	SQYD	EROSION CONTROL (CLASS 1) (TYPE D)
1.00	CUYD	SEDIMENT REMOVAL (SET PRICE)
1.00	LNFT	TEMPORARY BERM (SET PRICE)
335.00	LNFT	BIODEGRADABLE LOG (20")
270.00	LNFT	FILTER SOCK (18")
240.00	SQYD	GEOTEXTILE (EROSION CONTROL)
190.00	LNFT	SILT FENCE
1.00	LS	SWPPP DESIGN
30.00	EACH	SWPPP INSPECTION
45.00	EACH	WATER POLLUTION CONTROL MANAGER
1.00	MGAL	WATER (EROSION CONTROL) (SET PRICE)
47.00	CUYD	CLASS I EXCAVATION
260.00	CUYD	CLASS II EXCAVATION
671.60	CUYD	CONCRETE (GRADE 4.0) (AE) (SW)
98.00	CUYD	CONCRETE (GRADE 4.0) (AE)
196,960.00	LBS.	REINFORCING STEEL (GRADE 60)
3.00	EACH	CONTRACTOR FURNISHED PDA
2,494.00	LNFT	PILES (STEEL) (HP12X53)
40.00	EACH	CAST STEEL PILE POINTS
251.00	CUYD	SLOPE PROTECTION (RIPRAP STONE)
1.00	LS	SEEDING

*** END OF CONTRACT ***

SUMMARY OF QUANTITIES

DATE: 08/21/2019

LETTING DATE: September 18, 2019

TIME: 02:50pm

519094535 STATE PROJECT NO: 087 TE 0434-01 DBE GOAL: 10.0%
 WORKING DAYS: 80 COMPLETION DATE:
 COUNTY: SEDGWICK
 PEDESTRIAN & BICYCLE PATHS. DERBY TO MULVANE PATHWAY IN SEDGWICK CO.
 LENGTH IS 1.71 MI.

QUANTITY	UNIT	ITEM DESCRIPTION
1.00	LS	CONTRACTOR CONSTRUCTION STAKING
1.00	EACH	FIELD OFFICE AND LABORATORY (TYPE A)
1.00	LS	MOBILIZATION
1.00	LS	MOBILIZATION (DBE)
1.00	LS	REMOVAL OF EXISTING STRUCTURES
1.00	CUYD	CONCRETE FOR SEAL COURSE (SET PRICE)
1.00	CUYD	FOUNDATION STABILIZATION (SET PRICE)
1.00	LS	TRAFFIC CONTROL
1.00	HOUR	FLAGGER (SET PRICE)
1.00	LS	CLEARING AND GRUBBING
1,133.00	CUYD	COMMON EXCAVATION (URB)
26.00	CUYD	ROCK EXCAVATION
1.00	MGAL	WATER (GRADING) (SET PRICE)
293.00	CUYD	COMPACTION OF EARTHWORK (TYPE B) (MR-90)
71.00	LNFT	CROSS ROAD PIPE (18") (RCP)
136.00	LNFT	CROSS ROAD PIPE (24") (RCP)
391.00	LNFT	CROSS ROAD PIPE (1.5 SQ.FT.) (RCPHE)
9.00	LNFT	ENTRANCE PIPE (5.0 SQ.FT.) (RCPHE)
2.00	EACH	END SECTION (18") (RC)
4.00	EACH	END SECTION (24") (RC)
12.00	EACH	END SECTION (1.5 SQ.FT.) (RCHE)
1.00	EACH	END SECTION (5.0 SQ.FT.) (RCHE)
9,596.00	SQYD	SIDEWALK CONSTRUCTION (4") (AE)
189.00	SQYD	SIDEWALK CONSTRUCTION (6") (AE)
186.00	SQYD	SIDEWALK RAMP
1.00	CUYD	TEMPORARY SURFACING MATERIAL (AGGREGATE) (SET PRICE)
11,976.00	SQYD	GRANULAR BASE (6")
1.00	MGAL	WATER (GRANULAR BASE) (SET PRICE)
239.00	SQYD	RIPRAP (LIGHT STONE) (100 LB)
1.00	STA.	ERADICATION OF TRAVELED WAY
30.00	LNFT	HANDRAIL (METAL) (4'- 6")
10.40	CUYD	CONCRETE (GRADE 4.0) (RCB)
2.00	CUYD	CONCRETE (GRADE 4.0) (AE) (RCB)
13.00	SQYD	BRIDGE BACKWALL PROTECTION SYSTEM
650.00	LBS.	REINFORCING STEEL (GRADE 60)
750.00	LBS.	REINFORCING STEEL (GRADE 60) (EPOXY COATED)
6.00	CUYD	FOUNDATION STABILIZATION
12.00	CUYD	GRANULAR BACKFILL (WINGWALLS)
1.00	EACH	BRIDGE PROJECT MARKER
1.00	LS	SIGN (REMOVE AND RESET)
3.00	EACH	ADJUSTMENT OF VALVE BOX (WATER)
390.00	LBS.	TEMPORARY FERTILIZER (15-30-15)
52.00	LBS.	TEMPORARY SEED (CANADA WILD RYE)
117.00	LBS.	TEMPORARY SEED (GRAIN OATS)
117.00	LBS.	TEMPORARY SEED (STERILE WHEATGRASS)
1.00	CUYD	SEDIMENT REMOVAL (SET PRICE)

KANSAS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

LETTING DATE: September 18, 2019

DATE: 08/21/2019
TIME: 02:50pm

519094535 CONT...

QUANTITY	UNIT	ITEM DESCRIPTION
1.00	LNFT	TEMPORARY BERM (SET PRICE)
680.00	LNFT	BIODEGRADABLE LOG (20")
8,300.00	LNFT	SILT FENCE
1.00	LS	SWPPP DESIGN
20.00	EACH	SWPPP INSPECTION
30.00	EACH	WATER POLLUTION CONTROL MANAGER
3,510.00	LBS.	MULCHING TACKING SLURRY
7.80	TON	MULCHING
1.00	MGAL	WATER (EROSION CONTROL) (SET PRICE)
25.10	CUYD	CONCRETE (GRADE 4.0) (RCB BR)
10.90	CUYD	CONCRETE (GRADE 4.0) (AE) (RCB BR)
45.00	SQYD	BRIDGE BACKWALL PROTECTION SYSTEM
930.00	LBS.	REINFORCING STEEL (GRADE 60)
5,180.00	LBS.	REINFORCING STEEL (GRADE 60) (EPOXY COATED)
246.00	CUYD	CLASS III EXCAVATION (RCB)
14.00	CUYD	FOUNDATION STABILIZATION
12.00	CUYD	GRANULAR BACKFILL (WINGWALLS)
1.00	EACH	BRIDGE PROJECT MARKER
177.00	SQYD	CONCRETE PAVEMENT (6" UNIFORM) (AE)
197.00	LNFT	CURB AND GUTTER, COMBINED (AE)
5.00	TON	SURFACING MATERIAL (AB-3)
1,400.00	LNFT	PAVEMENT MARKING (EPOXY) (WHITE) (4")
13.00	LNFT	PAVEMENT MARKING (EPOXY) (WHITE) (6")
26.00	LNFT	PAVEMENT MARKING (EPOXY) (YELLOW) (4")
72.00	LNFT	PAVEMENT MARKING (INTERSECTION GRADE) (WHITE) (24")
1.00	LS	TRAFFIC SIGNAL
208.00	LBS.	FERTILIZER (16-20- 0)
16.40	LBS.	SEED (SIDE OATS GRAMA) (EL RENO)
1.30	LBS.	SEED (BLUE GRAMA GRASS) (LOVINGTON)
19.80	LBS.	SEED (PRAIRIE JUNE GRASS)
117.00	LBS.	SEED (FESCUE) (TALL) (ENDOPHYTE-FREE)
117.00	LBS.	SEED (RYEGRASS) (PERENNIAL)

*** END OF CONTRACT ***

SUMMARY OF QUANTITIES

DATE: 08/21/2019

LETTING DATE: September 18, 2019

TIME: 02:50pm

519096121

STATE PROJECT NO: U075-007 KA 5285-01

DBE GOAL:

WORKING DAYS: 10 COMPLETION DATE:

COUNTY: BROWN

RUMBLE STRIPS. US-75 FR S OF FAIRVIEW INTERCHANGE N TO US-75/K-246 JCT IN
BR CO. LENGTH IS 7.100 MI.

QUANTITY	UNIT	ITEM DESCRIPTION
1.00	LS	MOBILIZATION
1.00	LS	TRAFFIC CONTROL
1.00	HOUR	FLAGGER (SET PRICE)
377.00	STA.	RUMBLE STRIPS (MILLED) (ASPHALT) (CENTERLINE)
9,430.00	LNFT	PAVEMENT MARKING (THERMOPLASTIC) (YELLOW) (4")
*** END OF CONTRACT ***		

SUMMARY OF QUANTITIES

DATE: 08/21/2019

LETTING DATE: September 18, 2019

TIME: 02:50pm

519096242

STATE PROJECT NO: 015 KA 5302-01
 WORKING DAYS: 45 COMPLETION DATE:
 COUNTY: CLOUD

DBE GOAL:

MILLING AND HMA OVERLAY. HOST KA 5302-01. K194, KA 5300-01, FR N OF RR ROW AT SIMPSON N TO US24 JCT IN CD CO. LENGTH IS 1.580 MI. US-24, KA 5301-01, FR CD/MC CL E TO 0.241 MI E OF US-81 JCT IN CD CO. LENGTH IS 15.555 MI

QUANTITY	UNIT	ITEM DESCRIPTION
1.00	LS	MOBILIZATION
1.00	EACH	FIELD OFFICE AND LABORATORY (TYPE A)
1.00	LS	MAINTENANCE AND RESTORATION OF HAUL ROADS (SET PRICE)
1.00	LS	TRAFFIC CONTROL
1.00	HOUR	FLAGGER (SET PRICE)
1.00	MGAL	WATER (EARTHWORK COMPACTION) (SET PRICE)
1.00	TON	MATERIAL FOR HMA PATCHING (SET PRICE)
1.00	LS	ASPHALT DENSITY PAY ADJUSTMENT
1.00	LS	ASPHALT AIR VOID PAY ADJUSTMENT
1.00	EACH	ASPHALT CORE (SET PRICE)
400.00	SQYD	MILLING
1,923.00	TON	HMA OVERLAY (SR-12.5A) (PG 64-22)
1,923.00	TON	QUALITY CONTROL TESTING (HMA)
5.00	TON	EMULSIFIED ASPHALT (SS-1HP)
313.00	TON	PAVEMENT EDGE WEDGE (ROCK)
83.40	STAL	PAVEMENT MARKING (TEMP) 4" BROKEN (3')(TYPE I)
3,946.00	LNFT	PAVEMENT MARKING (MULTI-COMPONENT) (YELLOW) (4")
16,686.00	LNFT	PAVEMENT MARKING (MULTI-COMPONENT) (WHITE) (6")
1.00	EACH	PAVEMENT MRK SYM (INTERSECTION GRADE) (WHITE)(RAILROAD XING)
7,810.00	TON	MILLING
23,907.00	TON	HMA OVERLAY (SR-12.5A) (PG 70-22)
23,907.00	TON	QUALITY CONTROL TESTING (HMA)
63.00	TON	EMULSIFIED ASPHALT (SS-1HP)
3,080.00	TON	PAVEMENT EDGE WEDGE (ROCK)
822.00	STAL	PAVEMENT MARKING (TEMP) 4" BROKEN (3')(TYPE I)
822.00	STAL	PAVEMENT MARKING (TEMP) 4" BROKEN (3')(TYPE II)
51,705.00	LNFT	PAVEMENT MARKING (MULTI-COMPONENT) (YELLOW) (4")
169,455.00	LNFT	PAVEMENT MARKING (MULTI-COMPONENT) (WHITE) (6")
365.00	LNFT	PAVEMENT MARKING (MULTI-COMPONENT) (YELLOW) (12")

*** END OF CONTRACT ***

SUMMARY OF QUANTITIES

DATE: 08/21/2019

LETTING DATE: September 18, 2019

TIME: 02:50pm

519096252

STATE PROJECT NO: K014-027 KA 5295-01

DBE GOAL:

WORKING DAYS: 30 COMPLETION DATE:

COUNTY: ELLSWORTH

MILLING AND HMA OVERLAY. K-14 FR K140 JCT TO I-70 JCT IN EW CO. LENGTH IS 7.727 MI.

QUANTITY	UNIT	ITEM DESCRIPTION
1.00	LS	MOBILIZATION
1.00	EACH	FIELD OFFICE AND LABORATORY (TYPE A)
1.00	LS	MAINTENANCE AND RESTORATION OF HAUL ROADS (SET PRICE)
1.00	LS	TRAFFIC CONTROL
1.00	HOUR	FLAGGER (SET PRICE)
11,918.00	TON	MILLING
4,363.00	TON	HMA-COMMERCIAL GRADE (CLASS A)
10,448.00	TON	HMA OVERLAY (SR-12.5A) (PG 64-22)
10,448.00	TON	QUALITY CONTROL TESTING (HMA)
27.00	TON	EMULSIFIED ASPHALT (SS-1HP)
802.40	STA.	SHOULDERS (AGGREGATE) (HMA WIDENING)
1.00	TON	MATERIAL FOR HMA PATCHING (SET PRICE)
1.00	LS	ASPHALT DENSITY PAY ADJUSTMENT
1.00	LS	ASPHALT AIR VOID PAY ADJUSTMENT
1.00	EACH	ASPHALT CORE (SET PRICE)
1,265.00	TON	PAVEMENT EDGE WEDGE (ROCK)
1.00	MGAL	WATER (EARTHWORK COMPACTION) (SET PRICE)
405.30	STAL	PAVEMENT MARKING (TEMP) 4" BROKEN (3')(TYPE I)
405.30	STAL	PAVEMENT MARKING (TEMP) 4" BROKEN (3')(TYPE II)
81,604.00	LNFT	PAVEMENT MARKING (MULTI-COMPONENT) (WHITE) (6")
28,756.00	LNFT	PAVEMENT MARKING (MULTI-COMPONENT) (YELLOW) (4")
1,068.00	LNFT	PAVEMENT MARKING REMOVAL

*** END OF CONTRACT ***

SUMMARY OF QUANTITIES

DATE: 08/21/2019

LETTING DATE: September 18, 2019

TIME: 02:50pm

519096262

STATE PROJECT NO: 053 KA 5298-01
 WORKING DAYS: 30 COMPLETION DATE:
 COUNTY: LINCOLN

DBE GOAL:

SURFACE RECYCLE AND CHIP SEAL. KA 5296-01, K-18, FR ECL OF LINCOLN TO OT
 CO LI IN LC CO. LENGTH IS 12.984 MI. KA 5297-01, K-252, FR NCL OF BEVERLY N TO
 K-18 JCT IN LC CO. LENGTH IS 0.453 MI.

QUANTITY	UNIT	ITEM DESCRIPTION
1.00	LS	MOBILIZATION
1.00	LS	TRAFFIC CONTROL
1.00	TON	MATERIAL FOR HMA PATCHING (SET PRICE)
1.00	LS	SURFACE RECYCLING PAY ADJUSTMENT
1.00	MGAL	WATER (FLEXIBLE PAVEMENT) (SET PRICE)
1.00	HOUR	FLAGGER (SET PRICE)
684.00	STA.	SURFACE RECYCLING (2")
333.00	TON	ASPHALT REJUVENATING AGENT
363.00	TON	EMULSIFIED ASPHALT (CRS-1HP) (SEAL)
1,875.00	CUYD	COVER MATERIAL (CM-L-2)
684.00	STA.	MANIPULATION (CHIP SEAL)
1,368.00	STAL	PAVEMENT MARKING (TEMP) 4" BROKEN (3')(TYPE II)
684.00	STAL	FLEXIBLE RAISED PAVEMENT MARKERS (4" BROKEN (3 FT.))
24.00	STA.	SURFACE RECYCLING (2")
10.00	TON	ASPHALT REJUVENATING AGENT
11.00	TON	EMULSIFIED ASPHALT (CRS-1HP) (SEAL)
55.00	CUYD	COVER MATERIAL (CM-L-2)
24.00	STA.	MANIPULATION (CHIP SEAL)
48.00	STAL	PAVEMENT MARKING (TEMP) 4" BROKEN (3')(TYPE II)
24.00	STAL	FLEXIBLE RAISED PAVEMENT MARKERS (4" BROKEN (3 FT.))

*** END OF CONTRACT ***

SUMMARY OF QUANTITIES

DATE: 08/21/2019

LETTING DATE: September 18, 2019

TIME: 02:50pm

519096363

STATE PROJECT NO: K009-074 KA 5308-01

DBE GOAL:

WORKING DAYS: 45 COMPLETION DATE:

COUNTY: PHILLIPS

MILLING AND HMA OVERLAY. K9, FR US183 JCT E TO 0.117 MI W OF KIRWIN IN PL

CO. LENGTH IS 10.053 MI.

QUANTITY	UNIT	ITEM DESCRIPTION
1.00	LS	MOBILIZATION
1.00	LS	MAINTENANCE AND RESTORATION OF HAUL ROADS (SET PRICE)
1.00	EACH	FIELD OFFICE AND LABORATORY (TYPE A)
1.00	LS	TRAFFIC CONTROL
1.00	HOUR	FLAGGER (SET PRICE)
146,350.00	SQYD	MILLING
23,870.00	TON	HMA OVERLAY (SR-19A) (PG 64-22)
12,365.00	TON	HMA OVERLAY (SR-12.5A) (PG 64-22)
36,235.00	TON	QUALITY CONTROL TESTING (HMA)
63.00	TON	EMULSIFIED ASPHALT (SS-1H OR CSS-1H)
1.00	TON	MATERIAL FOR HMA PATCHING (SET PRICE)
1.00	EACH	ASPHALT CORE (SET PRICE)
1.00	LS	ASPHALT DENSITY PAY ADJUSTMENT
1.00	LS	ASPHALT AIR VOID PAY ADJUSTMENT
1.00	LS	ASPHALT PAVEMENT SMOOTHNESS
1,066.10	STAL	PAVEMENT MARKING (TEMP) 4" BROKEN (3')(TYPE I)
1,066.10	STAL	PAVEMENT MARKING (TEMP) 4" BROKEN (3')(TYPE II)
1,795.00	TON	PAVEMENT EDGE WEDGE (ROCK)
1.00	MGAL	WATER (EARTHWORK COMPACTION) (SET PRICE)
52,093.00	LNFT	PAVEMENT MARKING (MULTI-COMPONENT) (YELLOW) (4")
104,440.00	LNFT	PAVEMENT MARKING (MULTI-COMPONENT) (WHITE) (6")

*** END OF CONTRACT ***

SUMMARY OF QUANTITIES

DATE: 08/21/2019

LETTING DATE: September 18, 2019

TIME: 02:50pm

519096373

STATE PROJECT NO: K009-074 M 0072-01
 WORKING DAYS: CCD COMPLETION DATE: 10/30/20
 COUNTY: PHILLIPS
 STOCKPILE ASPHALT MATERIAL. FR NT/PL CO LI E TO US183 JCT IN WL CO.
 LENGTH IS 17.501 MI. STATE TIE KA 5307-01.

DBE GOAL:

QUANTITY	UNIT	ITEM DESCRIPTION
100.00	TON	HMA-COMMERCIAL GRADE (CLASS A)
*** END OF CONTRACT ***		

SUMMARY OF QUANTITIES

DATE: 08/21/2019

LETTING DATE: September 18, 2019

TIME: 02:50pm

519096383

STATE PROJECT NO: U040-100 M 0071-01
 WORKING DAYS: CCD COMPLETION DATE: 10/30/20
 COUNTY: WALLACE
 STOCKPILE ASPHALT MATERIAL. FR ECL SHARON SPRINGS E TO WALG CO LI IN
 WA CO. LENGTH IS 15.387 MI. STATE TIE KA 5303-01.

DBE GOAL:

QUANTITY	UNIT	ITEM DESCRIPTION
100.00	TON	HMA-COMMERCIAL GRADE (CLASS A)
		*** END OF CONTRACT ***

SUMMARY OF QUANTITIES

DATE: 08/21/2019

LETTING DATE: September 18, 2019

TIME: 02:50pm

519096535

STATE PROJECT NO: U183-017 KA 5310-01

DBE GOAL:

WORKING DAYS: 50 COMPLETION DATE:

COUNTY: COMANCHE

MILLING AND HMA OVERLAY. US-183, FR US160 JCT TO CM/KW CO LI IN CM CO.

LENGTH IS 7.142 MI. STATE TIE KA 5309-01.

QUANTITY	UNIT	ITEM DESCRIPTION
1.00	LS	MOBILIZATION
1.00	LS	TRAFFIC CONTROL
1.00	HOUR	FLAGGER (SET PRICE)
2,854.00	TON	MILLING
1.00	TON	MATERIAL FOR HMA PATCHING (SET PRICE)
1.00	LS	ASPHALT AIR VOID PAY ADJUSTMENT
1.00	LS	ASPHALT DENSITY PAY ADJUSTMENT
1.00	EACH	ASPHALT CORE (SET PRICE)
1.00	EACH	BOND CORE (SET PRICE)
9,820.00	TON	HMA OVERLAY (SR-12.5A) (PG 64-22)
9,820.00	TON	QUALITY CONTROL TESTING (HMA)
120,348.00	SQYD	EMULSIFIED ASPHALT
943.00	TON	PAVEMENT EDGE WEDGE (ROCK)
1.00	MGAL	WATER (EARTHWORK COMPACTION) (SET PRICE)
377.10	STAL	PAVEMENT MARKING (TEMP) 4" BROKEN (3')(TYPE II)
377.10	STAL	FLEXIBLE RAISED PAVEMENT MARKERS (4" BROKEN (3 FT.))
5,082.00	TON	HMA-COMMERCIAL GRADE (CLASS A)
700.70	STA.	SHOULDERS (AGGREGATE) (HMA WIDENING)

*** END OF CONTRACT ***

SUMMARY OF QUANTITIES

DATE: 08/21/2019

LETTING DATE: September 18, 2019

TIME: 02:50pm

519096545

STATE PROJECT NO: K014-048 KA 5311-01

DBE GOAL:

WORKING DAYS: 35 COMPLETION DATE:

COUNTY: KINGMAN

MILL AND HMA OVERLAY. K-14 FR K-42 JCT TO BEG OF CONC PVMT IN KINGMAN IN
KM CO. LENGTH IS 12.648 MI.

QUANTITY	UNIT	ITEM DESCRIPTION
1.00	LS	MOBILIZATION
1.00	EACH	FIELD OFFICE AND LABORATORY (TYPE A)
1.00	LS	MAINTENANCE AND RESTORATION OF HAUL ROADS (SET PRICE)
1.00	LS	TRAFFIC CONTROL
1.00	HOUR	FLAGGER (SET PRICE)
5,336.00	TON	MILLING
17,785.00	TON	HMA OVERLAY (SR-12.5A) (PG 64-22)
17,785.00	TON	QUALITY CONTROL TESTING (HMA)
217,952.00	SQYD	EMULSIFIED ASPHALT
1.00	LS	ASPHALT DENSITY PAY ADJUSTMENT
1.00	LS	ASPHALT AIR VOID PAY ADJUSTMENT
1.00	EACH	ASPHALT CORE (SET PRICE)
1.00	EACH	BOND CORE (SET PRICE)
1.00	TON	MATERIAL FOR HMA PATCHING (SET PRICE)
1,670.00	TON	PAVEMENT EDGE WEDGE (ROCK)
1.00	MGAL	WATER (EARTHWORK COMPACTION) (SET PRICE)
668.00	STAL	PAVEMENT MARKING (TEMP) 4" BROKEN (3')(TYPE II)
668.00	STAL	FLEXIBLE RAISED PAVEMENT MARKERS (4" BROKEN (3 FT.))
7,423.00	TON	HMA-COMMERCIAL GRADE (CLASS A)
1,023.40	STA.	SHOULDERS (AGGREGATE) (HMA WIDENING)

*** END OF CONTRACT ***

SUMMARY OF QUANTITIES

DATE: 08/21/2019

LETTING DATE: September 18, 2019

TIME: 02:50pm

519096575

STATE PROJECT NO: U183-049 KA 5309-01

DBE GOAL:

WORKING DAYS: 50 COMPLETION DATE:

COUNTY: KIOWA

MILLING AND HMA OVERLAY. US-183, FR CM/KW CO LI TO US-54 JCT IN KW CO.

LENGTH IS 15.492 MI. STATE TIE KA 5310-01.

QUANTITY	UNIT	ITEM DESCRIPTION
1.00	LS	MOBILIZATION
1.00	LS	MAINTENANCE AND RESTORATION OF HAUL ROADS (SET PRICE)
1.00	EACH	FIELD OFFICE AND LABORATORY (TYPE A)
1.00	LS	TRAFFIC CONTROL
1.00	HOUR	FLAGGER (SET PRICE)
6,177.00	TON	MILLING
1.00	TON	MATERIAL FOR HMA PATCHING (SET PRICE)
1.00	LS	ASPHALT AIR VOID PAY ADJUSTMENT
1.00	LS	ASPHALT DENSITY PAY ADJUSTMENT
1.00	EACH	ASPHALT CORE (SET PRICE)
1.00	EACH	BOND CORE (SET PRICE)
19,887.00	TON	HMA OVERLAY (SR-12.5A) (PG 64-22)
19,887.00	TON	QUALITY CONTROL TESTING (HMA)
243,718.00	SQYD	EMULSIFIED ASPHALT
2,045.00	TON	PAVEMENT EDGE WEDGE (ROCK)
1.00	MGAL	WATER (EARTHWORK COMPACTION) (SET PRICE)
818.00	STAL	PAVEMENT MARKING (TEMP) 4" BROKEN (3')(TYPE II)
818.00	STAL	FLEXIBLE RAISED PAVEMENT MARKERS (4" BROKEN (3 FT.))
5,686.00	TON	HMA-COMMERCIAL GRADE (CLASS A)
784.00	STA.	SHOULDERS (AGGREGATE) (HMA WIDENING)

*** END OF CONTRACT ***

SUMMARY OF QUANTITIES

DATE: 08/21/2019

LETTING DATE: September 18, 2019

TIME: 02:50pm

519096636

STATE PROJECT NO: 028 KA 5293-01

DBE GOAL:

WORKING DAYS: 40 COMPLETION DATE:

COUNTY: FINNEY

MILL AND HMA OVERLAY. KA 5293-01 HOST. KA 5291-01, US-83, FR OLD US83 JCT TO S US50 JCT IN FI CO. LENGTH IS 8.11 MI. KA 5291-01, US-83B, FRUS83 JCT TO SCL OF GARDEN CITY IN FI CO. LENGTH IS 1.74 MI.

QUANTITY	UNIT	ITEM DESCRIPTION
1.00	LS	MOBILIZATION
1.00	LS	MAINTENANCE AND RESTORATION OF HAUL ROADS (SET PRICE)
1.00	EACH	FIELD OFFICE AND LABORATORY (TYPE A)
1.00	TON	MATERIAL FOR HMA PATCHING (SET PRICE)
1.00	LS	ASPHALT AIR VOID PAY ADJUSTMENT
1.00	LS	ASPHALT DENSITY PAY ADJUSTMENT
1.00	EACH	ASPHALT CORE (SET PRICE)
1.00	MGAL	WATER (FLEXIBLE PAVEMENT) (SET PRICE)
1.00	LS	TRAFFIC CONTROL
1.00	HOURL	FLAGGER (SET PRICE)
14,469.00	TON	MILLING
14,469.00	TON	HMA OVERLAY (SR-12.5A) (PG 70-22)
28.00	TON	EMULSIFIED ASPHALT (SS-1HP)
14,469.00	TON	QUALITY CONTROL TESTING (HMA)
428.20	STAL	PAVEMENT MARKING (TEMP) 4" BROKEN (3')(TYPE I)
174.00	TON	EMULSIFIED ASPHALT (CRS-1HP) (SEAL)
813.00	CUYD	COVER MATERIAL (CM-L-2)
428.20	STA.	MANIPULATION (CHIP SEAL)
411.80	STA.	RUMBLE STRIPS (MILLED) (ASPHALT) (CENTERLINE)
823.70	STA.	RUMBLE STRIPS (MILLED) (ASPHALT)
95,840.00	LNFT	PAVEMENT MARKING (MULTI-COMPONENT) (WHITE) (6")
46,742.00	LNFT	PAVEMENT MARKING (MULTI-COMPONENT) (YELLOW) (4")
295.00	LNFT	PAVEMENT MARKING (MULTI-COMPONENT) (YELLOW) (12")
17.00	EACH	PAVEMENT MRK SYM (INTERSECTION GRADE) (WHITE) (LEFT ARROW)
14.00	EACH	PAVEMENT MRK SYM (INTERSECTION GRADE) (WHITE) (RT ARROW)
10,939.00	LNFT	PAVEMENT MARKING REMOVAL
3,623.00	TON	MILLING
3,623.00	TON	HMA OVERLAY (SR-12.5A) (PG 70-22)
7.00	TON	EMULSIFIED ASPHALT (SS-1HP)
3,623.00	TON	QUALITY CONTROL TESTING (HMA)
91.90	STAL	PAVEMENT MARKING (TEMP) 4" BROKEN (3')(TYPE I)
41.00	TON	EMULSIFIED ASPHALT (CRS-1HP) (SEAL)
194.00	CUYD	COVER MATERIAL (CM-L-2)
91.90	STA.	MANIPULATION (CHIP SEAL)
24,697.00	LNFT	PAVEMENT MARKING (MULTI-COMPONENT) (WHITE) (6")
16,978.00	LNFT	PAVEMENT MARKING (MULTI-COMPONENT) (YELLOW) (4")
370.00	LNFT	PAVEMENT MARKING (MULTI-COMPONENT) (WHITE) (12")
13.00	LNFT	PAVEMENT MARKING (INTERSECTION GRADE) (WHITE) (24")
2.00	EACH	PAVEMENT MRK SYM (INTERSECTION GRADE) (WHITE) (STOP)
2.00	EACH	PAVEMENT MRK SYM (INTERSECTION GRADE) (WHITE) (AHEAD)
3,721.00	LNFT	PAVEMENT MARKING REMOVAL

*** END OF CONTRACT ***