

203 - RESETTING EXISTING CULVERTS

SECTION 203

RESETTING EXISTING CULVERTS

203.1 DESCRIPTION

Remove and reset the existing culverts and end sections as specified in the Contract Documents.

BID ITEMS

Resetting End Section
Resetting Pipe Culvert

UNITS

Each
Linear Foot

203.2 MATERIALS

Provide the required materials that comply with the materials' divisions (**SECTIONS 1000 – 2500**).

203.3 CONSTRUCTION REQUIREMENTS

Remove the designated structures without damaging. Store and protect the structure from damage, if the structure is not reset immediately. Replace, in kind, any structures or materials damaged or lost.

Clean all structures before resetting.

Reset the structures at the locations shown in the Contract Documents. Excavate for, place and backfill the structures according to **SECTION 204**.

203.4 MEASUREMENT AND PAYMENT

The Engineer will measure each removal and resetting of an existing end section.

The Engineer will measure the removal and resetting of an existing pipe culvert by the linear foot of culvert reset.

Payment for "Resetting End Section" and "Resetting Pipe Culvert" at the contract unit prices is full compensation for the specified work.

If, upon removal, the Engineer determines that the existing culvert or end section is damaged, and the damage is not a result of the Contractor's actions, the Engineer will pay for the replacement of the culvert or end section as "Extra Work", **subsection 104.6**.