

**KANSAS DEPARTMENT OF TRANSPORTATION
SPECIAL PROVISION TO THE
STANDARD SPECIFICATIONS, 2007 EDITION**

SECTION 901

TEMPORARY EROSION AND POLLUTION CONTROL

Page 900-1, subsection 901.1. In the BID ITEMS list change, "Temporary Seed (**)" to "Temporary Seed (***)".**

Page 900-1, subsection 901.1, add the following Bid Item:

Curb Inlet Protection

Linear Foot

Page 900-2, subsection 901.2, add the following subsection:

g. Curb Inlet Protection. Provide burlap bags or synthetic mesh, aggregate, 2 inch by 4 inch board as specified in the Contract Documents. Alternative products may be used with the Engineer's approval. The Engineer will accept the material for curb inlet protection based on condition and visual inspection of the installed material.

Page 900-4, subsection 901.3n., add the following:

Only use the soil erosion mix under erosion control blankets.

Page 900-4, delete subsection 901.3p.(2) and replace with the following:

(2) Areas with Erosion Control (Class II). Place the Erosion Control (Class II) as shown in the Contract Documents.

If Pyramat® erosion control (Class II) is used, cover it with ½ inch of pulverized, fine-grained soil. Hand rake the soil into the erosion control material; then mulch the area according to **SECTION 904**.

Page 900-6, subsection 901.3, add the following subsection:

v. Curb Inlet Protection. Install the curb inlet protection as shown in the Contract Documents.

Page 900-6, subsection 901.4, add the following to the fifth paragraph:

If the quantity of sediment removal is approximately 50 cubic yards or greater in one location, the Engineer may pay for sediment removal by force account according to **subsection 109.3** rather than paying the contract set price for the bid item "Sediment Removal". Whether paid as a set price or by force account, the Engineer will not pay for a quantity or cost that is incurred because of the Contractor's failure to install seed timely or failure to remove sediment timely as **SECTION 109** requires.

Page 900-6, subsection 901.4, add the following after the twelfth paragraph:

The Engineer will measure curb inlet protection by the linear foot.

Page 900-6, subsection 901.4. Add the following paragraph to the end of the subsection:

The Engineer will not measure for separate payment any erosion control devices installed in Contractor-Furnished borrow locations. These items are subsidiary to Common Excavation (Contractor-Furnished) in the contract.