KANSAS DEPARTMENT OF TRANSPORTATION
SPECIAL PROVISION TO THE
STANDARD SPECIFICATIONS, 1990 EDITION

SECTION 821

TRAFFIC CONTROL

SIGNING OF 2-LANE HIGHWAY WITH 1 LANE CLOSED FOR RESURFACING, REPAIR, AND SURFACE OVERLAY.

The Contractor shall furnish and erect all traffic control signs that are required by the Plans and Specifications and in accordance with the details as shown on Standard Plan Sheets TE700SI, TE702SI, TE710SI, TE730SI, and TE732SI. The cost of furnishing and erecting all signs shall be paid for by the unit shown in the Contract for "Traffic Control". See Section 821, Traffic Control, of the Standard Specifications.

12-05-01 TE