

**KANSAS DEPARTMENT OF TRANSPORTATION
SPECIAL PROVISION TO THE
STANDARD SPECIFICATIONS, EDITION 2015**

SECTION 831

DITCH LINING

Page 800-84, subsection 831.1, delete first two bid items and replace with the following:

Aggregate Ditch Lining (*)(**)	Ton
Aggregate Backslope Ditch Lining (**)	Ton
*Aggregate size	
**Grouted, when specified	

Page 800-84, add the following to subsection 831.3b.:

When designated in the Contract Documents, place concrete grout over the ditch lining to fill all the voids. Apply Type 2 liquid membrane-forming compound as the curing medium. Apply the curing medium immediately after the concrete surface is finished, and before the set takes place. Maintain the cure for 7 days. In cold weather, maintain the concrete temperature above 32°F for the first 4 days of the 7 day cure period.

08-10-15 C&M (LAL)
Oct-15 Letting